



# Minnesota Airport System Pavement Evaluation 2012 Update

St. Cloud Regional Airport (STC)

St. Cloud, Minnesota



### Prepared for:

Office of Aeronautics
Minnesota Department of Transportation
222 East Plato Boulevard
Saint Paul, MN 55107
(800) 657-3922

January 2013

100 Trade Centre Drive, Suite 200 | Champaign, IL 61820 | transportation@ara.com | p 217-356-4500 | f 217-356-3088

#### Final Report

# Mn/DOT Airport Pavement Management System 2012

### St. Cloud Regional Airport

#### **Prepared for:**

Office of Aeronautics Minnesota Department of Transportation 222 East Plato Boulevard Saint Paul, MN 55107 (800) 657-3922

#### **Prepared by:**

Applied Research Associates, Inc. 100 Trade Centre Dr., Suite 200 Champaign, IL 61820 (217) 356-4500

January 2013



#### **Table of Contents**

1.	Introduction	1
	1.1 Project Background	
	1.2 Pavement Management Approach	
	1.3 Scope of Work	
2.	Project Approach	2
	2.1 Update Pavement Inventory	
	2.1.1 Pavement Network Definition	
	2.1.2 Naming Scheme	
	2.2.1 Distress Types	
	2.3 PCI Results	
	2.4 Projected PCI	13
3.	Recommendations	14
	3.1 Near Term Maintenance	14
	3.2 Major Rehabilitation	
	3.3 Federal Guidelines	15
Δn	pendix A - Sample Unit Maps	
	pendix B - Pictures	
	pendix C - PCI Distress Report	
	pendix D - Distress Identification	
•	pendix E - Maintenance and Major Rehabilitation Policies	
	pendix F - Localized Maintenance Recommendations	
Ap	pendix G - Maintenance Repair Guidelines	
Lie	st of Figures	
LIS	of Figures	
Fig	ure 1. Pavement condition life cycle.	2
_	ure 2. Network definition map	
_	ure 3. PCI rating scale and repair levels.	
Fig	ure 4. 2012 PCI map	9
Fig	ure 5. Condition distribution	10
Fig	ure 6. Area-weighted PCI by pavement use	10
Fig	ure 7. Projected PCI by percent area	13
Lie	st of Tables	
LIS	of traples	
Tak	ole 1. Branch definition	5
	ole 2. PCI distress types	
	ole 3. PCI section summary table	
	ole 4. Summary of maintenance work plan	
	ole 5. Recommended 5-year major rehabilitation plan	

#### **Abbreviations and Acronyms**

AAC Asphalt Overlaid with Asphalt

AC Asphalt Concrete

APC PCC Overlaid with Asphalt

APMS Airport Pavement Management System

CAD Computer-aided Drafting
CIP Capital Improvement Plan
FAA Federal Aviation Administration

FOD Foreign Object Debris

GIS Geographic Information System
L&T Longitudinal & Transverse Cracking

LCD Last Construction Date

Mn/DOT Minnesota Department of Transportation Office of Aeronautics

PCC Portland Cement Concrete
PCI Pavement Condition Index
STC St. Cloud Regional Airport



#### 1. Introduction

Since 1995, Federal grant assurances have required that, in order to continue receiving Federal funding, airports implement a pavement maintenance-management program for any pavement constructed or repaired using Federal money. To help individual airports meet this grant assurance and improve the statewide airport system, the Minnesota Department of Transportation (Mn/DOT) Office of Aeronautics contracted with Applied Research Associates, Inc. (ARA) to provide pavement evaluation and management inspections at local airports. This report contains the results of the 2012 pavement inspections at St. Cloud Regional Airport (STC).

Pavement conditions were assessed using the Pavement Condition Index (PCI) procedure, outlined in Federal Aviation Administration (FAA) Advisory Circular (AC) 150/5380 and ASTM D5340 for airfield pavements. The PCI was developed to provide a numerical value indicating overall pavement condition that correlates well with the ratings of experienced engineers. During a PCI survey, visible signs of deterioration within a selected sample unit are recorded and analyzed. The final calculated PCI value is a number from 0 to 100, with 100 representing a pavement in excellent condition. The PCI evaluation makes possible forecasting of future deterioration and allows for accurate projections of maintenance and rehabilitative needs.

The data collected during this project were entered into the MicroPAVER pavement management software program developed by the U.S. Army Corps of Engineers, Construction Engineering Research Laboratory. The capabilities of MicroPAVER were utilized to meet the following project objectives:

- Update and store pavement inventory and condition data.
- Develop models to predict future conditions.
- Develop maintenance and repair recommendations.
- Report the results at the individual and statewide level.

#### 1.1 Project Background

The general aviation airfields throughout Minnesota play a key role in the movement of goods and services with an estimated overall economic impact of \$1.6 billion. Mn/DOT realizes the value in maintaining the paved facilities by implementing and updating an airport pavement management system (APMS). An APMS provides guidance for decisions regarding pavement maintenance and repair policies at an airport and can identify short-, medium-, and long-term rehabilitation needs. Mn/DOT typically has performed PCI inspections at each airport on a 3-year cycle so that the most recent pavement condition data in the APMS reflect the field conditions.

#### 1.2 Pavement Management Approach

The main goal of any pavement management system is to identify pavements that will receive the most benefit from an optimally timed repair. By projecting the rate at which the pavement condition will deteriorate, the optimal time for applying treatments can be determined. Typically, the optimal repair time is the point at which a gradual rate of deterioration begins to increase to a much faster rate, as illustrated in figure 1. It is critical to identify this point in time to avoid higher rehabilitation costs caused by excess deterioration. Figure 1 also shows conceptually how it is cheaper to maintain pavements that are in good to fair condition, rather than wait until the poor condition requires an expensive reconstruction treatment.






Figure 1. Pavement condition life cycle.

Often, the identified needs will cost more than the available budget and will need to be prioritized. The APMS can measure the impact of a limited budget scenario by projecting the future condition of deferred projects. Ultimately, the APMS will provide Mn/DOT and the airport a planning tool that can help identify pavement needs, optimize the selection of projects and treatments over a multi-year period, and understand the consequences of these plans.

#### 1.3 Scope of Work

Beginning in 2008, Mn/DOT retained ARA for 5 years to update the APMS for 103 of Minnesota's publicly owned general aviation airports. Mn/DOT identified approximately 1/3 of the airports to be inspected each year and provided the available construction history information and existing MicroPAVER databases for each airport. ARA coordinated the PCI inspections with each airport. After the field work was completed, ARA updated the MicroPAVER database and computer-aided drafting (CAD) map for each airport. MicroPAVER was then used to develop a maintenance work plan based on current distresses. In addition, a 5-year projection identifying work levels of recommended pavement repair needs was prepared at the state level for the various stakeholders to use as a planning tool. Individual reports, such as this one, were prepared for each airport documenting the results of the pavement inspections. A statewide analysis report was prepared based on that inspection year's airports. The airport maps were linked to the MicroPAVER database to allow for geographic information system (GIS) viewing of data. Also, training was provided on the use of the MicroPAVER software and PCI procedure.

#### 2. Project Approach

#### 2.1 Update Pavement Inventory

The pavement inventory at STC represents the airfield pavements that are intended for aviation-related traffic. The main objective in updating the pavement inventory was to determine the year of the construction (or most recent overlay), the limits of the project, and the surface type for each pavement area based on construction history. When available, Mn/DOT provided this information for the pavement-related projects for areas not already included in previous inspections. ARA then used this information to update the pavement section definitions on the CAD map and MicroPAVER database based on project limits, surface type, layer properties, traffic patterns, and overall condition.



#### 2.1.1 Pavement Network Definition

The construction history information was used to divide the pavement network at STC into management units—branches, sections, and sample units. A branch is a single entity that serves a distinct function. For example, a runway is considered a branch because it serves a single function (allowing aircraft to take off and land). On an airfield, a branch typically represents an entire runway, taxiway, or apron.

Because of the disparity of characteristics that can occur throughout a branch, it is further subdivided into units called sections. A section is a portion of the pavement that has uniform construction history, pavement structure, traffic patterns, and condition throughout its entire length or area. Sections are used as a management unit for the selection of potential maintenance and rehabilitation projects. The guideline used in deciding where section breaks are located is to think of the section as the "repair unit"—a portion of the pavement that will be managed independently and evaluated separately for pavement maintenance and rehabilitation.

Pavement sections are further subdivided into sample units for inspection purposes. The typical sample unit size for asphalt concrete (AC) pavements is 5,000 square feet  $\pm 2,000$  square feet and 20 slabs  $\pm 8$  slabs for portland cement concrete (PCC) pavements. A statistical based sampling rate was used to determine the number of sample units to inspect for each section. The inspected sample units were representative of the overall condition within a section and were used to extrapolate the condition as a whole.

#### 2.1.2 Naming Scheme

For the pavement management system to work efficiently, some unique identifiers were added to the database. The branch names assigned were designed to assist in identification of the pavement area. The first characters are used to identify the pavement use—apron, runway, taxiway, or taxilane (pavement in and around hangar areas). The next character is a number or letter used to further identify the pavement branch (such as RY1331 for Runway 13/31 or CTA1 for connector Taxiway A1). The sections for each branch are assigned a number starting with 001, 002, and so on. Table 1 presents the branches defined for STC and their area. For those airports with taxiway guidance signs, the branch ID may or may not match up with the signage in the field; however, the branch name will correspond.

Figure 2 presents the network definition for STC and represents the pavements included in the APMS. Some privately built/maintained pavements and "driveways" leading into hangars may not be included here because they are considered outside the scope of work.




Figure 2. Network Definition at St. Cloud Regional Airport (STC).



Table 1. Branch definition.

Branch Id	Name	Number of Sections	Area (SF)
APA	Apron A	1	150,000
APB	Apron B	2	268,750
CTA1	Connecting Taxiway A1	1	20,400
CTA2	Connecting Taxiway A2	1	23,100
CTA3	Connecting Taxiway A3	1	23,100
CTA3X	Connecting Taxiway A3 Extended	2	14,970
CTA4	Connecting Taxiway A4	1	20,400
CTC	Connecting Taxiway C	1	19,100
CTD1	Connecting Taxiway D	3	32,865
CTD2	Connecting Taxiway D2	1	204,363
CTE	Connecting Taxiway E	1	40,600
PPTC	Part Parallel Taxiway C	1	64,950
PPTE	Part Parallel Taxiway E	2	57,820
PTA	Parallel Taxiway A	1	415,500
PTD	Parallel Taxiway D	5	147,870
RP1	Run-Up Pad 1	1	22,800
RP2	Run-Up Pad 2	1	22,800
RY1331	Runway 13-31	3	1,050,000
RY523	Runway 5-23	5	238,400
TLA	Taxilane A	5	305,890
		Airport Total	3,143,678

#### 2.2 Pavement Evaluation

The pavement surfaces at STC were visually inspected on June 22 and 23, 2012, using the PCI procedure. During a PCI inspection, inspectors walk over the surface of the pavement and identify visible signs of distress within a sample unit. Appendix A presents the scalable map used during the inspection to locate the inspected sample units. Each distress type is identified, then classified as low, medium, or high severity, and recorded on field sheets. In general, the higher the severity, the higher the foreign object damage (FOD) potential. The quantity, or extent, is measured for each distress/severity combination.

After collecting and summarizing the distress type, severity, and quantity for each of the inspected sample units, the distress data were entered into the MicroPAVER database and a PCI was calculated. The PCI procedure uses established deduct curves to determine the actual number of points to deduct for each distress type/severity combination, depending on the density of the distress. The inspected sample unit PCI's were then averaged to determine an overall PCI for that section.

The PCI value provides a general sense as to the level of rehabilitation that will be needed to repair a given pavement. In general terms, maintenance activities such as crack sealing and patching often provide benefit when the PCI > 60. However, as the pavement continues to deteriorate, more complex and expensive treatments will be necessary. Pavements with a PCI between 40 and 60 are good candidates for a variety of major repairs ranging from overlays to reconstruction. Once the PCI drops below 40, reconstruction is typically the only viable alternative. Figure 3 presents the PCI inputs, rating scale, and the corresponding general work repair levels.



### **Pavement Condition Index (PCI)**




Figure 3. PCI rating scale and repair levels.

#### 2.2.1 Distress Types

To better understand the cause of pavement deterioration, it is necessary to look at the distress types associated with each PCI. Each distress type has been classified into three groups based on cause—load, climate/durability, or other. Load-related distresses such as alligator cracking in asphalt pavements, or corner breaks in PCC pavements, indicate that the structural integrity of the pavement has been compromised. Climate-related distresses indicate that the pavement has aged due to seasonal environmental effects. Distresses that cannot be attributed solely to either load or climate, are classified as other. Table 2 presents the asphalt and PCC distress types in the PCI procedure, their classification, and identifies which distresses were located at STC during the pavement inspection.



Table 2. PCI distress types.

Asphalt Distresses	Cause	PCC Distresses	Cause
	Classification		Classification
Alligator cracking	Load	Blowup	Climate
Bleeding	Other	Corner break	Load
Block cracking	Climate	Linear cracking	Load
Corrugation	Other	Durability cracking	Climate
Depression	Other	Joint seal damage	Climate
Jet blast	Other	Small patch	Other
Joint reflection cracking	Climate	Large patch	Other
L&T cracking	Climate	Popouts	Other
Oil spillage	Other	Pumping	Other
Patching	Other	Scaling/crazing	Other
Polished aggregate	Other	Faulting	Other
Raveling	Climate	Shattered slab	Load
Rutting	Load	Shrinkage cracking	Other
Shoving	Other	Joint spalling	Other
Slippage cracking	Other	Corner spalling	Other
Swelling	Other	Alkali Silica Reaction	Climate
Weathering	Climate		

Indicates distresses found at STC

#### 2.3 PCI Results

The results of the 2012 PCI inspection are presented in figure 4. The overall area-weighted PCI for STC is 81. When summarizing PCI values, an area-weighted calculation is used instead of a straight mathematical average because the area-weighted calculations eliminate the skewing of the PCI due to the disparity of the section sizes.

Figures 5 and 6 present the overall PCI for STC by area distribution and pavement use, respectively. Table 3 presents the PCI summary for each section at STC, including the drop in PCI per year. Generally, pavement sections will deteriorate between 1 and 3 PCI points per year. Sections deteriorating at higher rates may need maintenance above the normal application rates and should be closely monitored in case major repairs become necessary.

Appendix C contains the detailed inspection report with sample unit data produced from MicroPAVER. Appendix D describes the distress types most commonly identified during the PCI inspections of Minnesota airports.



This page intentionally left blank.




Figure 4. 2012 Pavement Condition Index Rating at St. Cloud Regional Airport (STC).






Figure 5. Condition distribution.




Figure 6. Area-weighted PCI by pavement use.



Table 3. PCI section summary table.

		Surface	Section	2	2009	2012	Drop in	% Dedu	ıct due to	
Branch ID	Section ID Surface Section LCD <sup>2</sup> PCI		PCI PCI/Yr <sup>3</sup>		Load <sup>4</sup>	Climate <sup>5</sup>	Distress types			
APA	1	PCC	150,000	2001*	100	100	0.0	0	0	-
										Alligator cracking, block cracking, Longitudinal & transverse (L&T) cracking,
APB	1**	AC	225,000	1985	55	65	1.3	16	81	oil spillage, raveling
APB	2**	AC	43,750	1985	47	65	1.3	31	69	Alligator cracking, L&T cracking
CTA1	1	PCC	20,400	2001	100	97	0.3	0	0	Joint spalling
CTA2	1	PCC	23,100	2001	100	92	0.7	0	0	Faulting
CTA3	1	PCC	23,100	2001	100	100	0.0	0	0	-
CTA3X	1	PCC	10,700	2001	90	89	1.0	0	66	Joint seal damage, shrinkage cracking
CTA3X	2	AC	4,270	2001	82	72	2.5	35	53	Depression, L&T cracking, weathering
CTA4	1	PCC	20,400	2001	100	100	0.0	0	0	-
CTC	1	PCC	19,100	2001	98	100	0.0	0	0	-
CTD1	1	AC	21,680	1985	58	54	1.7	19	81	Alligator cracking, depression, L&T cracking, patching, raveling,
CTD1	2	AC	7,435	1985	63	61	1.4	22	78	Alligator cracking, L&T cracking, raveling
CTD1	3	AC	3,750	2001	92	86	1.3	0	100	L&T cracking, raveling
CTD2	1	AC	204,363	1985	51	53	1.7	24	76	Alligator cracking, L&T cracking, patching, raveling
CTE	1	PCC	40,600	2001	100	100	0.0	0	0	-
PPTC	1	PCC	64,950	2001	98	98	0.2	0	58	Joint seal damage, corner spalling
PPTE	1**	AC	55,000	1985	52	70	1.1	0	100	L&T cracking
PPTE	2	AAC	2,820	2001	n/a	95	0.5	0	100	L&T cracking
PTA	1	PCC	415,500	2001	100	100	0.0	0	0	Corner spalling
PTD	1	AC	48,000	1985	55	60	1.5	27	73	Alligator cracking, depression, L&T cracking, patching, raveling, weathering
PTD	2	AAC	2,820	2001	n/a	88	1.1	0	100	L&T cracking
PTD	3	PCC	51,000	2001	100	99	0.1	0	0	Joint spalling
PTD	4	AC	6,050	2001	82	81	1.7	0	100	L&T cracking
PTD	5	AC	40,000	1985	53	54	1.7	17	83	Alligator cracking, L&T cracking, patching, raveling
RP1	1	PCC	22,800	2001	100	100	0.0	0	0	-



Duamah ID	s :: 15	Surface type <sup>1</sup>	Section area (SF)	LCD <sup>2</sup>	2009 PCI	2012 PCI	Drop in PCI/Yr <sup>3</sup>	% Deduct due to		Distusse to make
Branch ID	Section ID							Load <sup>4</sup>	Climate <sup>5</sup>	Distress types
RP2	1	PCC	22,800	2001	100	100	0.0	0	0	-
RY1331	1	PCC	350,000	2001	97	98	0.2	0	0	Joint spalling, corner spalling
										Joint seal damage, small patch, corner
RY1331	2	PCC	350,000	2001	96	97	0.3	0	74	spalling
RY1331	3	PCC	350,000	2001	99	99	0.1	0	0	Corner spalling
										Alligator cracking, block cracking,
RY523	1	AC	52,500	1985	28	21	2.9	36	64	depression, L&T cracking, raveling
RY523	2**	AC	8,400	2001	85	81	1.7	0	100	L&T cracking
RY523	3	PCC	70,000	2001	99	98	0.2	0	65	Joint seal damage, corner spalling
RY523	4**	AC	17,500	2001	61	62	3.5	0	91	L&T cracking, raveling, shoving
										Alligator cracking, block cracking,
RY523	5	AC	90,000	1985	27	16	3.1	34	66	depression, L&T cracking, raveling
										Alligator cracking, block cracking,
			44= 000	40=04			4.0			depression, L&T cracking, raveling, rutting,
TLA	1	AAC	117,000	1970*	24	20	1.9	35	65	weathering
			- 040	10004						Alligator cracking, depression, L&T
TLA	2	AC	7,840	1990*	53	42	2.6	39	50	cracking, weathering
										Alligator cracking, block cracking,
A			400 550	4005*	7.0	40	2.4	40	40	depression, L&T cracking, raveling,
TLA	3	AAC	102,550	1995*	76	48	3.1	43	48	swelling, weathering
	_									Alligator cracking, block cracking, L&T
TLA	4	AAC	37,750	1995*	71	27	4.3	24	76	cracking, raveling, weathering
	= de de									Alligator cracking, L&T cracking, raveling,
TLA	5**	AAC	40,750	1995*	75	60	2.4	12	88	weathering

<sup>&</sup>lt;sup>1</sup>AC = asphalt cement; AAC = asphalt overlaid with asphalt; PCC = portland cement concrete; APC = PCC overlaid with asphalt

<sup>&</sup>lt;sup>2</sup>LCD = last construction date (original construction, last overlay, or reconstruction [whichever is most recent])

 $<sup>^{3}</sup>$ Drop in PCI/Yr = (100 – PCI)/age where age = 2012 - LCD

<sup>&</sup>lt;sup>4</sup>Percent of deduct due to load = Percentage of PCI points subtracted from 100 for load related distresses

<sup>&</sup>lt;sup>5</sup>Percent of deduct due to climate = Percentage of PCI points subtracted from 100 for climate/durability related distresses

<sup>\*</sup> estimated LCD

<sup>\*\*</sup> These sections have received maintenance (slurry seal) since 2009 inspection



#### 2.4 Projected PCI

After the 2012 distress data was entered into MicroPAVER and the PCI determined, a modeling approach was used to predict future PCI levels based on historical PCI data from Mn/DOT's airports. Pavements were grouped together in performance families based on similar construction, traffic, pavement use, and other factors affecting pavement performance. These performance models predict future PCI, not future distresses.

Figure 7 shows the projected PCI at STC by percent area for the next 5 years assuming no major repairs (overlays, reconstruction, etc.) are performed during that period. It shows how quickly a pavement network can deteriorate when no capital improvements are made.




Figure 7. Projected PCI by percent area.



#### 3. Recommendations

A 5-year maintenance and rehabilitation program was developed for STC based on the 2012 pavement inspections and the anticipated PCI deterioration for this period. The recommendations are divided into two categories—near term maintenance and major rehabilitation. The near term maintenance is intended to address annual maintenance needs such as crack sealing and localized patching. The major rehabilitations are applied globally and are capable of returning the pavement to a nearly distress free-state. Cost for both categories are based on industry averages and may have to be adjusted to account for local costs.

The last portion of the report covers the FAA Grant Assurance Number 11 and the steps the airport must take to remain in compliance with this program.

#### 3.1 Near Term Maintenance

Near term maintenance is considered activities such as crack sealing, patching, and surface treatments that help to slow down the rate that a pavement is deteriorating. Localized maintenance policies and unit costs were developed with Mn/DOT for both asphalt and PCC surfaces; each policy presents the recommended maintenance treatment for each distress/severity combination and are presented in appendix E.

Table 4 presents the summarized maintenance work quantities and estimated cost to apply this near term maintenance plan at STC. The repair quantities are based on extrapolated distress quantities from the 2012 PCI inspection. National averages of unit costs are used to estimate total costs for each treatment type; adjustments of local unit costs rates may be necessary for each airport to more accurately determine the maintenance budgetary needs.

Treatment	<b>Estimated Repair Quantity</b>	<b>Unit Costs</b>	<b>Estimated Costs</b>
Crack Sealing - Asphalt	25,892 ft	\$1.12/ft	\$28,999
Joint Seal	6,591 ft	\$1.69/ft	\$11,138
Patching - Asphalt Deep	37,225 ft <sup>2</sup>	\$10.46/ft <sup>2</sup>	\$389,376
Patching - Asphalt Shallow	8,306 ft <sup>2</sup>	\$7.02/ft <sup>2</sup>	\$58,312
Patching – PCC Partial Depth	90 ft <sup>2</sup>	\$9.45/ft <sup>2</sup>	\$847
		Total	\$569,487

Table 4. Summary of maintenance work plan.

Detailed results are reported by section and by treatment type in appendix F. The section format summarizes the maintenance that could be done for each pavement section by type of repair, and estimated quantity of repair. Likewise, the treatment format summarizes the quantity for each repair type across the entire airport.

When using this plan, it is recommended that the entire section be viewed to determine whether the identified distress types are so advanced in density and severity that maintenance efforts will no longer be cost-effective. Maintenance treatments are most cost-effective when applied to pavements that are generally in good condition. It is also important to understand that the maintenance plan is based on the distress types, severities, and quantities found during the 2012 PCI survey. As field conditions change, the maintenance plan will become less accurate. Therefore, it will be most useful if



implemented by the end of 2013. Applying maintenance treatments should be an annual event at the airport, and this maintenance plan can serve as a baseline for that work. Guidelines for performing crack sealing and patching techniques are provided in appendix G.

#### 3.2 Major Rehabilitation

In addition to the annual maintenance activities such as crack sealing and patching, some pavements may require more substantial rehabilitation. As a planning aid to the airport, Mn/DOT, and FAA, table 5 provides a summary from MicroPAVER of the predicted 5-year pavement rehabilitation needs at STC. Although the predicted rehabilitation timeline identifies specific sections and the general timing for the repair, more in-depth project-level studies will be needed to determine exactly how to fix each pavement. Routine maintenance should also be programmed annually throughout the airport, but these efforts should be coordinated with the following rehabilitation recommendations.

The pavement sections identified for major rehabilitation in this report are predicted to reach a condition level where either overlays or reconstruction should be considered. Note that this analysis is based on an unlimited budget, and these recommendations will need to be adjusted to account for economic and operational constraints. Additionally, identifying projects for work does not guarantee that Federal or State funding will be available to complete the work in the year shown. The airport and Mn/DOT should view these recommendations as viable projects when preparing future Capital Improvement Plans (CIP).

Branch ID Section ID Year **Estimated Cost** CTD1 2013 \$102,764 1 1 \$1,002,268 CTD2 2013 PTD 1 2013 \$181,618 PTD 5 2013 \$189,602 RY523 1 2013 \$399.000 RY523 5 2013 \$684,000 TLA 2013 \$889,200 1 2 TLA 2013 \$48,947 TLA 3 2013 \$576,397 TLA 4 2013 \$286,900 CTD1 2 2014 \$28,178 RY523 4 2015 \$66,323 5-year Airport Total \$4,455,197

Table 5. Recommended 5-year major rehabilitation plan.

#### 3.3 Federal Guidelines

In 1995, Congress mandated that the FAA require, as a condition of grant funding, that airports be prepared to present documentation of a maintenance management program on pavement that has been constructed, reconstructed, or repaired with Federal assistance.

The FAA has defined an acceptable maintenance management program, and this report fulfills many requirements of such a program, including documenting:



- Locations of all runways, taxiways, and aprons.
- Dimensions of the pavement system.
- Types of pavement.
- Year of construction or most recent major rehabilitation.

However, **the airport owner must be an active participant**, specifically by implementing the following actions:

- Annotate pavement areas that have been constructed, reconstructed, or repaired with Federal financial assistance.
- Conduct a "drive-by" inspection at least monthly to detect changes in pavement condition.
- Keep complete records of maintenance activities. Record the date of each "drive-by" inspection and any maintenance performed as a result. Records must be maintained on file for a minimum of 5 years.
- Document detailed inspection information with a history of recorded pavement deterioration by PCI survey (e.g., this report).

An example of a form that can be completed during "drive-by" inspections is provided in appendix G.



This page intentionally left blank.

# Appendix A Sample Unit Maps




Figure A.1. Sheet Index Map at St. Cloud Regional Airport (STC).




Figure A.2. Sample unit layout for runway and taxiways at St. Cloud Regional Airport (STC).




Figure A.3. Sample unit layout for runway and taxiways at St. Cloud Regional Airport (STC).




Figure A.4. Sample unit layout for runway and taxiways at St. Cloud Regional Airport (STC).

## Appendix B Pictures



STC APA 001 (PCI = 100)



STC APB 001 (PCI = 65)



STC APB 002 (PCI = 65)



STC CTA1 001 (PCI = 97)



STC CTA2 001 (PCI = 92)



STC CTA3 001 (PCI = 100)



STC CTA3X 001 (PCI = 89)



STC CTA3X 002 (PCI = 72)



STC CTA4 001 (PCI = 100)



STC CTC 001 (PCI = 100)



STC CTD1 001 (PCI = 54)



STC CTD1 002 (PCI = 61)



STC CTD1 003 (PCI = 86)



STC CTD2 001 (PCI = 53)



STC CTE 001 (PCI = 100)



STC PPTC 001 (PCI = 98)



STC PPTE 001 (PCI = 70)



STC PPTE 002 (PCI = 95)



STC PTA 001 (PCI = 100)



STC PTD 001 (PCI = 60)



STC PTD 002 (PCI = 88)



STC PTD 003 (PCI = 99)



STC PTD 004 (PCI = 81)



STC PTD 005 (PCI = 54)



STC RP1 001 (PCI = 100)



STC RP2 001 (PCI = 100)



STC RY523 001 (PCI = 21)



STC RY523 002 (PCI = 81)



STC RY523 003 chipping along joint, (PCI = 98)



STC RY523 003 (PCI = 98)



STC RY523 003 (PCI = 98)



STC RY523 004 (PCI = 62)



STC RY523 005 (PCI = 16)



STC RY523 005 (PCI = 16)



STC RY1331 001 Corner spall, (PCI = 98)



STC RY1331 001 (PCI = 98)



STC RY1331 002 (PCI = 97)



STC TLA 001 Rutting, (PCI = 20)



STC TLA 001 (PCI = 20)



STC TLA 001 (PCI = 20)



STC TLA 002 (PCI = 42)



STC TLA 003 Depression, (PCI = 48)



STC TLA 003 (PCI = 48)



STC TLA 003 (PCI = 48)



STC TLA 004 (PCI = 27)



STC TLA 005 (PCI = 60)

### Appendix C

# **PCI Distress Report**

MN103-2012 CH

Sample Comments: <NO DISTRESSES>

Network: STC	Name:	ST. CLOUD				
Branch: APA	Name:	APRON A		Use: APRON	Area: 150	0,000.00SqFt
Section: 001 Surface: PCC	of 1 Fami	From: 100 ly: MN2012 PCC		To: 305	Zone: E	Last Const.: 09/30/2002 Category: 2 Rank: P
Area: 150,000.005	SqFt I	Length: 600.	00Ft Width	: 250.00Ft		
Slabs: 375 Shoulder: Str	Slab Widtl reet Type:	1: 20.00Ft Grade: 0.00	Slab Length: Lanes: 0	20.00Ft	Joint Length:	14,150.00Ft
Section Comments: esti	imated LCD					
Inspection Comments: Sample Number: Sample Comments: <no distressi<="" th=""><th></th><th>ype: R</th><th>Area:</th><th>20.00Slabs</th><th>PCI = 100</th><th></th></no>		ype: R	Area:	20.00Slabs	PCI = 100	
Sample Number: Sample Comments: <no distressi<="" td=""><td></td><td>ype: R</td><td>Area:</td><td>20.00Slabs</td><td>PCI = 100</td><td></td></no>		ype: R	Area:	20.00Slabs	PCI = 100	
Sample Number: Sample Comments: <no distressi<="" td=""><td></td><td>ype: R</td><td>Area:</td><td>20.00Slabs</td><td>PCI = 100</td><td></td></no>		ype: R	Area:	20.00Slabs	PCI = 100	
Sample Number:	303 T	ype: R	Area:	20.00Slabs	PCI = 100	

#### MN103-2012 CH

Report Generated Date: December 20, 2012						
Network: STC Name: ST. CLOUD						
Branch: APB Name: APRON B			Use: APRO	ON	Area: 268	3,750.01SqFt
Section:         001         of         2         From:         100           Surface:         AC         Family:         MN2012 Asphalt Apro           Area:         225,000.01SqFt         Length:         900.00Ft	ons	Wi	To: 508		Zone: E	Last Const.: 09/30/1985 Category: 2 Rank: S
Shoulder: Street Type: Grade: 0.00	Lanes:	0				
Section Comments: 2011 slurry seal						
Last Insp. Date: 06/23/2012 Total Samples: 45 Sur Conditions: PCI: 65 Inspection Comments:	veyed: {	8				
Sample Number: 108 Type: R Sample Comments:	Area:		5,000.00SqFt		PCI = 60	
43 BLOCK CRACKING		L	4,200.00 S	SqFt	Comments:	
48 LONGITUDINAL/TRANSVERSE CRACKING		L	80.00 F	7t	Comments:	
52 RAVELING		L	12.00 S	SqFt	Comments:	
Sample Number: 203 Type: R Sample Comments:	Area:		5,000.00SqFt		PCI = 65	
48 LONGITUDINAL/TRANSVERSE CRACKING		L	807.00 F	7t	Comments:	
41 ALLIGATOR CRACKING		L	4.00 S	SqFt	Comments:	
Sample Number: 302 Type: R Sample Comments:	Area:		5,000.00SqFt		PCI = 72	
48 LONGITUDINAL/TRANSVERSE CRACKING		L	692.00 F	?t	Comments:	
Sample Number: 304 Type: R Sample Comments:	Area:		5,000.00SqFt		PCI = 66	
48 LONGITUDINAL/TRANSVERSE CRACKING		L	771.00 F	7t	Comments:	
41 ALLIGATOR CRACKING		L	12.00 S	SqFt	Comments:	
Sample Number: 306 Type: R Sample Comments:	Area:		5,000.00SqFt		PCI = 61	
48 LONGITUDINAL/TRANSVERSE CRACKING		L	898.00 F	7t	Comments:	
49 OIL SPILLAGE		N	15.00 S		Comments:	
41 ALLIGATOR CRACKING		L	40.00 S	SqFt	Comments:	
Sample Number: 308 Type: R Sample Comments:	Area:		5,000.00SqFt		PCI = 66	
48 LONGITUDINAL/TRANSVERSE CRACKING		L	745.00 F	7t	Comments:	
48 LONGITUDINAL/TRANSVERSE CRACKING		M	53.00 F		Comments:	
Sample Number: 401 Type: R Sample Comments:	Area:		5,000.00SqFt		PCI = 66	
48 LONGITUDINAL/TRANSVERSE CRACKING		L	735.00 F	7t	Comments:	
41 ALLIGATOR CRACKING		L	8.00 S		Comments:	
Sample Number: 405 Type: R Sample Comments:	Area:		5,000.00SqFt		PCI = 61	
48 LONGITUDINAL/TRANSVERSE CRACKING		L	526.00 F	īt	Comments:	
48 LONGITUDINAL/TRANSVERSE CRACKING		M	9.00 F		Comments:	
41 ALLIGATOR CRACKING		L	33.00 S		Comments:	
43 BLOCK CRACKING		L	208.00 S	SqFt	Comments:	

#### MN103-2012 CH

Report Generated Date: December 20, 2012

48 LONGITUDINAL/TRANSVERSE CRACKING

Network: STC Name: ST. CLOUD						
Branch: APB Name: APRON B			Use: AP	RON	Area: 268	3,750.01SqFt
Section: 002 of 2 From: 109			To: 5	10		Last Const.: 09/30/1985
Surface: AC Family: MN2012 Asphalt Apr	rons				Zone: E	Category: 2 Rank: S
Area: 43,750.00SqFt Length: 175.00Ft		Width	250.00	Ft		
Shoulder: Street Type: Grade: 0.00	Lanes:	0				
Section Comments: 2011 slurry seal						
Last Insp. Date: 06/23/2012 Total Samples: 10 Sur	rveyed: 3	_				
Conditions: PCI: 65	•					
Inspection Comments:						
Sample Number: 209 Type: R Sample Comments:	Area:	5,	000.00SqFt		PCI = 71	
48 LONGITUDINAL/TRANSVERSE CRACKING		L	524.00	Ft	Comments:	
48 LONGITUDINAL/TRANSVERSE CRACKING		M	56.00	Ft	Comments:	
Sample Number: 310 Type: R Sample Comments:	Area:	3,	750.00SqFt		PCI = 60	
48 LONGITUDINAL/TRANSVERSE CRACKING		L	595.00	Ft	Comments:	
48 LONGITUDINAL/TRANSVERSE CRACKING		M	37.00	Ft	Comments:	
41 ALLIGATOR CRACKING		M	16.00	SqFt	Comments:	
Sample Number: 409 Type: R Sample Comments:	Area:	5,	000.00SqFt		PCI = 62	
Sample Comments: 41 ALLIGATOR CRACKING		M	18.00	SaFt	Comments:	
48 LONGITUDINAL/TRANSVERSE CRACKING		L	725.00	-	Comments:	
10 Long I ob Live J in the Charles of the Charles			725.00		COMMICTION.	

26.00 Ft

Comments:

MN103-2012 CH

Report Generated Date: December 20, 2012

Network:	STC	Name: ST. CL	OUD				
Branch:	CTA1	Name: CONNI	ECTING TAXIWA	Y A1	Use: TAXIWAY	Area: 2	20,400.00SqFt
Section: Surface:	001 PCC	of 1 Fr Family: MN	rom: 100 2012 PCC		To: 102	Zone: E	Last Const.: 09/29/2001 Category: 2 Rank: P
Area: Slabs: 68 Shoulder:		Length: Slab Width:	295.00Ft 15.00Ft rade: 0.00	Width: Slab Length: Lanes: 0	60.00Ft 20.00Ft	Joint Length:	1,710.00Ft
Section Con		Type. Gi	ade: 0.00	Laics. 0			

Last Insp. Date: 06/22/2012 Total Samples: 3 Surveyed: 1

Conditions: PCI: 97 Inspection Comments:

Sample Number: 101 Type: R Area: 20.00Slabs PCI = 97

Sample Comments:

74 JOINT SPALLING L 2.00 Slabs Comments:

MN103-2012 CH

Report Generated Date: December 20, 2012

Network:	STC	Name: ST	Г. CLOUD				
Branch:	CTA2	Name: Co	onnecting Taxiway A2		Use: TAXIWAY	Area: 2	3,100.00SqFt
Section:	001	of 1	From: 100		To: 102		Last Const.: 09/30/2001
Surface:	PCC	Family:	MN2012 PCC			Zone: E	Category: 2 Rank: S
Area:	23,100.00SqFt	Leng	gth: 295.00Ft	Width:	60.00Ft		
Slabs: 77	;	Slab Width:	15.00Ft	Slab Length:	20.00Ft	Joint Length:	1,710.00Ft
Shoulder:	Street	Гуре:	Grade: 0.00	Lanes: 0			
Section Con	nments:						

Last Insp. Date: 06/22/2012 Total Samples: 3 Surveyed: 1

Conditions: PCI: 92 Inspection Comments:

Sample Number: 100 Type: R Area: 20.00Slabs PCI = 92

Sample Comments:

71 FAULTING L 2.00 Slabs Comments:

MN103-2012 CH

Report Generated Date: December 20, 2012

Type: R

ea:	23,100.00SqFt
ne: E	Last Const.: 09/30/2001 Category: 2 Rank: P
t Lengtl	h: 1,710.00Ft
t -	Lengt

Area:

20.00Slabs

PCI = 100

Sample Number:

Sample Comments:
<NO DISTRESSES>

101

MN103-2012 CH

Report Generated Date: December 20, 2012

Network:	STC	Name: ST	C. CLOUD				
Branch:	CTA3X	Name: Co	onnecting Taxiway A3 ex	i	Use: TAXIWAY	Area: 1	4,970.00SqFt
Section: Surface:	001 PCC	of 2 Family:	From: 103 MN2012 PCC		To: 104	Zone: E	Last Const.: 09/30/2001 Category: 2 Rank: P
Area:	10,700.00SqFt	Leng		Width:	60.00Ft		2 1
Slabs: 36		Slab Width:	15.00Ft	Slab Length:	20.00Ft	Joint Length:	960.00Ft
Shoulder:	Street 7	Гуре:	Grade: 0.00	Lanes: 0			
Section Cor	nments:						

Last Insp. Date: 06/23/2012 Total Samples: 2 Surveyed: 1

Conditions: PCI: 89 Inspection Comments:

 $Sample \ Number: \quad 104 \qquad \qquad Type: \ R \qquad \qquad Area: \qquad \quad 20.00Slabs \qquad \qquad PCI = 89$ 

Sample Comments:

73 SHRINKAGE CRACKING N 5.00 Slabs Comments: 65 JOINT SEAL DAMAGE M 20.00 Slabs Comments:

#### MN103-2012 CH

Report Generated Date: December 20, 2012

Network:	STC	Name: ST. CLOUD			
Branch:	CTA3X	Name: Connecting Taxiway A3 ext	Use: TAXIWAY	Area:	14,970.00SqFt
Section: Surface:	002 AC	of 2 From: 105 Family: MN2012 Asphalt Taxiways	To: 105	Zone: E	Last Const.: 09/30/2001 Category: 2 Rank: P
Area: Shoulder:	4,270.00SqFt Street Ty	Length: 60.00Ft Width: vpe: Grade: 0.00 Lanes: 0	60.00Ft		

Section Comments:

Last Insp. Date: 06/23/2012 Total Samples: 1 Surveyed: 1

Conditions: PCI: 72 Inspection Comments:

Sample Number: 105 Type: R Sample Comments:	Area:	4,270.00SqFt		PCI = 72
48 LONGITUDINAL/TRANSVERSE CRACKING	I	87.00	Ft	Comments:
48 LONGITUDINAL/TRANSVERSE CRACKING	M	20.00	Ft	Comments:
45 DEPRESSION	I	25.00	SqFt	Comments:
41 ALLIGATOR CRACKING	I	15.00	SqFt	Comments:
57 WEATHERING	I	600.00	SqFt	Comments:

MN103-2012 CH

Report Generated Date: December 20, 2012

Type: R

Network:	STC	Name: S	ST. CLOUD				
Branch:	CTA4	Name: 0	Connecting Taxiway A4		Use: TAXIWAY	Area: 20	0,400.00SqFt
Section: Surface:	001 PCC	of 1 Family	From: 100 : MN2012 PCC		To: 102	Zone: E	Last Const.: 09/30/2001 Category: 2 Rank: P
Area:	20,400.00SqF	Lei	ngth: 295.00Ft	Width:	60.00Ft		
Slabs: 68		Slab Width:	15.00Ft	Slab Length:	20.00Ft	Joint Length:	1,710.00Ft
Shoulder:	Street	Type:	Grade: 0.00	Lanes: 0			
Section Cor	nments:						
Last Insa	Data: 06/22/	2012 Total Sa	mples: 20 Suc	wayada 1			
-	s: PCI: 100	2012 10tai Sa	mples: 20 Sur	rveyed: 1			
Inspection (							

20.00Slabs

Area:

PCI = 100

Sample Number:

Sample Comments:
<NO DISTRESSES>

100

MN103-2012 CH

Report Generated Date: December 20, 2012

Type: R

Network:	STC	Name: S	T. CLOUD				
Branch:	CTC	Name: C	CONNECTING TAXIWA	Y C	Use: TAXIWAY	Area: 1	19,100.00SqFt
Section: Surface:	001 PCC	of 1 Family:	From: 100 MN2012 PCC		To: 102	Zone: E	Last Const.: 09/30/2001 Category: 2 Rank: S
Area:	19,100.00SqFt	Len	gth: 310.00Ft	Width:	60.00Ft		
Slabs: 64 Shoulder:	Street	Slab Width: Type:	15.00Ft Grade: 0.00	Slab Length: Lanes: 0	20.00Ft	Joint Length:	1,800.00Ft
Section Cor	nments:						

Area:

20.00Slabs

PCI = 100

Sample Number:

Sample Comments:
<NO DISTRESSES>

100

#### MN103-2012 CH

41 ALLIGATOR CRACKING

48 LONGITUDINAL/TRANSVERSE CRACKING

48 LONGITUDINAL/TRANSVERSE CRACKING

50 PATCHING

50 PATCHING

52 RAVELING

Network: STC	Name:	ST. CLOUD				
Branch: CTD1	Name:	CONNECTING TAX	IWAY D	Use: TAXIWAY	Area:	32,865.00SqFt
	of 3	From: 200		To: 206		Last Const.: 09/30/1985
Surface: AC	Famil	ly: MN2012 Asphalt	Taxiways		Zone: E	Category: 2 Rank: S
Area: 21,680.00SqFt	L	ength: 338.00	)Ft Wi	dth: 60.00Ft		
Shoulder: Street Typ		Grade: 0.00	Lanes: 0			
	•					
Section Comments:						
Conditions: PCI : 54		r	Surveyed: 2			
Conditions: PCI : 54 Inspection Comments:  Sample Number: 201		/pe: R	Area:	3,000.00SqFt	PCI = 54	
Conditions: PCI: 54 Inspection Comments:  Sample Number: 201 Sample Comments:			Area:	_		:
Conditions: PCI: 54 Inspection Comments:  Sample Number: 201 Sample Comments: 50 PATCHING			Area:	62.00 SqFt	Comments	
Sample Comments: 50 PATCHING 50 PATCHING			Area: L M	62.00 SqFt 6.00 SqFt	Comments Comments	:
Conditions: PCI: 54 Inspection Comments:  Sample Number: 201 Sample Comments: 50 PATCHING 50 PATCHING	Ту	/pe: R	Area: L M L	62.00 SqFt	Comments Comments	: :
Conditions: PCI: 54 Inspection Comments:  Sample Number: 201 Sample Comments: 50 PATCHING 50 PATCHING 45 DEPRESSION	Ty TRANSVI	/pe: R ERSE CRACKING	Area: L M L L	62.00 SqFt 6.00 SqFt 4.00 SqFt	Comments Comments	: : :
Conditions: PCI:54 Inspection Comments:  Sample Number: 201 Sample Comments: 50 PATCHING 50 PATCHING 45 DEPRESSION 48 LONGITUDINAL/T	Ty TRANSVI	/pe: R ERSE CRACKING	Area: L M L L	62.00 SqFt 6.00 SqFt 4.00 SqFt 250.00 Ft	Comments Comments Comments Comments	: : :
Conditions: PCI:54 Inspection Comments:  Sample Number: 201 Sample Comments: 50 PATCHING 50 PATCHING 45 DEPRESSION 48 LONGITUDINAL/T	Ty TRANSVI	/pe: R ERSE CRACKING	Area: L M L L L M M	62.00 SqFt 6.00 SqFt 4.00 SqFt 250.00 Ft 86.00 Ft	Comments Comments Comments Comments Comments	: : : :

M

L

Μ

L

M

M

7.00 SqFt

52.00 SqFt 15.00 SqFt

15.00 SqFt

85.00 Ft

180.00 SqFt

236.00 Ft

Comments:

Comments:

Comments:

Comments:

Comments:

Comments:

#### MN103-2012 CH

Report Generated Date: December 20, 2012

Network:	STC	Name: ST. CLOUD	
Branch:	CTD1	Name: CONNECTING TAXIWAY D	Use: TAXIWAY Area: 32,865.00SqFt
Section:	002	of 3 From: 400	To: 400 Last Const.: 09/30/1985  Zone: E Category: 2 Rank: S
Surface:	AC	Family: MN2012 Asphalt Taxiways	
Area:	7,435.00SqFt	Length: 142.00Ft Widt	1: 50.00Ft
Shoulder:	Street Ty	pe: Grade: 0.00 Lanes: 0	

Section Comments:

Last Insp. Date: 06/23/2012 Total Samples: 2 Surveyed: 1

Conditions: PCI: 61 Inspection Comments:

Sample Number: 400 Type: R	Area:		5,335.00SqFt		PCI = 61
Sample Comments:					
52 RAVELING		L	375.00	SqFt	Comments:
41 ALLIGATOR CRACKING		M	8.00	SqFt	Comments:
48 LONGITUDINAL/TRANSVERSE CRACKING		L	544.00	Ft	Comments:
48 LONGITUDINAL/TRANSVERSE CRACKING		M	92.00	Ft	Comments:

#### MN103-2012 CH

Report Generated Date: December 20, 2012

Network:	STC	Name: ST. CLOUD					
Branch:	CTD1	Name: CONNECTIN	IG TAXIWAY D		Use: TAXIWAY	Area:	32,865.00SqFt
Section: Surface:	003 AC	of 3 From: Family: MN2012			To: 401	Zone: E	Last Const.: 09/30/2001 Category: 2 Rank: S
Area: Shoulder:	3,750.00SqFt Street Ty	Length: pe: Grade:	75.00Ft 0.00 Lane	Width:	50.00Ft		

Section Comments:

Last Insp. Date: 06/22/2012 Total Samples: 1 Surveyed: 1

Conditions: PCI: 86 Inspection Comments:

Sample Number: 401 Type: R	Area:	3,750.00SqFt	PCI = 86
Sample Comments:			
52 RAVELING	L	18.00 SqFt	Comments:
48 LONGITUDINAL/TRANSVERSE CRACKING	L	58.00 Ft	Comments:
52 RAVELING	M	28.00 SqFt	Comments:

#### MN103-2012 CH

Report Generated Date: December 20, 2012

48 LONGITUDINAL/TRANSVERSE CRACKING

48 LONGITUDINAL/TRANSVERSE CRACKING

41 ALLIGATOR CRACKING

Report Generated Date: December 20, 2012				
Network: STC Name: ST. CLOUD				
Branch: CTD2 Name: CONNECTING TAXIV	WAY D2	Use: TAXIWAY	Area: 204	4,363.01SqFt
Section: 001 of 1 From: 300		To: 306		Last Const.: 09/30/1985
Surface: AC Family: MN2012 Asphalt Ta	axiways		Zone: E	Category: 2 Rank: S
Area: 204,363.01SqFt Length: 338.00F	t Widt	th: 601.00Ft		
Shoulder: Street Type: Grade: 0.00	Lanes: 0			
Section Comments:				
Conditions: PCI: 53 Inspection Comments:  Sample Number: 302 Type: R	Area:	3,000.00SqFt	PCI = 57	
Sample Comments: 48 LONGITUDINAL/TRANSVERSE CRACKING	L	209.00 Ft	Comments:	
48 LONGITUDINAL/TRANSVERSE CRACKING	M	62.00 Ft	Comments:	
41 ALLIGATOR CRACKING	M	4.00 SqFt	Comments:	
52 RAVELING	L	75.00 SqFt	Comments:	
50 PATCHING	L	94.00 SqFt	Comments:	
50 PATCHING	М	62.00 SqFt	Comments:	
Sample Number: 305 Type: R Sample Comments:	Area:	3,000.00SqFt	PCI = 50	
50 PATCHING	M	60.00 SqFt	Comments:	
52 RAVELING	L	100.00 SqFt	Comments:	
48 LONGITUDINAL/TRANSVERSE CRACKING	L	173.00 Ft	Comments:	

M

Η

41.00 Ft

17.00 Ft

20.00 SqFt

Comments:

Comments:

Comments:

MN103-2012 CH

<NO DISTRESSES>

Network: STC	Name: S'	Г. CLOUD				
Branch: CTE	Name: C	ONNECTING TAXIWA	Y E	Use: TAXIWAY	Area: 40	0,600.00SqFt
Section: 001 Surface: PCC	of 1 Family:	From: 100 MN2012 PCC		To: 105	Zone: E	Last Const.: 09/30/2001 Category: 2 Rank: P
Section Comments:	Slab Width: treet Type:	15.00Ft Grade: 0.00	Width: Slab Length: Lanes: 0	60.00Ft 20.00Ft	Joint Length:	3,600.00Ft
Conditions: PCI:		nples: 7 Sur	veyed: 2			
Sample Number: Sample Comments: <no distress<="" td=""><td>101 Type</td><td>: R</td><td>Area:</td><td>20.00Slabs</td><td>PCI = 100</td><td></td></no>	101 Type	: R	Area:	20.00Slabs	PCI = 100	
Sample Number: Sample Comments:	104 Type	: R	Area:	20.00Slabs	PCI = 100	

MN103-2012 CH

Sample Comments:
<NO DISTRESSES>

Network: STC	Name	e: ST. CLO	UD				
Branch: PPTC	Name	e: PART PA	ARALLEL TA	XIWAY C	Use: TAXIWAY	Area:	64,950.00SqFt
Section: 001	of	1 Fro	om: 100		To: 110		Last Const.: 09/30/200
Surface: PCC	Fai	mily: MN2	012 PCC			Zone: E	Category: 2 Rank: P
Area: 64,950.00	SqFt	Length:	1,070.00F	Width	: 60.00Ft		
Slabs: 216 Shoulder: S	Slab Wic	dth:	15.00Ft de: 0.00	Slab Length: Lanes: 0	20.00Ft	Joint Length:	6,360.00Ft
Last Insp. Date: 06.		ıl Samples:	11 S	urveyed: 3			
Conditions: PCI:	98	l Samples:	11 S	urveyed: 3			
Conditions: PCI: Inspection Comments Sample Number:	98	Il Samples:	11 S	urveyed: 3  Area:	20.00Slabs	PCI = 98	
Conditions: PCI: ! Inspection Comments  Sample Number: Sample Comments:	98:		11 S		20.00Slabs 20.00 Slabs	PCI = 98 Comments:	
Conditions: PCI: Inspection Comments Sample Number: Sample Comments: 65 JOINT SEA	98 : 102 AL DAMAGE		11 S	Area:			
Conditions: PCI:	98 : 102 AL DAMAGE 105	Type: R	11 S	Area:	20.00 Slabs	Comments:	

MN103-2012 CH

Report Generated Date: December 20, 2012

48 LONGITUDINAL/TRANSVERSE CRACKING

Network: STC	Name: ST. CLOUI	)				
Branch: PPTE	Name: PART PAR	ALLEL TAXIWAY E	Use:	TAXIWAY	Area:	57,820.00SqFt
Section: 001	of 2 From	: 200	To	D: 210		Last Const.: 09/30/1985
Surface: AC	Family: MN2012	2 Asphalt Taxiways			Zone: E	Category: 2 Rank: S
Area: 55,000.00SqFt	Length:	1,100.00Ft	Width: 50	).00Ft		
Shoulder: Street	Type: Grade:	0.00 Lanes:	0			
Section Comments: 2011 slu	nrry seal est.					
Inspection Comments:						
Sample Number: 201	Type: R	Area:	5,000.00SqFt		PCI = 74	
Sample Number: 201 Sample Comments:			•	00 Ft	PCI = 74 Comments:	
Sample Number: 201 Sample Comments: 48 LONGITUDINAL Sample Number: 204			•	00 Ft		
Sample Number: 201 Sample Comments: 48 LONGITUDINAL Sample Number: 204 Sample Comments:	/TRANSVERSE CRA	ACKING Area:	L 615.0	00 Ft	Comments:	
Sample Number: 201 Sample Comments: 48 LONGITUDINAL Sample Number: 204 Sample Comments: 48 LONGITUDINAL	/TRANSVERSE CRA	ACKING Area:	5,000.00SqFt		Comments:	
Sample Number: 201 Sample Comments: 48 LONGITUDINAL Sample Number: 204 Sample Comments: 48 LONGITUDINAL 48 LONGITUDINAL	/TRANSVERSE CRA	ACKING Area:	5,000.00SqFt	00 Ft	Comments: PCI = 69 Comments:	
Sample Number: 201 Sample Comments: 48 LONGITUDINAL Sample Number: 204 Sample Comments: 48 LONGITUDINAL 48 LONGITUDINAL	/TRANSVERSE CRA Type: R /TRANSVERSE CRA /TRANSVERSE CRA Type: R	ACKING  Area:  ACKING  ACKING  Area:	L 615.0  5,000.00SqFt  L 592.0  M 12.0  5,000.00SqFt	00 Ft	Comments:  PCI = 69  Comments: Comments:	

M

14.00 Ft

Comments:

MN103-2012 CH

Report Generated Date: December 20, 2012

Network: STC Name: ST. CLOUD

Branch: PPTE Name: PART PARALLEL TAXIWAY E Use: TAXIWAY Area: 57,820.00SqFt

Section: 002 of 2 From: 211 To: 211 Last Const.: 09/30/2001

Zone:

Category:

Rank: P

Surface: AAC Family: MN2012 Asphalt Taxiways

Area: 2,820.00SqFt Length: 47.00Ft Width: 60.00Ft

Shoulder: Street Type: Grade: 0.00 Lanes: 0

Section Comments:

Last Insp. Date: 06/23/2012 Total Samples: 1 Surveyed: 1

Conditions: PCI: 95 Inspection Comments:

Sample Number: 211 Type: R Area: 2,820.00SqFt PCI = 95

Sample Comments:

48 LONGITUDINAL/TRANSVERSE CRACKING L 27.00 Ft Comments:

#### MN103-2012 CH

Network: STC	Name: ST					
Branch: PTA	Name: PA	ARALLEL TAXIWA	Y A	Use: TAXIWAY	Area: 41	5,500.00SqFt
Section: 001 Surface: PCC	of 1 Family:	From: 100 MN2012 PCC		To: 169	Zone: E	Last Const.: 09/29/2001 Category: 2 Rank: P
Area: 415,500.00SqF Slabs: 1,385 Shoulder: Stree	t Leng Slab Width: t Type:	gth: 6,925.00Ft 15.00Ft Grade: 0.00	Slab Lengt Lanes: 0		Joint Length:	41,490.00Ft
Section Comments:						
Last Insp. Date: 06/22/Conditions: PCI: 100 Inspection Comments:	2012 Total Sam	nples: 69 S	Surveyed: 7			
Sample Number: 105 Sample Comments: <no distresses<="" td=""><td>71</td><td>: R</td><td>Area:</td><td>20.00Slabs</td><td>PCI = 100</td><td></td></no>	71	: R	Area:	20.00Slabs	PCI = 100	
Sample Number: 115	Туре	: R	Area:	20.00Slabs	PCI = 98	
Sample Comments: 75 CORNER SPALE	LING		L	1.00 Slabs	Comments:	
Sample Number: 125 Sample Comments: <no distresses<="" td=""><td>71</td><td>: R</td><td>Area:</td><td>20.00Slabs</td><td>PCI = 100</td><td></td></no>	71	: R	Area:	20.00Slabs	PCI = 100	
Sample Number: 135 Sample Comments: <no distresses<="" td=""><td>31</td><td>: R</td><td>Area:</td><td>20.00Slabs</td><td>PCI = 100</td><td></td></no>	31	: R	Area:	20.00Slabs	PCI = 100	
Sample Number: 145 Sample Comments: <no distresses<="" td=""><td>31</td><td>: R</td><td>Area:</td><td>20.00Slabs</td><td>PCI = 100</td><td></td></no>	31	: R	Area:	20.00Slabs	PCI = 100	
Sample Number: 155 Sample Comments: <no distresses<="" td=""><td>31</td><td>: R</td><td>Area:</td><td>20.00Slabs</td><td>PCI = 100</td><td></td></no>	31	: R	Area:	20.00Slabs	PCI = 100	
Sample Number: 165 Sample Comments: <no distresses<="" td=""><td>J1 ·</td><td>: R</td><td>Area:</td><td>20.00Slabs</td><td>PCI = 100</td><td></td></no>	J1 ·	: R	Area:	20.00Slabs	PCI = 100	

#### MN103-2012 CH

Section: 001	Report Generated Date: December 20, 2012				
Last Const.: 09/30/198   Surface: AC   Family: MN2012 Asphalt Taxiways   To: 111   Zone: E   Category: 2   Rank: Startage   AC   Family: MN2012 Asphalt Taxiways   Street Type: Grade: 0.00   Lanes: 0   Category: 2   Rank: Startage   Rank: Star	Network: STC Name: ST. CLOUD				
Surface: AC   Family: MN2012 Asphalt Taxiways   Zone: E   Category: 2   Rank: Street   48,000.00SqFt   Length: 1,200.00Ft   Width: 40,00Ft   Street Type: Grade: 0.00   Lanes: 0   Section Comments: has old ST	Branch: PTD Name: PARALLEL TAXIWAY	D	Use: TAX	XIWAY Area:	147,870.00SqFt
Area: 48,000.00SqFt			To: 11	1	
Street Type:   Grade: 0.00   Lanes: 0	Surface: AC Family: MN2012 Asphalt Tax	iways		Zone: E	Category: 2 Rank: S
Conditions: PCI: 60   Comments: has old ST	$Area: \qquad 48,000.00 SqFt \qquad \qquad Length: \qquad 1,200.00 Ft$	W	idth: 40.00F	t	
Last Insp. Date: 06/22/2012 Total Samples: 12 Surveyed: 3 Conditions: PCI: 60 Inspection Comments:    Sample Number:	Shoulder: Street Type: Grade: 0.00	Lanes: 0			
Conditions: PCI:60	Section Comments: has old ST				
Sample Comments:	Last Insp. Date: 06/22/2012 Total Samples: 12 Su Conditions: PCI: 60 Inspection Comments:	rveyed: 3			
### ALLIGATOR CRACKING	1	Area:	4,000.00SqFt	PCI = 60	
L	•	М	14.00	Saft Comments	<b>a:</b>
M   36.00 SqFt   Comments:   Square					
48 LONGITUDINAL/TRANSVERSE CRACKING  48 LONGITUDINAL/TRANSVERSE CRACKING  55.00 Ft  Comments:	50 PATCHING	M			
### LONGITUDINAL/TRANSVERSE CRACKING M 55.00 Ft Comments:    Sample Number: 106	57 WEATHERING	L		-	
Sample Number:   106   Type: R	48 LONGITUDINAL/TRANSVERSE CRACKING	L	289.00	Ft Comment:	<b>3</b> :
Sample Comments:	48 LONGITUDINAL/TRANSVERSE CRACKING	M	55.00	Ft Comments	s:
M	Sample Number: 106 Type: R Sample Comments:	Area:	4,000.00SqFt	PCI = 63	
48 LONGITUDINAL/TRANSVERSE CRACKING  48 LONGITUDINAL/TRANSVERSE CRACKING  48 LONGITUDINAL/TRANSVERSE CRACKING  49 M 34.00 Ft Comments:  40 DEPRESSION  40 L 2.00 SqFt Comments:  41 ALLIGATOR CRACKING  42 M 6.00 SqFt Comments:  43 Area: 4,000.00SqFt PCI = 56  44 Apple Comments:  45 Depression  46 L 15.00 SqFt Comments:  47 APPLIES COMMENTS:  48 LONGITUDINAL/TRANSVERSE CRACKING  49 M 64.00 SqFt Comments:  40 APPLIES COMMENTS:  41 ALLIGATOR CRACKING  42 M 17.00 SqFt Comments:  43 ALLIGATOR CRACKING  44 ALLIGATOR CRACKING  45 Depression  46 L 300.00 SqFt Comments:  47 ALLIGATOR CRACKING  48 LONGITUDINAL/TRANSVERSE CRACKING  49 L 361.00 Ft Comments:  40 Comments:  41 ALLIGATOR CRACKING  41 ALLIGATOR CRACKING  42 Depression  43 A.00 Ft Comments:  44 Comments:  45 Comments:  46 Comments:  47 Comments:  48 LONGITUDINAL/TRANSVERSE CRACKING  48 LONGITUDINAL/TRANSVERSE CRACKING  49 Comments:  40 Comments:  40 Comments:  41 Comments:  42 Comments:  43 Comments:  44 Comments:  45 Comments:  46 Comments:	50 PATCHING	L	30.00	SqFt Comment:	s:
48 LONGITUDINAL/TRANSVERSE CRACKING       M       34.00 Ft       Comments:         45 DEPRESSION       L       2.00 SqFt       Comments:         41 ALLIGATOR CRACKING       M       6.00 SqFt       Comments:         Sample Number:       110       Type: R       Area:       4,000.00SqFt       PCI = 56         Sample Comments:       E       15.00 SqFt       Comments:         50 PATCHING       M       64.00 SqFt       Comments:         41 ALLIGATOR CRACKING       M       17.00 SqFt       Comments:         52 RAVELING       L       300.00 SqFt       Comments:         48 LONGITUDINAL/TRANSVERSE CRACKING       L       361.00 Ft       Comments:	50 PATCHING	M	54.00	SqFt Comments	s:
L   2.00 SqFt   Comments:   41 ALLIGATOR CRACKING	48 LONGITUDINAL/TRANSVERSE CRACKING	L	282.00	Ft Comment:	s:
### ALLIGATOR CRACKING M 6.00 SqFt Comments:    Sample Number: 110	48 LONGITUDINAL/TRANSVERSE CRACKING	= =			s:
Sample Number: 110   Type: R   Area: 4,000.00SqFt   PCI = 56	45 DEPRESSION				<b>3</b> :
Sample Comments:  50 PATCHING L 15.00 SqFt Comments:  50 PATCHING M 64.00 SqFt Comments:  41 ALLIGATOR CRACKING M 17.00 SqFt Comments:  52 RAVELING L 300.00 SqFt Comments:  48 LONGITUDINAL/TRANSVERSE CRACKING L 361.00 Ft Comments:	41 ALLIGATOR CRACKING	М	6.00	SqFt Comment:	5:
50 PATCHING L 15.00 SqFt Comments: 50 PATCHING M 64.00 SqFt Comments: 41 ALLIGATOR CRACKING M 17.00 SqFt Comments: 52 RAVELING L 300.00 SqFt Comments: 48 LONGITUDINAL/TRANSVERSE CRACKING L 361.00 Ft Comments:	Sample Number: 110 Type: R Sample Comments:	Area:	4,000.00SqFt	PCI = 56	
41 ALLIGATOR CRACKING M 17.00 SqFt Comments: 52 RAVELING L 300.00 SqFt Comments: 48 LONGITUDINAL/TRANSVERSE CRACKING L 361.00 Ft Comments:	50 PATCHING	L	15.00	SqFt Comment:	s:
52 RAVELING L 300.00 SqFt Comments: 48 LONGITUDINAL/TRANSVERSE CRACKING L 361.00 Ft Comments:	50 PATCHING	M	64.00	SqFt Comments	s:
48 LONGITUDINAL/TRANSVERSE CRACKING L 361.00 Ft Comments:	41 ALLIGATOR CRACKING	M	17.00	SqFt Comments	s:
	52 RAVELING	L	300.00	SqFt Comments	5:
48 LONGITUDINAL/TRANSVERSE CRACKING M 56.00 Ft Comments:	48 LONGITUDINAL/TRANSVERSE CRACKING	L			s:
	48 LONGITUDINAL/TRANSVERSE CRACKING	М	56.00	Ft Comment:	S:

MN103-2012 CH

STC

Network:

Report Generated Date: December 20, 2012

Branch: PTD Name: PARALLEL TAXIWAY D Use: TAXIWAY Area: 147,870.00SqFt

Section: 002 of 5 From: 112 To: 112 Last Const.: 09/30/2001
Surface: AAC Family: MN2012 Asphalt Taxiways Zone: Category: Rank: S

Area: 2,820.00SqFt Length: 50.00Ft Width: 60.00Ft

Shoulder: Street Type: Grade: 0.00 Lanes: 0

Name: ST. CLOUD

Section Comments:

Last Insp. Date: 06/22/2012 Total Samples: 1 Surveyed: 1

Conditions: PCI: 88 Inspection Comments:

Sample Number: 112 Type: R Area: 2,820.00SqFt PCI = 88

Sample Comments:

48 LONGITUDINAL/TRANSVERSE CRACKING L 108.00 Ft Comments:

MN103-2012 CH

Report Generated Date: December 20, 2012

THE WOIK.	STC	Name:	ST. CLOUD					
Branch:	PTD	Name:	PARALLEL	TAXIWAY D		Use: TAXIWAY	Area: 14	47,870.00SqFt
Section: Surface:	003 PCC	of 5 Famil	From: y: MN2012			To: 107	Zone: E	Last Const.: 09/30/2003 Category: 2 Rank: S
Area:	51,000.00SqFt	L	ength:	650.00Ft	Width	: 60.00Ft		
Slabs: 170 Shoulder: Section Com	Street		Grade:		Slab Length: Lanes: 0	20.00Ft	Joint Length:	3,840.00Ft
Conditions	: PCI : 99	012 Total S	amples: 9	Surve	eyed: 2			
Conditions Inspection C Sample Nu	: PCI : 99 comments:		pe: R	Surve	Area:	20.00Slabs	PCI = 98	
Conditions Inspection C Sample Nu Sample Corr	: PCI : 99 comments:	Ту		Surve		20.00Slabs 1.00 Slabs	PCI = 98 Comments:	

MN103-2012 CH

Report Generated Date: December 20, 2012

Network: STC Name: ST. CLOUD Branch: PTD Name: PARALLEL TAXIWAY D Use: TAXIWAY Area: 147,870.00SqFt Section: 004 From: 121 To: 121 Last Const.: 09/30/2001 of 5 Family: MN2012 Asphalt Taxiways Surface: Zone: E Category: 2 Rank: S AC Area: 6,050.00SqFt Length: 110.00Ft Width: 55.00Ft

Shoulder: Street Type: Grade: 0.00 Lanes: 0

Section Comments:

Last Insp. Date: 06/22/2012 Total Samples: 1 Surveyed: 1

Conditions: PCI: 81 Inspection Comments:

Sample Number: 121 Type: R Area: 6,050.00SqFt PCI = 81

Sample Comments:

48 LONGITUDINAL/TRANSVERSE CRACKING L 25.00 Ft Comments: 48 LONGITUDINAL/TRANSVERSE CRACKING M 112.00 Ft Comments:

#### MN103-2012 CH

52 RAVELING

48 LONGITUDINAL/TRANSVERSE CRACKING

48 LONGITUDINAL/TRANSVERSE CRACKING

Report Generated Date: December 20, 2012

N 1				
Network: STC Name: ST. CLOUD				
Branch: PTD Name: PARALLEL TAXIWAY	D	Use: TAXIWAY	Area: 14	7,870.00SqFt
Section: 005 of 5 From: 122		To: 129		Last Const.: 09/30/1985
Surface: AC Family: MN2012 Asphalt Tax	tiways		Zone: E	Category: 2 Rank: S
Area: 40,000.00SqFt Length: 800.00Ft	Wio	dth: 50.00Ft		
Shoulder: Street Type: Grade: 0.00	Lanes: 0			
200000000000000000000000000000000000000	•			
Section Comments: old ST				
T C				
Inspection Comments:  Sample Number: 122 Type: R Sample Comments:	Area:	4,000.00SqFt	PCI = 52	
	Area:		PCI = 52 Comments:	
Sample Number: 122 Type: R Sample Comments:		4,000.00SqFt 350.00 SqFt 3.00 SqFt		
Sample Number: 122 Type: R Sample Comments: 52 RAVELING	L	350.00 SqFt	Comments:	
Sample Number: 122 Type: R Sample Comments: 52 RAVELING 41 ALLIGATOR CRACKING	L M	350.00 SqFt 3.00 SqFt	Comments:	
Sample Number: 122 Type: R Sample Comments: 52 RAVELING 41 ALLIGATOR CRACKING 48 LONGITUDINAL/TRANSVERSE CRACKING 48 LONGITUDINAL/TRANSVERSE CRACKING Sample Number: 126 Type: R	L M L	350.00 SqFt 3.00 SqFt 812.00 Ft	Comments: Comments:	
Sample Number: 122 Type: R Sample Comments: 52 RAVELING 41 ALLIGATOR CRACKING 48 LONGITUDINAL/TRANSVERSE CRACKING 48 LONGITUDINAL/TRANSVERSE CRACKING	L M L M	350.00 SqFt 3.00 SqFt 812.00 Ft 60.00 Ft	Comments: Comments: Comments:	
Sample Number: 122 Type: R Sample Comments: 52 RAVELING 41 ALLIGATOR CRACKING 48 LONGITUDINAL/TRANSVERSE CRACKING 48 LONGITUDINAL/TRANSVERSE CRACKING Sample Number: 126 Type: R Sample Comments:	L M L M	350.00 SqFt 3.00 SqFt 812.00 Ft 60.00 Ft	Comments: Comments: Comments: Comments:	

L

Μ

75.00 SqFt

307.00 Ft

101.00 Ft

Comments:

Comments:

Comments:

MN103-2012 CH

Sample Number:

Sample Comments:
<NO DISTRESSES>

Report Generated Date: December 20, 2012

200

Type: R

Network:	STC	Name: S	T. CLOUD				
Branch:	RP1	Name: R	un-up Pad 1		Use: TAXIWAY	Area:	22,800.00SqFt
Section: Surface:	001 PCC	of 1 Family:	From: 200 MN2012 PCC		To: 301	Zone: E	Last Const.: 09/30/2001 Category: 2 Rank: S
Area:	22,800.00SqF	t Len	gth: 190.00Ft	Width:	120.00Ft		
Slabs: 76		Slab Width:	15.00Ft	Slab Length:	20.00Ft	Joint Length:	2,350.00Ft
Shoulder:	Stree	et Type:	Grade: 0.00	Lanes: 0			
Section Cor	nments:						
Section Cor	mments:	2012 Total Sar		veyed: 1			
•	s: PCI: 100		ipies. 4 Sui	veyed. 1			

Area:

20.00Slabs

PCI = 100

MN103-2012 CH

Report Generated Date: December 20, 2012

Type: R

Network: Name: ST. CLOUD STC Branch: RP2 Name: Run-up Pad 2 Use: TAXIWAY Area: 22,800.00SqFt Section: 001 of From: 268 To: 369 Last Const.: 09/30/2001 Family: MN2012 PCC PCC Surface: Zone: E Category: 2 Rank: S Area: 22,800.00SqFt Length: 190.00Ft Width: 120.00Ft Joint Length: Slabs: 76 Slab Width: 15.00Ft Slab Length: 20.00Ft 2,350.00Ft Shoulder: Street Type: Grade: 0.00 Lanes: 0 Section Comments: Last Insp. Date: 06/22/2012 Total Samples: Surveyed: 1 Conditions: PCI: 100 Inspection Comments:

Area:

20.00Slabs

PCI = 100

Sample Number: Sample Comments:

<NO DISTRESSES>

269

#### MN103-2012 CH

<NO DISTRESSES>

Report Generated Date: December 20, 2012

Network: STC	Name: ST	C. CLOUD				
Branch: RY1331	Name: RI	JNWAY 13-31		Use: RUNWAY	Area: 1,050	0,000.00SqFt
Section: 001 Surface: PCC	of 3 Family:	From: 100 MN2012 PCC		To: 157	Zone: E	Last Const.: 09/30/2001 Category: 2 Rank: P
Area: 350,000.00SqFt	Leng	th: 7,000.00Ft	Width	50.00Ft		
Slabs: 1,167 Shoulder: Street T	Slab Width: Type:	15.00Ft Grade: 0.00	Slab Length: Lanes: 0	20.00Ft	Joint Length:	33,783.33Ft
Section Comments:						
Last Insp. Date: 06/22/20 Conditions: PCI: 98 Inspection Comments:	)12 Total Sam	ples: 58 Su	rveyed: 6			
Sample Number: 103 Sample Comments: <no distresses=""></no>	Туре	R	Area:	18.00Slabs	PCI = 100	
Sample Number: 113 Sample Comments: <no distresses=""></no>	Туре	R	Area:	18.00Slabs	PCI = 100	
Sample Number: 123 Sample Comments:	Type	R	Area:	18.00Slabs	PCI = 98	
74 JOINT SPALLIN	1G		L	1.00 Slabs	Comments:	
Sample Number: 133 Sample Comments:	Туре	R	Area:	18.00Slabs	PCI = 95	
75 CORNER SPALL:	ING		Н	1.00 Slabs	Comments:	
Sample Number: 143 Sample Comments:	Туре	R	Area:	18.00Slabs	PCI = 95	
75 CORNER SPALL	ING		Н	1.00 Slabs	Comments:	
Sample Number: 153 Sample Comments:	Туре	R	Area:	18.00Slabs	PCI = 100	

#### MN103-2012 CH

Report Generated Date: December 20, 2012

Network: STC Nan	ne: ST. CLOUD				
NIC INGII	nc. bi.cloub				
Branch: RY1331 Nan	ne: RUNWAY 13-31		Use: RUNWAY	Area: 1,050	,000.00SqFt
Section: 002 of Surface: PCC F	3 From: 300 amily: MN2012 PCC		To: 357	Zone: E	Last Const.: 09/30/2001 Category: 2 Rank: P
Area: 350,000.00SqFt	Length: 7,000.00Ft	Width:	50.00Ft		
Slabs: 1,167 Slab W	idth: 15.00Ft	Slab Length:	20.00Ft	Joint Length:	33,783.33Ft
Shoulder: Street Type:	Grade: 0.00	Lanes: 0			
Section Comments:					
Last Insp. Date: 06/22/2012 To Conditions: PCI: 97 Inspection Comments:	tal Samples: 58 Su	ırveyed: 6			
Sample Number: 304 Sample Comments:	Type: R	Area:	24.00Slabs	PCI = 94	
66 SMALL PATCH		L	2.00 Slabs	Comments:	
75 CORNER SPALLING		L	3.00 Slabs	Comments:	
Sample Number: 314 Sample Comments:	Type: R	Area:	24.00Slabs	PCI = 98	
66 SMALL PATCH		L	2.00 Slabs	Comments:	
Sample Number: 324 Sample Comments:	Type: R	Area:	24.00Slabs	PCI = 97	
75 CORNER SPALLING		M	1.00 Slabs	Comments:	
Sample Number: 334 Sample Comments: <no distresses=""></no>	Type: R	Area:	24.00Slabs	PCI = 100	
Sample Number: 344 Sample Comments: <no distresses=""></no>	Type: R	Area:	24.00Slabs	PCI = 100	
Sample Number: 354 Sample Comments:	Type: R	Area:	24.00Slabs	PCI = 93	
65 JOINT SEAL DAMAGE		M	24.00 Slabs	Comments:	

MN103-2012 CH

<NO DISTRESSES>

Report Generated Date: December 20, 2012

Network: STC	Name:	ST. CLOUD				
Branch: RY1331	Name:	RUNWAY 13-31		Use: RUNWAY	Area: 1,050	,000.00SqFt
Section: 003 Surface: PCC Area: 350,000.008		From: 500 ily: MN2012 PCC Length: 7,000.00	0Ft Width:	To: 557	Zone: E	Last Const.: 09/30/2002 Category: 2 Rank: P
Slabs: 1,167 Shoulder: Str Section Comments:	Slab Widt reet Type:	h: 15.00Ft Grade: 0.00	Slab Length: Lanes: 0	20.00Ft	Joint Length:	33,783.33Ft
Last Insp. Date: 06/2 Conditions: PCI: 99 Inspection Comments:		Samples: 58	Surveyed: 6			
Sample Number: Sample Comments: 75 CORNER SPA		ype: R	Area: L	18.00Slabs 2.00 Slabs	PCI = 96 Comments:	
Sample Number: :: Sample Comments: <no distresse<="" td=""><td></td><td>ype: R</td><td>Area:</td><td>18.00Slabs</td><td>PCI = 100</td><td></td></no>		ype: R	Area:	18.00Slabs	PCI = 100	
Sample Number: Sample Comments: <no distresse<="" td=""><td></td><td>ype: R</td><td>Area:</td><td>18.00Slabs</td><td>PCI = 100</td><td></td></no>		ype: R	Area:	18.00Slabs	PCI = 100	
Sample Number: Sample Comments: <no distresse<="" td=""><td></td><td>ype: R</td><td>Area:</td><td>18.00Slabs</td><td>PCI = 100</td><td></td></no>		ype: R	Area:	18.00Slabs	PCI = 100	
Sample Number: Sample Comments: <no distresse<="" td=""><td></td><td>ype: R</td><td>Area:</td><td>18.00Slabs</td><td>PCI = 100</td><td></td></no>		ype: R	Area:	18.00Slabs	PCI = 100	
Sample Number: Sample Comments:	555 T	ype: R	Area:	18.00Slabs	PCI = 100	

#### MN103-2012 CH

Report Generated Date: December 20, 2012.

Report Generated Date: December 20, 2012				
Network: STC Name: ST. CLOUD				
Branch: RY523 Name: RUNWAY 5-23		Use: RUNWAY	Area: 23	8,400.00SqFt
Section: 001 of 5 From: 100		To: 113		Last Const.: 09/30/1985
Surface: AC Family: MN2012 Asphalt Runw	vays		Zone: E	Category: 2 Rank: S
Area: 52,500.00SqFt Length: 700.00Ft	V	Width: 75.00Ft		
Shoulder: Street Type: Grade: 0.00	Lanes: 0			
Section Comments:				
Last Insp. Date: 06/22/2012 Total Samples: 14 Surv	veyed: 3			
Conditions: PCI: 21				
Inspection Comments:				
Sample Number: 101 Type: R	Area:	3,750.00SqFt	PCI = 22	
Sample Comments:		, 1		
41 ALLIGATOR CRACKING	M		Comments:	
48 LONGITUDINAL/TRANSVERSE CRACKING	L		Comments:	
48 LONGITUDINAL/TRANSVERSE CRACKING	M		Comments:	
45 DEPRESSION	L		Comments:	
52 RAVELING	М	3,750.00 SqFt	Comments:	
Sample Number: 106 Type: R Sample Comments:	Area:	3,750.00SqFt	PCI = 16	
41 ALLIGATOR CRACKING	M	182.00 SqFt	Comments:	
43 BLOCK CRACKING	L	1,875.00 SqFt	Comments:	
48 LONGITUDINAL/TRANSVERSE CRACKING	L		Comments:	
48 LONGITUDINAL/TRANSVERSE CRACKING	M		Comments:	
52 RAVELING	М	3,750.00 SqFt	Comments:	
Sample Number: 111 Type: R	Area:	3,750.00SqFt	PCI = 24	
Sample Comments: 41 ALLIGATOR CRACKING	L	142.00 SqFt	Comments:	
48 LONGITUDINAL/TRANSVERSE CRACKING	L		Comments:	
48 LONGITUDINAL/TRANSVERSE CRACKING	M		Comments:	
45 DEPRESSION	L		Comments:	
52 RAVELING	M	<del>-</del>	Comments:	
	1.1	3,,30.00 8410	001111101100	

MN103-2012 CH

STC

Network:

Report Generated Date: December 20, 2012

Branch: RY523 Name: RUNWAY 5-23 Use: RUNWAY Area: 238,400.00SqFt

Section: 002 of 5 From: 115 To: 116 Last Const.: 09/30/2001

Zone: E

Category:

2 Rank: S

Surface: AC Family: MN2012 Asphalt Runways

Area: 8,400.00SqFt Length: 100.00Ft Width: 84.00Ft

Shoulder: Street Type: Grade: 0.00 Lanes: 0

Name: ST. CLOUD

Section Comments: maintenance since 2009 inspection

Last Insp. Date: 06/22/2012 Total Samples: 2 Surveyed: 1

Conditions: PCI: 81 Inspection Comments:

Sample Number: 114 Type: R Area: 3,975.00SqFt PCI = 81

Sample Comments:

48 LONGITUDINAL/TRANSVERSE CRACKING L 185.00 Ft Comments: 48 LONGITUDINAL/TRANSVERSE CRACKING M 10.00 Ft Comments:

MN103-2012 CH

Report Generated Date: December 20, 2012

Network: STC Name: ST. CLOUD				
Network. STC Name: S1. CLOUD				
Branch: RY523 Name: RUNWAY 5	-23	Use: RUNWAY	Area: 238	s,400.00SqFt
Section: 003 of 5 From:		To: 131		Last Const.: 09/30/200
Surface: PCC Family: MN2012	PCC		Zone: E	Category: 2 Rank: S
Area: 70,000.00SqFt Length:	700.00Ft Width:	100.00Ft		
Slabs: 140 Slab Width: 25	00Ft Slab Length:	20.00Ft	Joint Length:	5,500.00Ft
Last Insp. Date: 06/22/2012 Total Samples: 7 Conditions: PCI: 98 Inspection Comments:	Surveyed: 2			
Sample Number: 100 Type: R Sample Comments:	Area:	20.00Slabs	PCI = 98	
65 JOINT SEAL DAMAGE	L	20.00 Slabs	Comments:	
Sample Number: 105 Type: R Sample Comments:	Area:	20.00Slabs	PCI = 98	

#### MN103-2012 CH

52 RAVELING

52 RAVELING

Report Generated Date: December 20, 2012

48 LONGITUDINAL/TRANSVERSE CRACKING

48 LONGITUDINAL/TRANSVERSE CRACKING

Network:	STC	Name: S	T. CLOUD									
Branch:	RY523	Name: I	RUNWAY 5	-23			Use: RUN	IWAY	Area:	238	8,400.00SqFt	
Section:	004	of 5	From:	132			To: 133	3			Last Const.:	09/30/200
Surface:	AC	Family	MN2012	Asphalt Runy	ways				Zone:	E	Category:	2 Rank: S
Area:	17,500.00SqFt	Ler	ngth:	200.00Ft		Width:	75.00Ft	t				
Shoulder:	Street T	ype:	Grade:	0.00	Lanes:	0						
Condition	Date: 06/22/20	-		Sur	rveyed: 2							
Last Insp. Conditions Inspection (	Date: 06/22/20 as: PCI: 62 Comments:	12 Total Sa		Sur	rveyed: 2  Area:		5.00SqFt		PCI = 59			
Last Insp. Conditions Inspection ( Sample No	Date: 06/22/20 as: PCI: 62 Comments:  (umber: 132 mments:	12 Total Sar	mples: 4			4,17	1					
Last Insp. Conditions Inspection C Sample No Sample Condense LON	Date: 06/22/20 as: PCI: 62 Comments:  [umber: 132 mments: [GITUDINAL/	12 Total Sar	mples: 4		Area:	4,17 L	505.00 F		Commer			
Last Insp. Conditions Inspection O Sample No Sample Con 48 LON 52 RAV	Date: 06/22/20 as: PCI: 62 Comments: fumber: 132 mments: GITUDINAL/	12 Total Sar	mples: 4		Area:	4,17 L L	505.00 F 160.00 S	SqFt	Commer Commer	nts:		
Last Insp. Conditions Inspection ( Sample No Sample Con 48 LON 52 RAV	Date: 06/22/20 as: PCI: 62 Comments:  [umber: 132 mments: [GITUDINAL/	12 Total Sar	mples: 4		Area:	4,17 L	505.00 F	SqFt SqFt	Commer	nts:		

L

M

350.00 Ft

11.00 Ft

550.00 SqFt

75.00 SqFt

Comments:

Comments:

Comments:

Comments:

#### MN103-2012 CH

Report Generated Date: December 20, 2012

Network: STC Name: ST. CLOUD				
Branch: RY523 Name: RUNWAY 5-23		Use: RUNWAY	Area: 23	8,400.00SqFt
Section: 005 of 5 From: 134 Surface: AC Family: MN2012 Asphalt Runv	ways	To: 159	Zone: E	Last Const.: 09/30/1985 Category: 2 Rank: S
Area: 90,000.00SqFt Length: 1,200.00Ft		7idth: 75.00Ft		
Shoulder: Street Type: Grade: 0.00	Lanes: 0	75.0011		
Section Comments:				
Last Insp. Date: 06/22/2012 Total Samples: 24 Sur Conditions: PCI: 16 Inspection Comments:	veyed: 5			
Sample Number: 138 Type: R Sample Comments:	Area:	3,750.00SqFt	PCI = 18	
48 LONGITUDINAL/TRANSVERSE CRACKING	L	456.00 Ft	Comments:	
41 ALLIGATOR CRACKING	M	366.00 SqFt	Comments:	
52 RAVELING	M	3,750.00 SqFt	Comments:	
Sample Number: 143 Type: R Sample Comments:	Area:	3,750.00SqFt	PCI = 15	
41 ALLIGATOR CRACKING	M	215.00 SqFt	Comments:	
48 LONGITUDINAL/TRANSVERSE CRACKING	L	118.00 Ft	Comments:	
45 DEPRESSION	L	16.00 SqFt	Comments:	
43 BLOCK CRACKING	L	2,818.00 SqFt	Comments:	
52 RAVELING	M	3,750.00 SqFt	Comments:	
Sample Number: 148 Type: R Sample Comments:	Area:	3,750.00SqFt	PCI = 16	
41 ALLIGATOR CRACKING	M	208.00 SqFt	Comments:	
45 DEPRESSION	L	10.00 SqFt	Comments:	
48 LONGITUDINAL/TRANSVERSE CRACKING	L	20.00 Ft	Comments:	
43 BLOCK CRACKING	L	2,600.00 SqFt	Comments:	
52 RAVELING	М	3,750.00 SqFt	Comments:	
Sample Number: 153 Type: R Sample Comments:	Area:	3,750.00SqFt	PCI = 15	
41 ALLIGATOR CRACKING	M	340.00 SqFt	Comments:	
43 BLOCK CRACKING	L	1,750.00 SqFt	Comments:	
48 LONGITUDINAL/TRANSVERSE CRACKING	L	142.00 Ft	Comments:	
52 RAVELING	M	3,750.00 SqFt	Comments:	
Sample Number: 158 Type: R Sample Comments:	Area:	3,750.00SqFt	PCI = 18	
41 ALLIGATOR CRACKING	M	292.00 SqFt	Comments:	
48 LONGITUDINAL/TRANSVERSE CRACKING	L	510.00 Ft	Comments:	
52 RAVELING	M	3,750.00 SqFt	Comments:	

#### MN103-2012 CH

Report Generated Date: December 20, 2012

Report Generated Date: December 20, 2012				
Network: STC Name: ST. CLOUD				
Branch: TLA Name: Taxilane A		Use: TAXILANE	Area: 30	5,890.00SqFt
Section: 001 of 5 From: 100		To: ??		Last Const.: 06/01/1970
Surface: AAC Family: MN2012 Asphalt Tax	ilanes		Zone: E	Category: 2 Rank: T
Area: 117,000.00SqFt Length: 420.00Ft	V	Vidth: 350.00Ft		
Shoulder: Street Type: Grade: 0.00	Lanes: 0			
Shoulder. Street Type. Grade. 6.60	Zunes. o			
Section Comments: estimated LCD				
Last Insp. Date: 06/22/2012 Total Samples: 29 Sur	rveyed: 4			
Conditions: PCI: 20				
Inspection Comments:				
Sample Number: 101 Type: R	Area:	3,000.00SqFt	PCI = 35	
Sample Comments:				
41 ALLIGATOR CRACKING	M		Comments:	
43 BLOCK CRACKING	L	2,500.00 SqFt	Comments:	
43 BLOCK CRACKING	M	375.00 SqFt	Comments:	
57 WEATHERING	L	200.00 SqFt	Comments:	
Sample Number: 300 Type: R Sample Comments:	Area:	4,500.00SqFt	PCI = 7	
41 ALLIGATOR CRACKING	M	2,000.00 SqFt	Comments:	
43 BLOCK CRACKING	M		Comments:	
43 BLOCK CRACKING	Н	<del>-</del>	Comments:	
45 DEPRESSION	L	26.00 SqFt	Comments:	
48 LONGITUDINAL/TRANSVERSE CRACKING	L	<del>-</del>	Comments:	
52 RAVELING	Н	18.00 SqFt	Comments:	
57 WEATHERING	Н	1,130.00 SqFt	Comments:	
Sample Number: 501 Type: R	Area:	5,000.00SqFt	PCI = 23	
Sample Comments:	M	454.00 SqFt	Commonta	
41 ALLIGATOR CRACKING 43 BLOCK CRACKING	M	2,270.00 SqFt	Comments:	
43 BLOCK CRACKING 43 BLOCK CRACKING	L M	2,273.00 SqFt	Comments:	
52 RAVELING	Н	<del>-</del>	Comments:	
JZ KAVELING	п	3.00 bqrc	Commencs	
Sample Number: 601 Type: R Sample Comments:	Area:	4,700.00SqFt	PCI = 18	
52 RAVELING	M	32.00 SqFt	Comments:	
41 ALLIGATOR CRACKING	M	888.00 SqFt	Comments:	
43 BLOCK CRACKING	H	<b>-</b>	Comments:	
52 RAVELING	H	-	Comments:	
53 RUTTING	L	-	Comments:	
43 BLOCK CRACKING	L		Comments:	
48 LONGITUDINAL/TRANSVERSE CRACKING	M		Comments:	
45 DEPRESSION	L	10.00 SqFt	Comments:	

#### MN103-2012 CH

Report Generated Date: December 20, 2012

Network: STC Name: ST. CLOUD Branch: TLA Name: Taxilane A Use: TAXILANE Area: 305,890.00SqFt Section: 002 of 5 From: 100 To: 102 Last Const.: 06/01/1990 Family: MN2012 Asphalt Taxilanes Surface: Zone: E Category: 2 Rank: T ACArea: 7,840.00SqFt Length: 245.00Ft Width: 32.00Ft Shoulder: Grade: 0.00 Lanes: 0 Street Type:

Section Comments: estimated LCD

Last Insp. Date: 06/22/2012 Total Samples: 2 Surveyed: 1

Conditions: PCI: 42 Inspection Comments:

Sample Number: 100 Type: R	Area:	4,000.00SqFt		PCI = 42
Sample Comments:				
45 DEPRESSION	I	73.00	SqFt	Comments:
48 LONGITUDINAL/TRANSVERSE CRACKING	I	6.00	Ft	Comments:
48 LONGITUDINAL/TRANSVERSE CRACKING	I	16.00	Ft	Comments:
48 LONGITUDINAL/TRANSVERSE CRACKING	I	563.00	Ft	Comments:
41 ALLIGATOR CRACKING	I	78.00	SqFt	Comments:
57 WEATHERING	I	420.00	SqFt	Comments:

#### MN103-2012 CH

Report Generated Date: December 20, 2012

Network: STC Name: ST. CLOUD					
Branch: TLA Name: Taxilane A		Use: TA	XILANE	Area: 305	5,890.00SqFt
Section: 003 of 5 From: 200 Surface: AAC Family: MN2012 Asphalt Tax	ilanes	To: 9	02	Zone: E	Last Const.: 06/01/1995 Category: 2 Rank: T
Area: 102,550.00SqFt Length: 400.00Ft		idth: 250.001	Ft		
Shoulder: Street Type: Grade: 0.00	Lanes: 0				
Section Comments: estimated LCD					
Last Insp. Date: 06/22/2012 Total Samples: 20 Su: Conditions: PCI: 48 Inspection Comments:	rveyed: 5				
Sample Number: 103 Type: R Sample Comments:	Area:	4,000.00SqFt		PCI = 28	
41 ALLIGATOR CRACKING	L	90.00		Comments:	
41 ALLIGATOR CRACKING	M	205.00	SqFt	Comments:	
41 ALLIGATOR CRACKING	Н	6.00	_	Comments:	
56 SWELLING	L	94.00		Comments:	
57 WEATHERING	L	500.00	_	Comments:	
48 LONGITUDINAL/TRANSVERSE CRACKING 48 LONGITUDINAL/TRANSVERSE CRACKING	L M	124.00 41.00		Comments: Comments:	
to LONGITUDINAL/TRANSVERSE CRACKING	IvI	41.00	rt	Commencs.	
Sample Number: 300 Type: R Sample Comments:	Area:	3,000.00SqFt		PCI = 45	
48 LONGITUDINAL/TRANSVERSE CRACKING	L	407.00	Ft	Comments:	
48 LONGITUDINAL/TRANSVERSE CRACKING	M	45.00	Ft	Comments:	
45 DEPRESSION	Н	10.00		Comments:	
41 ALLIGATOR CRACKING	M	50.00		Comments:	
57 WEATHERING	L	180.00	SqFt	Comments:	
Sample Number: 401 Type: R Sample Comments:	Area:	3,000.00SqFt		PCI = 32	
43 BLOCK CRACKING	M	838.00		Comments:	
43 BLOCK CRACKING	L	1,661.00	_	Comments:	
41 ALLIGATOR CRACKING	M	40.00		Comments:	
48 LONGITUDINAL/TRANSVERSE CRACKING	L	90.00		Comments:	
57 WEATHERING 52 RAVELING	L L	3,000.00 220.00		Comments:	
52 KAVELING	п	220.00	sqrt	Commencs.	
Sample Number: 504 Type: R Sample Comments:	Area:	4,800.00SqFt		PCI = 57	
41 ALLIGATOR CRACKING	М	18.00		Comments:	
48 LONGITUDINAL/TRANSVERSE CRACKING	L	52.00		Comments:	
48 LONGITUDINAL/TRANSVERSE CRACKING	M	318.00		Comments:	
57 WEATHERING	L	1,200.00	Patr	Comments:	
Sample Number: 603 Type: R Sample Comments:	Area:	3,200.00SqFt		PCI = 79	
48 LONGITUDINAL/TRANSVERSE CRACKING	M	32.00	Ft	Comments:	
48 LONGITUDINAL/TRANSVERSE CRACKING	L	172.00	Ft	Comments:	

#### MN103-2012 CH

Branch: TLA Name: Taxilane A		Use: TAXILANE	Area: 30	5,890.00SqFt
Section: 004 of 5 From: 100		To: 303		Last Const.: 06/01/1995
Surface: AAC Family: MN2012 Asphalt Taxilar	nes		Zone: E	Category: 2 Rank: T
Area: 37,750.00SqFt Length: 350.00Ft	$\mathbf{W}_{\mathbf{i}}$	idth: 140.00Ft		
Shoulder: Street Type: Grade: 0.00	Lanes: 0			
ast Insp. Date: 06/22/2012 Total Samples: 10 Surve Conditions: PCI: 27	eyed: 2			
Conditions: PCI : 27 nspection Comments:		4 800 00\$aEt	PCI = 24	
Conditions: PCI : 27 Inspection Comments:  Sample Number: 100 Type: R	Area:	4,800.00SqFt	PCI = 24	
Conditions: PCI : 27 nspection Comments:		4,800.00SqFt 64.00 SqFt	PCI = 24 Comments:	
Conditions: PCI : 27 Inspection Comments:  Sample Number: 100 Type: R Isomple Comments:	Area:	-		
Conditions: PCI: 27 Inspection Comments:  Sample Number: 100 Type: R Imple Comments:  11 ALLIGATOR CRACKING	Area:	64.00 SqFt	Comments:	
Conditions: PCI: 27 Inspection Comments:  Sample Number: 100 Type: R Sample Comments:  11 ALLIGATOR CRACKING 12 ALLIGATOR CRACKING 22 RAVELING 22 RAVELING	Area:	64.00 SqFt 30.00 SqFt 32.00 SqFt 3,000.00 SqFt	Comments: Comments: Comments:	
Conditions: PCI: 27 Inspection Comments:  Sample Number: 100 Type: R Imple Comments:  11 ALLIGATOR CRACKING 11 ALLIGATOR CRACKING 22 RAVELING	Area:  M L H	64.00 SqFt 30.00 SqFt 32.00 SqFt	Comments: Comments:	

Sample Number:	300	Type: R		Area:		4,700.00SqFt		PCI = 30
Sample Comments:								
52 RAVELING					Η	12.00	SqFt	Comments:
52 RAVELING					M	2,400.00	SqFt	Comments:
52 RAVELING					L	2,560.00	SqFt	Comments:
41 ALLIGATO	R CRAC	KING			M	16.00	SqFt	Comments:
43 BLOCK CR	ACKING				L	442.00	SqFt	Comments:
48 LONGITUD	INAL/T	RANSVERSE	CRACKING		L	533.00	Ft	Comments:
48 LONGITUD	INAL/T	RANSVERSE	CRACKING		M	66.00	Ft	Comments:

#### MN103-2012 CH

Sample Comments:

Report Generated Date:	December 20, 2012				
Network: STC	Name: ST. CLOUD				
Branch: TLA	Name: Taxilane A		Use: TAXILANE	Area: 305	5,890.00SqFt
Section: 005	of 5 From: 100		To: ??		Last Const.: 06/01/1995
Surface: AAC	Family: MN2012 Asphalt T	Taxilanes		Zone: E	Category: 2 Rank: T
Area: 40,750.00SqFt	Length: 350.00	Ft Wi	dth: 155.00Ft		
Shoulder: Street	Гуре: Grade: 0.00	Lanes: 0			
Inspection Comments:					
Sample Number: 100 Sample Comments:	Type: R	Area:	4,200.00SqFt	PCI = 65	
48 LONGITUDINAL	TRANSVERSE CRACKING	L	353.00 Ft	Comments:	
48 LONGITUDINAL	TRANSVERSE CRACKING	M	94.00 Ft	Comments:	
57 WEATHERING		M	2,400.00 SqFt	Comments:	
57 WEATHERING		L	1,800.00 SqFt	Comments:	
Sample Number: 300	Type: R	Area:	5,200.00SqFt	PCI = 56	

Sample Comments:

41 ALLIGATOR CRACKING

48 LONGITUDINAL/TRANSVERSE CRACKING

48 LONGITUDINAL/TRANSVERSE CRACKING

49 LONGITUDINAL/TRANSVERSE CRACKING

400.00 SqFt

400.00 SqFt

57 WEATHERING

L 2,600.00 SqFt

Comments:

## Appendix D

# **Distress Identification**

This appendix lists and describes distress types most commonly identified during the PCI inspections of Minnesota airports. Note that the pictures provided in this appendix are for illustration purposes and do not necessarily reflect the conditions or pavements at this airport. Descriptions and measurement inspection criteria are provided herein.

#### **Flexible (Asphalt) Pavement Distress**

#### **Example of Longitudinal and Transverse Cracking (L&T cracking)**



Longitudinal and transverse cracks are caused by pavement aging, by construction, and by subsurface movement. Aging occurs as pavement loses some of its components to the atmosphere and becomes more brittle. Consistent application of pavement sealcoats can help to prevent the occurrence of age related cracks. Cracks will also develop along poorly constructed paving lane joints. Ensuring that joints are made when both sides are still hot, and near the same temperature, is one of the best ways to mitigate this potential problem. Seasonal movement caused by changes in moisture content or temperature differences can also cause pavement cracks. Asphalt pavement placed over a PCC pavement or cement stabilized base course may evidence reflective cracking from the underlying material. Longitudinal and transverse cracks are not caused by wheel loads, although traffic may worsen their condition.

Low severity longitudinal and transverse cracks are less than ¼ inch wide, or if sealed with suitable filler material in satisfactory condition can be any width, less than 3 inches, if they are not spalled. Maintenance usually is not indicated for low-severity cracking. Moderately spalled cracks and cracks wider than ¼ inch which are not satisfactorily sealed are at medium severity. Medium-severity cracks should be sealed with a high-quality crack filling material. Severely spalled cracks and cracks wider than 3 inches are at high severity. High-severity L&T cracks normally require patching.

#### **Example of Block Cracking**



Block cracking is longitudinal and transverse cracking that has established a pattern of blocks ranging in size from 1ft x 1ft to 10ft x 10ft. This distress typically happens in older asphalt pavements and is an indication that the bituminous binder has lost most of its flexibility. The severity determination is basically determined by the crack width criteria defined for longitudinal and transverse cracking. Crack sealing typically is used to repair block cracking; however, the amount of required sealant can be extensive due to the high density of cracks.

#### **Example of Alligator Cracking**



Alligator (or fatigue) cracks are a series of interconnected load-related cracks caused by fatigue of the asphalt surface. Alligator cracking is a significant structural distress and develops only in places subject to traffic loads. These cracks typically initiate at the bottom of the asphalt layer (where tensile strains

are highest) and propagate upward - so once a fatigue crack is visible, significant damage has already occurred.

At low severity, alligator cracks are evidenced by a series of parallel hairline cracks (usually in a wheel path). Further traffic and deterioration leads to the interconnection of these cracks. Medium severity alligator cracking is a well-defined pattern of interconnected cracks, some spalling may be present. High severity alligator cracks have lost aggregate interlock between adjacent pieces, the cracks may be severely spalled with FOD potential, and most likely the pieces will move freely under traffic. Alligator cracking is a structural failure and cannot be repaired with sealant, the proper repair is full-depth patching.

#### Example of Raveling/Weathering



Raveling and weathering are the wearing away of the pavement surface. Raveling is the condition where the mid- to large size aggregates are becoming dislodged; weathering is when the fine aggregate wears away exposing the edges of the larger aggregate. This distress is usually evident over large areas. Raveling and weathering may indicate that the asphalt binder has hardened significantly. At low severity, the surface has started to wear away with few (if any) loose particles and the coarse surface aggregate is exposed to 1/4 of its diameter. At medium severity, the aggregate and/or binder have worn away with some loose and missing particles, and the surface texture is moderately rough and pitted, but the average depth of erosion is less than ¼ inch. At high severity, the aggregate and/or binder have worn away with a large amount of loose and missing particles, the surface texture is severely rough and pitted, and the top layer of aggregate has eroded away.

#### **Example of Patching**



Patched areas are defined when a portion of the original pavement is replaced with a material intended as a semi-permanent repair. A patch is documented as a defect because it is considered a break in the integrity of the pavement structure. Patches are constructed for a verity of reasons including utility repairs, correcting grade issues, and addressing a defect in the original pavement. The severity level of patches is determined by the amount of distress (i.e. cracking, depression, weathering/raveling, etc.) occurring within the limits of the patched area.

#### **Example of Rutting**



Ruts are localized, load related, areas of pavement having elevations lower than the surrounding sections. Rutting is due to base and subgrade consolidation, caused by excessive wheel loads or poor compactions. Ruts indicate structural failure, and can cause hydroplaning. At low severity, ruts have an

average depth of  $\frac{1}{2}$  to  $\frac{1}{2}$  inches. At medium severity, ruts have an average depth of  $\frac{1}{2}$  to  $\frac{1}{2}$  inch. High severity, ruts have an average depth greater than  $\frac{1}{2}$  inch. Full-depth patching is the appropriate repair for ruts.

#### **Rigid (Concrete) Pavement Distress**

#### Example of Longitudinal, Transverse, and Diagonal Cracking



LTD cracking is most often a result of externally applied loads and/or constrained temperature deformations. External loads cause LTD cracking through flexure. Temperature changes on restrained slabs will result in stresses due to friction or curling. When any of these stresses exceed the strength of the slab, cracking will occur. LTD cracking is recorded at low, medium, or high severity, depending on the width of crack opening and degree of deterioration. At low severity, the crack is less than 1/8th inch wide with little spalling and no corrective action is indicated. At medium severity, LTD cracks can be up to 1 inch wide with moderate spalling, and should be repaired and sealed using procedures similar to joint sealing. At high severity, cracks exceed 1 inch in width and may be severely spalled. High-severity LTD cracking is evidence of serious load failure of the slab, and correction may require patching or slab replacement. If the distress occurs in several adjacent slabs at medium or high severity, major rehabilitation of that pavement area is indicated.

When a slab is divided by LTD cracks into four or more pieces, the slab is said to be "divided" or "shattered." Shattered slab is a separate distress category and is indicative of significant structural failure as the slab loses its ability to distribute loads to subgrade and further slab deterioration can be expected. Shattered slabs are rated in three severities, with slab replacement recommended for medium and high severities.

#### **Example of Shrinkage Cracking**



Shrinkage cracks are small, nonworking (no spalling along edge) cracks that are visible at the surface but do not penetrate through the full depth of concrete. Shrinkage cracks most commonly occur shortly after construction due to concrete shrinkage during the curing process. Shrinkage cracks are usually so small that they are not visible until staining or material loss at crack edges begins to take place. Shrinkage cracks do not represent a structural weakness, and no corrective action is prescribed.

#### **Example of Joint and Corner Spalling**



Spalls at slab joints and corners are caused by excessive internal stress in the pavement. Spalls occur when these stresses exceed the shear strength of the concrete. Spalling usually results from thermal expansion during warm or hot weather. As slabs expand, they push against one another at joints. If the joints are filled with incompressibles, such as sand, or if adjacent slabs offset slightly, stresses can become severe, causing spalls. Spalling can be reduced significantly by conscientious maintenance of joint sealant.

Spall repair requires patching. The extent and severity of spalling on a pavement surface suggests appropriate action. For example, at low severity, spalled concrete remains securely in place in the slab. A low-severity spall should be monitored closely for further deterioration and should be patched when

spalled particles become loose in place, or at the next scheduled patching activity in the section. Medium- and high-severity spalls should be repaired immediately to prevent the incidence of FOD. If the pavement can be restored to serviceable condition, spalls should be carefully patched for long-term service. If the pavement is beyond repair, temporary patching should be considered to control FOD.

#### **Example of Durability Cracking**



Durability cracking (D-cracking) is caused by environmental factors, the most common of which is freezing/thawing. It usually appears as a pattern of hairline cracks running parallel to a joint or crack, or in a corner, where water tends to collect. This type of cracking eventually leads to disintegration of the pavement, creating FOD potential. At low severity, D-cracking is evident, but no disintegration has occurred. As the distress advances to medium severity, the distress pattern is evident over a significant area of the slab, and some disintegration and FOD potential exists. High severity durability cracking is evidenced by extensive cracking with loose and missing pieces and significant FOD potential.

#### **Example of Joint Seal Damage**



Joint seal damage is recorded at three severities: low, medium, and high. When joint sealant is in perfect condition (no damage), it is not a distress. At low severity, at least 10 percent of the sealant is debonded but still in contact with the joint edges (i.e., joint sealant is in serviceable condition but should

be monitored for evidence of more serious failure). Medium-severity joint seal damage is recorded when at least 10 percent of the sealant has visible gaps smaller than 1/8th inch and is an indicator that replacement should be programmed as soon as is practicable. In the meantime, aggressive inspection and sustaining maintenance is recommended to minimize subsurface damage from moisture penetration. At high severity, visible gaps exceed 1/8th inch and the amount and degree of joint seal damage is such that repair is no longer feasible. The only appropriate corrective action is sealant replacement.

On serviceable pavement, deteriorated joint sealant should be repaired or replaced to preserve pavement and subgrade integrity and prolong service life. The issue is not so clear-cut with unserviceable pavement. Pavement that can be restored to serviceable condition by maintenance activities such as patching and joint seal repair, or by slab replacement, should be so maintained as long as the process is cost-effective. However, when age and condition preclude economical return to serviceable condition by such means, joint seal repair would no longer be cost-effective and should be suspended except for an interim maintenance program to control FOD potential.

Joint sealant can stop the evidence of pumping (water forced to surface through joints and cracks) but will not correct the cause (voids under pavement).

This page intentionally left blank.

#### Appendix E

# **Maintenance and Major Rehabilitation Policies**

Table 1. Localized maintenance policy for asphalt surfaces.

Distress type	Distress severity	Maintenance treatment
	Low	Crack Sealing - AC
Alligator cracking	Medium	Patching - AC Deep
	High	Patching - AC Deep
Bleeding	N/A	Monitor
	Low	Monitor
Block cracking	Medium	Crack Sealing - AC
	High	Crack Sealing - AC
	Low	Monitor
Corrugation	Medium	Patching - AC Deep
	High	Patching - AC Deep
	Low	Monitor
Depression	Medium	Patching - AC Shallow
	High	Patching - AC Deep
Jet blast	N/A	Patching - AC Shallow
	Low	Monitor
Joint reflection cracking	Medium	Crack Sealing - AC
	High	Crack Sealing - AC
	Low	Monitor
Longitudinal & transverse cracking	Medium	Crack Sealing - AC
(L&T cracking)	High	Crack Sealing - AC
Oil spillage	N/A	Patching - AC Shallow
	Low	Monitor
Patching	Medium	Crack Sealing - AC
	High	Patching - AC Deep
Polished aggregate	N/A	Monitor
	Low	Monitor
Raveling	Medium	Surface Treatment
	High	Patching - AC Shallow
	Low	Monitor
Rutting	Medium	Patching - AC Deep
	High	Patching - AC Deep
	Low	Monitor
Shoving	Medium	Patching - AC Shallow
	High	Patching - AC Deep
Slippage cracking	N/A	Patching - AC Shallow
	Low	Monitor
Swelling	Medium	Patching - AC Deep
	High	Patching - AC Deep
	Low	Monitor
Weathering	Medium	Surface Treatment
	High	Patching - AC Shallow

Table 2. Localized maintenance policy for PCC surfaces.

Distress type	Distress severity	Maintenance treatment
	Low	Patching - PCC Partial Depth
Blow up	Medium	Slab Replacement - PCC
	High	Slab Replacement - PCC
	Low	Monitor
Corner break	Medium	Patching - PCC Full Depth
	High	Patching - PCC Full Depth
	Low	Monitor
Linear cracking	Medium	Crack Sealing - PCC
	High	Patching - PCC Full Depth
	Low	Monitor
Durability cracking	Medium	Patching - PCC Full Depth
, ,	High	Slab Replacement - PCC
	Low	Monitor
Joint seal damage	Medium	Joint Seal (Localized)
	High	Joint Seal (Localized)
	Low	Monitor
Small patch	Medium	Patching - PCC Partial Depth
·	High	Patching - PCC Partial Depth
	Low	Monitor
Large patch	Medium	Patching - PCC Full Depth
	High	Patching - PCC Full Depth
Popouts	N/A	Monitor
Pumping	N/A	Monitor
	Low	Monitor
Scaling	Medium	Patching - PCC Partial Depth
	High	Slab Replacement - PCC
	Low	Monitor
Faulting	Medium	Grinding (Localized)
	High	Grinding (Localized)
	Low	Monitor
Shattered slab	Medium	Crack Sealing - PCC
	High	Slab Replacement - PCC
Shrinkage cracking	N/A	Monitor
	Low	Monitor
Joint spall	Medium	Patching - PCC Partial Depth
	High	Patching - PCC Partial Depth
	Low	Monitor
Corner spall	Medium	Patching - PCC Partial Depth
	High	Patching - PCC Partial Depth
	Low	Monitor
ASR	Medium	Patching - PCC Full Depth

Table 3. Unit costs for localized maintenance treatments.

Treatment name	Unit cost
Crack Sealing - AC	\$1.12 ft
Crack Sealing - PCC	\$1.69 ft
Grinding (Localized)	\$4.41 ft
Joint Seal (Localized)	\$1.69 ft
Patching - AC Deep	\$10.46 sf
Patching - AC Leveling	\$3.66 sf
Patching - AC Shallow	\$7.02 sf
Patching - PCC Full Depth	\$65.70 sf
Patching - PCC Partial Depth	\$9.45 sf
Slab Replacement - PCC	\$35.37 sf
Surface Treatment	\$0.46 sf
Undersealing - PCC	\$2.80 ft

Table 4. Major rehabilitation unit costs based on PCI ranges.

PCI range	Cost
0-29	\$7.60 sf
30-39	\$6.30 sf
40-49	\$5.25 sf
50-59	\$3.70 sf
60-69	\$2.35 sf
> 70	\$1.15 sf

## Appendix F

# **Localized Maintenance Recommendations**

Table F.1. Recommended maintenance by section report (STC).

Branch ID	Section ID	Distress Type	Severity	Treatment	<b>Estimated Quantity</b>	Unit	Cost
APB	1	ALLIGATOR CR	L	Crack Sealing - AC	196	Ft	\$220
APB	1	L & T CR	М	Crack Sealing - AC	349	Ft	\$391
APB	1	OIL SPILLAGE	N	Patching - AC Shallow	125	SqFt	\$880
APB	2	L & T CR	М	Crack Sealing - AC	379	Ft	\$424
APB	2	ALLIGATOR CR	М	Patching - AC Deep	154	SqFt	\$1,611
CTA3X	1	JT SEAL DMG	М	Joint Seal (Localized)	960	Ft	\$1,622
CTA3X	2	ALLIGATOR CR	L	Crack Sealing - AC	11	Ft	\$12
CTA3X	2	L & T CR	M	Crack Sealing - AC	20	Ft	\$22
CTD1	1	L & T CR	M	Crack Sealing - AC	618	Ft	\$692
CTD1	1	PATCHING	М	Crack Sealing - AC	35	Ft	\$39
CTD1	1	ALLIGATOR CR	М	Patching - AC Deep	79	SqFt	\$822
CTD1	1	RAVELING	М	Surface Treatment	650	SqFt	\$299
CTD1	2	L & T CR	М	Crack Sealing - AC	128	Ft	\$144
CTD1	2	ALLIGATOR CR	М	Patching - AC Deep	29	SqFt	\$299
CTD1	3	RAVELING	М	Surface Treatment	28	SqFt	\$13
CTD2	1	L & T CR	Н	Crack Sealing - AC	579	Ft	\$649
CTD2	1	L & T CR	М	Crack Sealing - AC	3,508	Ft	\$3,929
CTD2	1	PATCHING	М	Crack Sealing - AC	1,347	Ft	\$1,508
CTD2	1	ALLIGATOR CR	М	Patching - AC Deep	937	SqFt	\$9,796
PPTC	1	CORNER SPALL	М	Patching - PCC Partial Depth	10	SqFt	\$92
PPTE	1	L & T CR	М	Crack Sealing - AC	95	Ft	\$107
PTD	1	L & T CR	М	Crack Sealing - AC	609	Ft	\$682
PTD	1	PATCHING	М	Crack Sealing - AC	230	Ft	\$257
PTD	1	ALLIGATOR CR	М	Patching - AC Deep	210	SqFt	\$2,192
PTD	4	L & T CR	М	Crack Sealing - AC	112	Ft	\$125
PTD	5	L & T CR	М	Crack Sealing - AC	805	Ft	\$902
PTD	5	PATCHING	М	Crack Sealing - AC	57	Ft	\$63
PTD	5	ALLIGATOR CR	М	Patching - AC Deep	89	SqFt	\$929
RY1331	1	CORNER SPALL	Н	Patching - PCC Partial Depth	58	SqFt	\$550
RY1331	2	JT SEAL DMG	М	Joint Seal (Localized)	5,631	Ft	\$9,516

Branch ID	Section ID	Distress Type	Severity	Treatment	<b>Estimated Quantity</b>	Unit	Cost
RY1331	2	CORNER SPALL	М	Patching - PCC Partial Depth	22	SqFt	\$206
RY523	1	ALLIGATOR CR	L	Crack Sealing - AC	235	Ft	\$263
RY523	1	L & T CR	М	Crack Sealing - AC	747	Ft	\$836
RY523	1	ALLIGATOR CR	М	Patching - AC Deep	1,731	SqFt	\$18,110
RY523	1	RAVELING	М	Surface Treatment	52,500	SqFt	\$24,150
RY523	2	L & T CR	М	Crack Sealing - AC	21	Ft	\$24
RY523	4	L & T CR	М	Crack Sealing - AC	39	Ft	\$44
RY523	4	RAVELING	М	Surface Treatment	427	SqFt	\$196
RY523	5	ALLIGATOR CR	М	Patching - AC Deep	7,157	SqFt	\$74,864
RY523	5	RAVELING	М	Surface Treatment	90,000	SqFt	\$41,400
TLA	1	BLOCK CR	Н	Crack Sealing - AC	3,089	Ft	\$3,460
TLA	1	BLOCK CR	М	Crack Sealing - AC	7,149	Ft	\$8,007
TLA	1	L & T CR	М	Crack Sealing - AC	449	Ft	\$503
TLA	1	ALLIGATOR CR	М	Patching - AC Deep	24,130	SqFt	\$252,399
TLA	1	RAVELING	Н	Patching - AC Shallow	320	SqFt	\$2,244
TLA	1	WEATHERING	Н	Patching - AC Shallow	7,687	SqFt	\$53,960
TLA	1	RAVELING	М	Surface Treatment	218	SqFt	\$100
TLA	2	L&TCR	Н	Crack Sealing - AC	12	Ft	\$13
TLA	2	L&TCR	М	Crack Sealing - AC	31	Ft	\$35
TLA	2	ALLIGATOR CR	М	Patching - AC Deep	207	SqFt	\$2,162
TLA	3	ALLIGATOR CR	L	Crack Sealing - AC	185	Ft	\$208
TLA	3	BLOCK CR	М	Crack Sealing - AC	1,455	Ft	\$1,630
TLA	3	L & T CR	М	Crack Sealing - AC	2,484	Ft	\$2,782
TLA	3	ALLIGATOR CR	М	Patching - AC Deep	1,957	SqFt	\$20,472
TLA	3	ALLIGATOR CR	Н	Patching - AC Deep	62	SqFt	\$646
TLA	3	DEPRESSION	Н	Patching - AC Deep	91	SqFt	\$956
TLA	4	ALLIGATOR CR	L	Crack Sealing - AC	51	Ft	\$57
TLA	4	L & T CR	М	Crack Sealing - AC	302	Ft	\$338
TLA	4	ALLIGATOR CR	М	Patching - AC Deep	394	SqFt	\$4,118
TLA	4	RAVELING	Н	Patching - AC Shallow	175	SqFt	\$1,227
TLA	4	RAVELING	М	Surface Treatment	21,458	SqFt	\$9,871
TLA	5	ALLIGATOR CR	L	Crack Sealing - AC	33	Ft	\$36
TLA	5	L & T CR	М	Crack Sealing - AC	533	Ft	\$597

Branch ID	Section ID	Distress Type	Severity	Treatment	<b>Estimated Quantity</b>	Unit	Cost
TLA	5	WEATHERING	М	Surface Treatment	10,404	SqFt	\$4,786
Airport Total							\$569,487

Table F.2. Recommended maintenance by treatment report (STC).

Branch ID	Section ID	Distress Type	Severity	Treatment	<b>Estimated Quantity</b>	Unit	Cost
APB	1	ALLIGATOR CR	L	Crack Sealing - AC	196	Ft	\$220
APB	1	L & T CR	M	Crack Sealing - AC	349	Ft	\$391
APB	2	L & T CR	M	Crack Sealing - AC	379	Ft	\$424
CTA3X	2	ALLIGATOR CR	L	Crack Sealing - AC	11	Ft	\$12
CTA3X	2	L & T CR	М	Crack Sealing - AC	20	Ft	\$22
CTD1	1	L & T CR	M	Crack Sealing - AC	618	Ft	\$692
CTD1	1	PATCHING	M	Crack Sealing - AC	35	Ft	\$39
CTD1	2	L & T CR	М	Crack Sealing - AC	128	Ft	\$144
CTD2	1	L & T CR	Н	Crack Sealing - AC	579	Ft	\$649
CTD2	1	L & T CR	М	Crack Sealing - AC	3,508	Ft	\$3,929
CTD2	1	PATCHING	M	Crack Sealing - AC	1,347	Ft	\$1,508
PPTE	1	L & T CR	M	Crack Sealing - AC	95	Ft	\$107
PTD	1	L & T CR	М	Crack Sealing - AC	609	Ft	\$682
PTD	1	PATCHING	М	Crack Sealing - AC	230	Ft	\$257
PTD	4	L & T CR	М	Crack Sealing - AC	112	Ft	\$125
PTD	5	L & T CR	М	Crack Sealing - AC	805	Ft	\$902
PTD	5	PATCHING	М	Crack Sealing - AC	57	Ft	\$63
RY523	1	ALLIGATOR CR	L	Crack Sealing - AC	235	Ft	\$263
RY523	1	L & T CR	М	Crack Sealing - AC	747	Ft	\$836
RY523	2	L & T CR	M	Crack Sealing - AC	21	Ft	\$24
RY523	4	L & T CR	M	Crack Sealing - AC	39	Ft	\$44
TLA	1	BLOCK CR	Н	Crack Sealing - AC	3,089	Ft	\$3,460
TLA	1	BLOCK CR	M	Crack Sealing - AC	7,149	Ft	\$8,007
TLA	1	L & T CR	М	Crack Sealing - AC	449	Ft	\$503
TLA	2	L & T CR	Н	Crack Sealing - AC	12	Ft	\$13
TLA	2	L & T CR	M	Crack Sealing - AC	31	Ft	\$35
TLA	3	ALLIGATOR CR	L	Crack Sealing - AC	185	Ft	\$208
TLA	3	BLOCK CR	М	Crack Sealing - AC	1,455	Ft	\$1,630
TLA	3	L & T CR	М	Crack Sealing - AC	2,484	Ft	\$2,782
TLA	4	ALLIGATOR CR	L	Crack Sealing - AC	51	Ft	\$57
TLA	4	L & T CR	M	Crack Sealing - AC	302	Ft	\$338
TLA	5	ALLIGATOR CR	L	Crack Sealing - AC	33	Ft	\$36

Branch ID	Section ID	Distress Type	Severity	Treatment	<b>Estimated Quantity</b>	Unit	Cost
TLA	5	L & T CR	М	Crack Sealing - AC	533	Ft	\$597
			25,892 Ft		\$28,999		
CTA3X	1	JT SEAL DMG	М	Joint Seal (Localized)	960	Ft	\$1,622
RY1331	2	JT SEAL DMG	М	Joint Seal (Localized)	5,631	Ft	\$9,516
			Tota	l Joint Seal (Localized) Quantity	6,591 Ft		\$11,138
APB	2	ALLIGATOR CR	М	Patching - AC Deep	154	SqFt	\$1,611
CTD1	1	ALLIGATOR CR	М	Patching - AC Deep	79	SqFt	\$822
CTD1	2	ALLIGATOR CR	М	Patching - AC Deep	29	SqFt	\$299
CTD2	1	ALLIGATOR CR	М	Patching - AC Deep	937	SqFt	\$9,796
PTD	1	ALLIGATOR CR	М	Patching - AC Deep	210	SqFt	\$2,192
PTD	5	ALLIGATOR CR	М	Patching - AC Deep	89	SqFt	\$929
RY523	1	ALLIGATOR CR	М	Patching - AC Deep	1,731	SqFt	\$18,110
RY523	5	ALLIGATOR CR	М	Patching - AC Deep	7,157	SqFt	\$74,864
TLA	1	ALLIGATOR CR	М	Patching - AC Deep	24,130	SqFt	\$252,399
TLA	2	ALLIGATOR CR	М	Patching - AC Deep	207	SqFt	\$2,162
TLA	3	ALLIGATOR CR	М	Patching - AC Deep	1,957	SqFt	\$20,472
TLA	3	ALLIGATOR CR	Н	Patching - AC Deep	62	SqFt	\$646
TLA	3	DEPRESSION	Н	Patching - AC Deep	91	SqFt	\$956
TLA	4	ALLIGATOR CR	М	Patching - AC Deep	394	SqFt	\$4,118
			Tot	tal Patching – AC Deep Quantity	37,225 SqFt		\$389,376
APB	1	OIL SPILLAGE	N	Patching - AC Shallow	125	SqFt	\$880
TLA	1	RAVELING	Н	Patching - AC Shallow	320	SqFt	\$2,244
TLA	1	WEATHERING	Н	Patching - AC Shallow	7,687	SqFt	\$53,960
TLA	4	RAVELING	Н	Patching - AC Shallow	175	SqFt	\$1,227
		Total Patching - AC Shallow Quantity			8,306 SqFt		\$58,312
PPTC	1	CORNER SPALL	М	Patching - PCC Partial Depth	10	SqFt	\$92
RY1331	1	CORNER SPALL	Н	Patching - PCC Partial Depth	58	SqFt	\$550
RY1331	2	CORNER SPALL	М	Patching - PCC Partial Depth	22	SqFt	\$206
	Total Patching – PCC Partial Depth Quantity			90 SqFt		\$847	
CTD1	1	RAVELING	М	Surface Treatment	650	SqFt	\$299
CTD1	3	RAVELING	М	Surface Treatment	28	SqFt	\$13
RY523	1	RAVELING	М	Surface Treatment	52,500	SqFt	\$24,150
RY523	4	RAVELING	М	Surface Treatment	427	SqFt	\$196

<b>Branch ID</b>	Section ID	Distress Type	Severity	Treatment	<b>Estimated Quantity</b>	Unit	Cost
RY523	5	RAVELING	М	Surface Treatment	90,000	SqFt	\$41,400
TLA	1	RAVELING	М	Surface Treatment	218	SqFt	\$100
TLA	4	RAVELING	М	Surface Treatment	21,458	SqFt	\$9,871
TLA	5	WEATHERING	M	Surface Treatment	10,404	SqFt	\$4,786
Total Surface Treatment Quantity 175,685 SqFt						\$80,815	
					Airpor	t Total	\$569,487

# **Maintenance Repair Guidelines**

#### **General Comments**

Ongoing inspections are the cornerstone of a maintenance management program. Crack sealing prevents surface water from entering the pavement structure and helps prevent the introduction of incompressible material into the paving joints and cracks, reducing the chances for spalls and further pavement deterioration.

Preservation of a pavement system will require a combination of preventive, sustaining, and restorative maintenance repairs. Preventive maintenance is primarily an inspection program, sustaining maintenance is an ongoing maintenance function, whose purpose is to seal newly formed cracks in areas where the sealant is in otherwise satisfactory condition. Restorative repairs are major work items, often performed under contract that typically involves complete removal and replacement of existing sealant.

#### **Maintenance Activities**

## Flexible (Asphalt) Pavement

Longitudinal and transverse (L&T) cracks at medium severity (>¾" wide) should be filled with a good quality crack filler material. High-severity cracks must normally be patched. Cracks rated at low severity may be narrow-unsealed cracks or sealed cracks up to 3 inches wide. The PCI procedure does not distinguish between narrow unfilled cracks and wider filled cracks. When 25 percent or more of total crack quantity is at medium or high severity, a restorative program becomes cost-effective. When medium- or high-severity cracking constitutes less than 25 percent of the total, sustaining maintenance is usually more cost-effective.

Medium- and high-severity existing patches should be replaced with new patches. Small areas (usually less than 100 square feet per patch) of alligator cracking and rutting at medium and high severity may also be repaired by patching. Larger patches should be considered if equipment can be made available to accomplish the work. Patching to repair up to 10 percent of the surface of a pavement feature that is otherwise serviceable can result in significant cost savings as compared to rehabilitation of the entire feature.

#### PCC (Concrete) Pavement

Joint seal damage at medium and high severity should be repaired. If medium- and high-severity damage is limited to less than about 25 percent of total joint length, sustaining maintenance is recommended. If medium and high-severity damage exceeds about 25 percent of the total joint length, joint sealant should be removed and replaced under a restorative repair project.

Longitudinal/transverse/diagonal (LTD) cracks at low and medium severity should be considered for sealing as part of the joint sealing project. High-severity LTD cracks require sealing, patching, or slab replacement, depending on the extent of deterioration.

Small patches are most often placed to repair medium- and high-severity spalls or to replace deteriorated older patches. Restorative small patches are typically partial depth repairs, usually to

load transfer steel. Large patches and corner breaks at medium and high severity should be repaired by full-depth large patches.

High-severity LTD cracks and shattered slabs are candidates for patching and slab replacement. Low-severity shattered slabs can be left in place pending further deterioration.

#### **Pavement Failure**

Before maintenance and repairs are attempted, it helps to have an understanding of the way pavement performs and deteriorates.

## **Environmental/Age-Related Deterioration**

Seasonal temperature changes cause expansion and contraction of the pavement materials, causing the pavement to move up to 1 foot per 1,000 feet. Much of this movement can be witnessed as the opening and closing of existing transverse cracks.

The pavement thickness and type of subgrade plays a large role in the formation and spacing interval of transverse cracks. If the subgrade material is smooth or rounded, the pavement surface will move relatively freely, the transverse cracks will usually be spaced far apart (>60 feet). If the subgrade material is rough or angular the pavement surface will not move freely and transverse cracks will be spaced more closely (<40 feet). The distance between transverse cracks will also depend on the pavement thickness, as a thicker pavement can resist cracking for longer lengths, but around 50 feet is typical for general aviation airport pavements.

Age related distress deals with the pavement oxidation or loss of volatile components to the atmosphere. An oxidized pavement becomes more brittle with time. Surface treatments and seal coats are designed, in part, to provide a protective barrier and prevent this type of oxidation.

#### **Materials Related Deterioration**

Subsurface water can have the greatest impact on pavement deterioration. A wet subgrade greatly reduces the ability of a pavement to support wheel loads, and the results often show up as rutting and cracking. The fine materials in a wet base can be pumped up through the cracks and eventually result in a loss of subgrade support. This loss of support can be evidenced as corner breaks and faulting. Moisture inside a pavement system expands when it freezes; creating stresses that push and tear at the pavement. The following thaw cycles will leave voids in the pavement structure that enable further rutting and breaking. Repeated freeze/thaw cycles will eventually cause pavement to disintegrate. One of the best ways to assure pavement longevity is to provide drainage and keep it dry.

Aggregate is the biggest component of any pavement structure, and it is the contact between the aggregate particles that actually transfers the load and provides the strength. Aggregate durability and shape are major factors affecting pavement performance. Durability is the ability of the aggregate to perform satisfactorily over time and resist the detrimental effect of nature. Sharp, well-angled aggregate that interlock, compact densely, and resists movement are the most desirable.

#### **Air Voids**

Well-distributed interconnected air voids allow escape paths for freezing water and generally reduce susceptibility to freeze/thaw damage. In PCC pavements, closely spaced interconnected air voids provide the greatest degree of protection.

Asphalt pavements, on the other hand, only tolerate air voids as necessary. Air voids allow for expansion of the asphalt binder, but also allow water penetration into the pavement. Interconnected air voids are undesirable here because the voids allow air to penetrate the asphalt layers and oxidize the binder. As air voids increase, durability and flexibility decrease, but stability and skid resistance increase. Asphalt pavements should be designed and compacted so that air voids are not interconnected. The air voids should allow only for the expansion of the asphalt and aggregate without, bleeding, and air voids should be kept low enough to prevent water and air from penetrating the asphalt layers.

#### **Binders**

Regardless of whether the pavement is asphalt or concrete, the binder material is mixed with the aggregate to coat all particles with a thin film. An asphalt coating allows the pavement to be flexible and still resist large movements. Durability of the asphalt pavement is increased by a thicker film because it is more resistant to age hardening; however, too thick of a film and the asphalt acts like a lubricant, promoting ruts, shoving, and bleeding. Specifications control aggregate and binder mix quantities, but each mix should be customized for materials available locally.

With a concrete pavement, the aggregate supports the load, but the cement binder interlocks with the aggregate to inhibit all movement. Hydration is the term for the chemical reaction of portland cement with water, and in the hydration process, dry cement particles react with water, to form gels, and then crystals, that grow and bond with the aggregate to form a rigid interlocking structure. Hydration can continue for years, but much of the ultimate strength will be reached within 28 days. Hydration is a sensitive chemical process, and typically, any admixtures used to accelerate the hydration process will reduce durability, and their use should be considered carefully or avoided.

#### Stress Distribution/Load Related Deterioration

PCC (rigid) and asphalt (flexible) pavements differ in the way loads are distributed. A concrete slab resists bending and transfers loads evenly, an asphalt pavement is designed to bend, and gradually spreads loads over wider areas. Rutting is a subgrade failure caused by a compressive yielding of the subgrade.

Load-related cracks can start at the top or bottom of a pavement section. In asphalt sections, load-related (fatigue) cracks start at the bottom. If a load-related crack reaches the surface, it usually indicates significant structural deficiency. In PCC pavement, corner breaks are caused by top tension, and the crack propagates downward. Mid-slab LTD cracks are examples of bottom tension.

Spalls can be caused by either wheel loads or environmental factors, anytime there is movement between adjacent slabs. If a small rock is allowed into a joint, a differential movement between adjacent slabs can cause a spall. Spalling can be minimized by keeping joint and crack sealant intact.




Figure 1. Pavement failure.

#### **Points to Remember**

#### Pavement wears out.

The longer a pavement remains in service, the greater the effort needed to keep it in service. A good maintenance and repair program will increase service life significantly, but cannot be expected to extend service life indefinitely.

#### Pavement moves.

Pavement moves in response to temperature changes. Transverse cracks can vary from nearly closed in the summer to open an inch or more in winter. This movement cannot be prevented. It must be understood and provided for during design and construction. The changing crack widths will dictate the reservoir size required for sealant. Measure cracks at their widest and narrowest states, then prepare adequate (½ - 1½ inch) sealant reservoirs for crack sealing projects.

# Longitudinal joints and cracks are important.

The most important reason for sealing cracks is to deny surface water access to the pavement and subgrade. Most water drains from centerline to shoulders. Longitudinal cracks, which run parallel to the centerline provide the greatest potential to divert water into the pavement structure, and must be sealed.

## Sealing is not always the best answer.

The FAA maximum allowable open trench width on aircraft movement areas is three-inches; therefore, any crack wider than three-inches should be patched. A severe spall or a crack that has settled below the pavement elevation indicates a failure. If the pavement has disintegrated to the point that aggregate interlock is lost, sealant alone will not be sufficient, and patching should be considered.

# Maintenance and repairs must be done correctly.

To achieve optimum results from repairs, proper preparation, use of quality materials, and proper application are essential. Any shortcuts will reduce the quality and effectiveness of the repairs. A rule of thumb is that proper maintenance will last twice as long as an unprepared area. Good maintenance takes time and deserves high-quality materials.

#### Schedule maintenance and repair activities carefully.

Any pavement defect can be corrected. Concentrate on repairs that are cost-effective, operationally important, and that extend service life. Some surface blemishes can be ignored safely, and many structural problems are beyond economical correction. When future rehabilitation is imminent, maintenance activities should be limited to only those that ensure continued safety and minimize foreign object damage (FOD) potential.

#### **Equipment**

Many excellent pavement repair and sealing products are available. Specialized tools and equipment help ensure quality repairs. This section reviews equipment compatible with airport needs.

#### **Air Compressor**

Used to remove sand and debris from prepared cracks and joints, the compressor should have a sustained capacity of 120 cubic feet per minute with a nozzle velocity of 100 psi. Trailer-mounted compressors typically have capacities in this range.

## **Concrete Saw**

A saw capable of making a minimum 3-inch deep cut is required. The saw should be capable of making cuts in asphalt or concrete. Gasoline-powered 5-25 hp wheel mounted saws typically are preferred for this type of work, but electric and pneumatic tools are also available.

## **Heating Kettle**

Applying sealant is the most time-consuming operation, and a sealing machine with heating and pressure application capabilities is a critical item in a sealing program. The capacity of the sealing equipment dictates the rate at which a crew progresses. For large sealing projects, a minimum 100 gallons/per hour sustained capacity is recommended. The unit should be a double boiler type, with mechanical agitators or continuous recirculation.

#### Router

A concrete saw can be used to prepare joints, but for random cracking, a mechanical router with a vertical impact mechanism is preferred. When cracks are being routed, this activity will dictate speed of the crew. Crack routers in the 25hp range are commonly used and are available from a variety of manufacturers.

#### Sand Cleaner

A sand blaster helps to clean loose particles and dust from prepared cracks. The unit must have sufficient force to expose fresh, vital pavement to bond with sealant and patching materials.

## **Vibratory Roller or Plate Compactor**

Required to properly compact plant mixed and packaged patching materials. Small rollers are best for pothole type applications, plate compactors are best for large areas.

## Other Equipment

Other general use equipment that can be helpful in a maintenance program includes bucket loaders, dump trucks, water tanks, and a power sweeper unit.

#### **Materials**

Pavement repair materials are constantly being introduced and improved. This section provides information on products compatible with airport needs.

#### Joint and Crack Sealer

Hot poured, pressure injected, polymeric rubberized asphalt sealant meeting ASTM D3405 specifications is suitable for most joint and crack sealing requirements. This product is relatively inexpensive, durable, and suitable for both PCC and asphalt pavements. Other, more expensive, hot applied sealants that promise longer life are being developed for specialty applications, and twin component cold applied sealants, similar to URASEAL 200, have also been used with success. Contact your local distributor.

#### Flexible Pavement Patch

Long-term patches should be made with a high-quality plant mixed hot asphalt having a ¾-inch maximum aggregate size and meeting FAA P401, or highest quality highway specifications. High-performance plant mixed cold patching products that can be stockpiled on-site have been developed. Low-quality packaged materials available from local hardware type stores should be avoided and only be used for temporary patches that maintain safety and service.

## **PCC Pavement Patch**

Permanent patches in PCC pavement should be made with a minimum 6-bag mix of hi-early air-entrained cement with 1-inch maximum size aggregate. Concrete should have zero slump and a coarse texture. As with asphalt patches, low-quality packaged materials should only be used as temporary patches to maintain safety and service until a more permanent repair can be made.

## **Techniques**

## **Crack Sealing**

- Cracks over ¼ inches wide should be sealed. Cracks wider than 3 inches should be patched.
- Sealant depth above the backer rope should be equal to the width of the reservoir, or as recommended by the manufacturer.
- Routed cracks should be sand blasted, to prepare the vertical edges for bonding with the sealant. Clean cracks with compressed air prior to sealing.
- Backing material should always be placed into the cracks. Commercial products are available, and several sizes of rope should always be available to accommodate various crack sizes.
- Apply sealant after placing the backer rope. Follow the manufacturer's instructions. Sealant should be applied to within ¼ inch of the pavement surface.
- The final activity is to clean the surrounding pavement areas. A vacuum sweeper works well for this. Allow the sealant time to set, before using a broom.




Figure 2. Crack sealing.

## Note:

The previous crack sealing technique is meticulous in its design and procedure. It has a proven record of performance. Using backer rope forces the sealant into a predictable shape—narrow in the center and wide on the sides. This sealant profile allows the sealant to firmly bond with the vertical edges, yet stretch easily with pavement movement. In an effort to minimize labor requirements and reduce crack-sealing costs, an alternative procedure, the overband technique, is presented below. This procedure can produce good results for up to 5 years.

Always remember that, within reasonable limits, thinner sealant material will stretch more easily with the pavement movement, and stay bonded longer.

## **Overband Technique**


A latex modified, fiber reinforced, asphalt cement sealant using the techniques outlined below.

#### Material

- Blend grade 20 or equivalent asphalt cement with latex rubber at 5 percent by weight of asphalt.
- Again, at 5 percent by weight of asphalt, add polyester fibers into agitator tank.
- Maintain blended asphalt temperature at least 20 degrees below flash point.
- Continuously recycle hot blended asphalt through pumps and hoses when heating kettle is in standby mode.

# **Application**

- Sealant should be applied to dry pavement, with ambient temperatures above 40 degrees.
- Cracks should be sand cleaned and blown free of debris immediately before sealing.
- Application of sealant immediately follows cleaning of the crack.
- Sealant should be pressure applied from a wand-type applicator with a special "overband" nozzle.
- Seat the sealant with a steel-wheeled roller immediately after placement.
- In wider cracks, a backer rope is recommended to limit material quantities required.







Figure 3. Overband sealing.

## Patching (Asphalt Pavement)

Cracks wider than 3 inches should be patched. Cracks with secondary cracking and vertical movement should also be patched. Failed existing patches should be replaced. Patching can also repair small areas of alligator cracking and rutting. A patch differs from sealant in that it restores load-bearing capacity. Therefore, it must be constructed carefully to distribute stresses evenly and perform as an integral piece of the surrounding pavement. The patch must be wide enough to ensure that it bonds to fresh, vital pavement on all sides, and deep enough to reach fresh underlying layers, but never less than 3 inches.

- Examine the distressed area and mark the patch outline. This examination may require a pick or chisel to test the pavement integrity in and around the distressed area.
- The patch area should be cut out with a vertical saw cut not less than 3 inches deep.
- The enclosed pavement should then be removed, leaving the vertical sawed edges undamaged and providing a relatively even, flat floor at the appropriate depth.
- The sides and bottom should be sand cleaned and blown out with compressed air

- The sides and bottom should then be painted with a rapid curing asphalt tack coat. The tack coat may be sprayed on or applied with a brush or rag. Care should be taken to achieve complete coverage without allowing excess material to "pool" on the bottom.
- Allow tack coat to cure (about 2 to 4 hours) until it reaches a gummy consistency, which readily retains the impression of a fingerprint.
- Place hot mixed asphalt concrete evenly and mound slightly above surrounding pavement. Allow approximately ¼ inch of compaction for each inch of patch depth.
- Compact in place with vibratory roller or plate compactor. Asphalt concrete should not be compacted in layers greater than 6 inches. If patch depth is greater than 6 inches, asphalt concrete should be placed and compacted in successive layers.
- In deep, narrow patches such as at joint reflective cracks, a sand asphalt mix may be required in lower layers to allow movement and prevent bridging the adjacent slabs.
- Considerable judgment is required in placing the asphalt concrete to achieve a fully compacted patch without creating a bump or depression. The ¼ inch per inch factor is a rule of thumb. Actual compression will vary with the mix. Experimentation and experience are required to achieve optimum results.







Figure 4. AC patch.

## Patching (PCC)

The technique outlined here simulates a thin bonded PCC overlay. This procedure has been proven in service throughout the country.

- Examine the distressed area and mark the patch outline. This examination may require a pick or chisel to test pavement integrity in and around the distressed area.
- Saw cut the area to a depth of 2 inches. The enclosed area is then chipped or jack hammered to solid pavement, but not less than a 2-inch nominal depth.
- The sides and bottom are sand cleaned and air-blasted to expose vital, clean concrete.
- A 25 percent solution of muriatic acid is applied to all exposed surfaces within the patch.
- The muriatic acid solution is thoroughly flushed from the patch area with water.
- Compressed air is used to remove excess water from the area, but exposed concrete must be maintained in a moist condition.
- The sides and bottom of the area are then coated with approximately a 1/16-inch layer of cement grout applied at the consistency of paste. The grout acts as an adhesive to bond the fresh concrete to existing concrete.
- If the patch is adjacent to joints, the continuity of the joint must be maintained by placing inserts approximately the shape of the desired joint against the wall of the patch.
- Before concrete grout begins to dry, concrete is placed in the patch area and is compacted into position with hand tampers or a vibrating plate tamper.
- When the patch has been struck to the proper slope and elevation, a surface texture is applied to approximate the texture of adjacent pavement.
- Joint edges may be edged slightly to remove sharp edges. The patch should be covered with polyethylene or sprayed with a curing compound.
- Clean the surrounding pavement before concrete spillover has a chance to set up.
- The patch may be open to traffic in 72 hours.






Figure 5. PCC patch.

## Joint Repair (PCC)

Seal joints in PCC pavement when existing sealant has deteriorated to a degree that allows water and incompressibles to enter the joint. Hairline cracks are not yet candidates for sealing.

- Rout a reservoir for the sealant. Sealant reservoir should be ½ inch wide and 1 inch deep.
- For cracks wider than ½ inch, the reservoir should be ¼ inch wider than the crack. Depth should be such that sealant above the backer rope is at most equal to reservoir width, or as recommended by manufacturer.
- Routed cracks should be sand cleaned, using fine sand at reduced pressure. Proper cleaning will expose fresh, vital pavement on the vertical crack edge.
- Immediately prior to sealing, cracks should be cleaned with compressed air. Ensure that all
  sand, debris, and incompressibles are removed from the crack. A small hand-held hook or
  plowing tool may be needed to dislodge some particles. Water cleaning is not recommended,
  simply because the drying time delays the sealing operation.
- After cleaning with compressed air, a backing material should be placed into the crack. The backer rope may be any compressible substance compatible with bituminous sealant material that will wedge into cracks at a designated depth and support the sealant. Several sizes should be immediately available in the field to accommodate various crack sizes.
- Sealant should be pressure applied with a wand type applicator to within ¼ inch of the pavement surface. Follow the equipment manufacturer's instructions.
- The final activity is to clean the surrounding pavement area. A vacuum sweeper works well. Brooms should not be used until the sealant has taken an initial set.



Typical joint with deficient sealant and a collection of debris & incompressibles.

Rout out old sealant, debris and incompressibles. Clean joint sides to expose fresh, clean concrete and stone. Retain existing reservoir shape.




Figure 6. PCC joint/crack repair.

Table 1. Maintenance and "drive by" inspection log.

Inspection Date	Inspector	Pavement location (branch/section)	Change in condition (new distress type, increased quantity or severity)	Maintenance performed since last inspection