

CIP 8Y5 -Clarissa Municipal Airport

State FY	Fed FY	Description	Funding Rates			2012 -2017					Estimated Construction Start Date	
			FAA	St	Mun	Project Cost	FAA Funding	State Funding	Local Funding	Other Programs		
2012		NO PROJECTS PROGRAMMED	0	0	0						0	6/1/2012
2013		No Projects Programmed	0	0	0						0	6/1/2013
2014		NO PROJECTS PROGRAMMED	0	0	0						0	6/1/2014
2015		NO PROJECTS PROGRAMMED	0	0	0						0	6/1/2015
2016		NO PROJECTS PROGRAMMED	0	0	0						0	6/1/2016
2017		NO PROJECTS PROGRAMMED	0	0	0						0	6/1/2017
			Totals								0	

Summary for Airport = Clarissa Municipal Airport (6 detail records)

5010 Inspection Remarks:

Last Inspection Year: 2010

Remark Key	Remark	Runway
B110-3	Rwy 10, crops 30 ft from end.	
A42	Rwy 10/28 Marked with Yellow Cones.	RWY 10
B110-1	No fence, toilet, or phone or map.	
B57	Approach to Rwy 28 obstructed by trees. Lower by 15 ft.	
B57	Rwy 28:Trees +45, 515 fm end, 170L, 11:1. Lower by 20 ft.	RWY 28
B57	Rwy 28: trees +45, 750 fm end, 180R, 16:1. Lower by 8 ft.	
B110-2	Only 1 tiedown marked. Three required.	
B110-4	Windsock faded.	
A110-1	Rwy 10/28 not plowed winter months.	

Monday, November 21, 2011