

## CIP D14 -Fertile Municipal Airport

State FY	Fed FY	Description	Funding Rates			2012 -2017					Estimated Construction Start Date
			FAA	St	Mun	Project Cost	FAA Funding	State Funding	Local Funding	Other Programs	
2013		improve drainage in approaches for access	0	80	20	42,786	0	34,229	8,557	0	7/1/2012
2014		MIRLs, etc. for GPS approach	0	80	20	125,000	0	100,000	25,000	0	7/2/2013
2015		Resurface & Widen Rwy 14/32 (3000')	0	80	20	330,000	0	264,000	66,000	0	7/1/2014
2015		Rehabilitate Apron	0	80	20	70,000	0	56,000	14,000	0	7/5/2014
2016		Arrival/Departure Building	0	80	20	120,000	0	96,000	24,000	0	7/3/2015
			<b>Totals</b>			<b>687,786</b>	<b>0</b>	<b>550,229</b>	<b>137,557</b>	<b>0</b>	

Summary for Airport = Fertile Municipal Airport (5 detail records)

# CIP D14 -Fertile Municipal Airport

2012 -2017

State Fed  
FY FY Description

Funding Rates  
FAA St Mun

Project  
Cost

FAA  
Funding

State  
Funding

Local  
Funding

Other  
Programs

Estimated  
Construction  
Start Date

## 5010 Inspection Remarks:

Last Inspection Year: 2009

Remark Key	Remark	Runway
A81	ACTVT LIRL RY 14/32; VASI RYS 14 & 32 - CTAF.	
A110-1	Beware of auto traffic on taxiways.	
B110-2	Bulletin Board locked in Elec Bldg	
A70	100LL self serve fuel available 24 hr with credit card.	
B110-3	No Toilet.	
B80	Rotating Beacon flash rate 12FPM. AC150/5345-12E should be 22-26FPM rate.	
B40	Runway lights leaning, need to be straightened.	
B110	Rwy 14; Runway Threshold / End Lights, 1 light white, needs to be green and red.	
A42	Rwy 14/32 bleached.	
B42	Rwy bleached and markings faded.	
B70	No fire extinguisher.	
B80	Old rotating beacon tower needs to be maintained or removed.	
B83	Windsock on old rotating beacon tower needs to be maintained or removed.	
B43	Rwy 14; VASI pad 6" off the ground. Should be no more than 1".	
A33	Rwy 14/32 markings faded.	