

CIP 13Y -Littlefork Municipal Airport - Hanover Airport

2012 -2017

State FY	Fed FY	Description	Funding Rates			Project Cost	FAA Funding	State Funding	Local Funding	Other Programs	Estimated Construction Start Date
			FAA	St	Mun						
2013		Airport Security Signs	0	70	30	3,000	0	2,100	900	0	7/1/2012
			Totals			3,000	0	2,100	900	0	

Summary for Airport = Littlefork Municipal Airport - Hanover Airport (1 detail record)

5010 Inspection Remarks:

Last Inspection Year: 2011

Remark Key	Remark	Runway
A110-01	Airport Closed winter months.	
B110-01	No AD building, phone, map, rules, toilet	
B110-02	Brush in primary surface, grass up to cones.	
A110-02	Ultralights on & invof airport.	
A042	RWY 09/27 Marked with yellow cones.	RWY 09
A110-03	FAA antenna 25feet tall 490 feet from RWY 27 end 367feet left.	
B57	Rwy 9: 19:1for trees should be 20:1. Trees penetrate approach surface by 3 feet.	
B110-03	No trespassing and ramp signage faded.	