Hector - 1D6

Hector Municipal Airport

Associated City: Hector, MN
MnDOT Classification: Intermediate Airport
NPIAS Airport: Yes

State Aviation System Plan Facility Needs by Term

Airside Facilities:	Base Year 2010	Short Term 2012 - 2015	Mid-Term 2016 - 2020	Long Term 2021 - 2030
Runway Extension (Feet)	2,776	-	-	-
Runway Widening (Feet)	50	25	-	-
Parallel Txy/Turnaround	Turnaround	-	-	-
Runway Lighting	LIRLs	-	-	-
Weather Reporting	No	-	-	-
Fuel Capacity (Gal.)	500	-	-	-
Transient Apron (S.Y.)	1,240	15,000	-	3,000
Based Apron (S.Y.)	1,000	-	-	-
Tie Downs (Each)	4	-	-	-
Navigational Systems:				
Primary R/W Approach Type	Visual/Basic NPI	Enhanced NPI w/Vertical	-	-
Wind Cone	Yes	-	-	-
Rotating Beacon	No	Yes	-	-
PAPIs / VASIs	None	PAPIs	-	-
REILs	No	Yes	-	-
Approach Lighting	None	-	-	-
Airport Buildings:				
Commercial Terminal	No	-	-	-
GA/Administration	Yes	-	-	-
Restroom	Yes	-	-	-
T-Hangar (Units)	7	8	0	0
Conventional Hangar (Units)	24	0	1	1
Landside Facilities:				
Automobile Parking (Spaces)	8	50	-	-
Perimeter Fencing	Partial	-	-	-

Notes: Data provided is for system planning purposes and shall not be used to justify individual improvement projects.
R/W = Runway, NP = Not Provided.

Source: MnDOT Office of Aeronautics 2011 Inventory Survey and Airport Database & HNTB Analysis.