



Publication No. FHWA NHI 12-049  
October, 2002  
Revised December, 2006  
Revised February, 2012

U.S. Department  
of Transportation

**Federal Highway  
Administration**

---

# Bridge Inspector's Reference Manual



***BIRM***  
**Volume 1**



**NATIONAL HIGHWAY INSTITUTE**

*Training Solutions for Transportation Excellence*





<b>1. Report No.</b> FHWA NHI 12-049	<b>2. Government Accession No.</b>	<b>3. Recipient's Catalog No.</b>
<b>4. Title and Subtitle</b>  Bridge Inspector's Reference Manual (BIRM)		<b>5. Report Date</b> October 2002/November 2006/February 2012
<b>7. Author (s)</b> Thomas W. Ryan, P.E., J. Eric Mann, P.E., Zachary M. Chill, E.I.T., Bryan T. Ott		<b>6. Performing Organization Code</b>  <b>8. Performing Organization Report No.</b> 23104 / 106915-HRS/118802
<b>9. Performing Organization Name and Address</b> Michael Baker, Jr., Inc. Airside Business Park, 100 Airside Drive Moon Township, PA 15108		<b>10. Work Unit No. (TRAIS)</b>  <b>11. Contract or Grant No.</b> DTFH61-06-T-00009-T09-B07
<b>12. Sponsoring Agency Name and Address</b> Federal Highway Administration National Highway Institute (HNHI-10) 1300 N. Courthouse Road Arlington, Virginia 22201		<b>13. Type of Report and Period Covered</b> Final Manual: October 2002  Revised Manual: December 2006  Revised Manual: February 2012
<b>15. Supplementary Notes</b> Baker Principle Investigator: Raymond A. Hartle, P.E. (2002, 2006) Baker Principle Investigator: Mary P. Rosick, P.E. (2012) Baker Project Manager: Thomas W. Ryan, P.E. (2002, 2006, 2012) FHWA Contracting Officer's Technical Representative: Larry E. Jones (2002, 2006) FHWA Contracting Officer's Technical Representative : Louisa M. Ward, E.I.T. (2012) Team Leader, Technical Review Team: John M. Hooks, P.E. (2002) Team Leader, Technical Review Team: Thomas D. Everett, P.E (2006) Team Leader, Technical Review Team: Gary E. Moss, P.E. (2012)		<b>14. Sponsoring Agency Code</b>
<b>16. Abstract</b> This document, the <i>Bridge Inspector's Reference Manual (BIRM)</i> , is a comprehensive manual on programs, procedures, and techniques for inspecting and evaluating a variety of in-service highway bridges. It is intended to replace the <i>BITM 90</i> which was first published in 1991 to assist in training highway personnel for the new discipline of bridge safety inspection. <i>BITM 90</i> replaced <i>BITM 70</i> which had been in use for 20 years and has been the basis for several training programs varying in length from a few days to two weeks. Comprehensive supplements to <i>BITM 70</i> have been developed to cover inspection of fracture critical bridge members, and culverts are now covered in the <i>BIRM</i> .  The <i>BIRM</i> is a revision and upgrading of the previous manual. Improved Bridge Inspection techniques are presented, and state-of-the-art inspection equipment is included. New or expanded coverage is provided on culverts, fracture critical members, cable-stayed bridges, prestressed segmental bridges, moveable bridge inspection, underwater inspection, and non-destructive evaluation and critical findings.  A three-week comprehensive training program on bridge inspection, based on the <i>BIRM</i> , has been developed. The program consists of a one-week course, FHWA-NHI Course No 130054, "Engineering Concepts for Bridge Inspectors," and a two-week course, FHWA-NHI Course No 130055, "Safety Inspection of In-Service Bridges." Together, these two courses meet the definition of a comprehensive training program in bridge inspection as defined in the National Bridge Inspection Standards. Successful completion of the prerequisite FHWA-NHI Course No. 130054 is required to register for this FHWA-NHI 130055 Course. FHWA-NHI Course No. 130101, Introduction to Safety Inspection of In-Service Bridges, web based training or FHWA-NHI Course No. 130101a web based training assessment may be substituted for FHWA-NHI Course No. 130054.  The catalogue for NHI Courses including the schedule, description and course request form can be found on the National Highway Institute web site: <a href="http://www.nhi.fhwa.dot.gov">www.nhi.fhwa.dot.gov</a>		

<b>17. Key Words</b> Bridge Inspection, Bridge Evaluation, Element Level Evaluation, Component Rating, Culvert Inspection, Critical Findings, Fracture Critical Members, Underwater Inspection		<b>18. Distribution Statement</b> This report is available to the public from the National Technical Information Service in Springfield, Virginia 22161 and from the Superintendent of Documents, U.S. Government Printing Office, Washington, D.C. 20402.	
<b>19. Security Classif. (of this report)</b> Unclassified	<b>20. Security Classif. (of this page)</b> Unclassified	<b>21. No. of Pages</b> 1020	<b>22. Price</b>

Form DOT F 1700.7 (8-72)

Reproduction of completed page authorized

## ACKNOWLEDGEMENTS

We would like to express appreciation to the following individuals and organizations who contributed to the development and review of the BITM 90 Manual program:

Applied Science Associates, Inc.  
Association of Diving Contractors, Inc. (Messrs. Castle, Harter, Hazelbaker, Hux, Maggard, McGeehan, and McGovern)  
R. Richard Avent, Ph.D., P.E. (Louisiana State University)  
William D. Domico, P.E. (Figg Engineering Group)  
John W. Fisher, Ph.D. (Lehigh University)  
Robert J. Hoyle, Jr., P.E., S.E.  
Heinz P. Koretzky, P.E. (Pennsylvania DOT-Retired)  
KTA-Tator, Inc.  
John A. Schultz, Jr., S.E. (Hazelet and Erdal, Inc.)  
Frieder Seible, Ph.D., P.E. (SEQAD Consulting Engineers, Inc.)  
Daryl B. Simons, Ph.D., P.E. (Simons and Associates, Inc.)  
Robert K. Simons, Ph.D., P.E. (Simons and Associates, Inc.)

Special thanks to the FHWA Technical Review Committee and NHI Instructional Development Review Committee:

John Bargo (2006)	Ken Foster (2011)	Claude Napier (2006)
Steve Belcher (2002)	Carl Highsmith (2006)	Larry O'Donnell (2006, 2011)
Douglas Blades (2011)	John Hooks (2002)	Jorge Pagan (2002)
Gary Bowling (2011)	Calvin Karoer (2006)	Meredith Perkins (2011)
Barry Brecto (2002, 2011)	Greg Kolle (2006)	George Romack (2002)
Eric Brown (2011)	Joe Krolak (2006)	Luc Saroufim (2006)
Shay Burrows (2006)	Gerald LaCosta (2011)	Lou Triandafilou (2002)
Milo Cress (2002)	Everett Matias (2006)	John Thiel (2002)
Shelia Dawadi (2002)	Gary Moss (2006)	Glenn Washer (2002)
Doug Edwards (2006)	Raymond McCormick (2002)	Robert Zaffetti (2011)
Thomas Everett (2006, 2011)	Curtis Monk (2002)	

We would also like to thank the following individuals and organizations for providing information or visual aids for the BITM 90 Manual:

Kathleen H. Almand (American Iron and Steel Institute)  
American Traffic Safety Services Association  
Bridge Grid Flooring Manufacturers Association  
The D.S. Brown Company  
Concrete Reinforcing Steel Institute  
Cosmec, Inc.  
Barry Dickson (West Virginia University)  
Dynamic Isolation Systems, Inc.  
Carl Edwards (Maine DOT)  
Elgard Corporation  
Thomas D. Everett (FHWA)  
Exodermic Bridge Deck Institute  
Paul S. Fisk (NDT Corporation)  
Geerhard Haaijer, Ph.D. (American Institute of Steel Construction, Inc.)  
John M. Hanson, Ph.D. (Wiss, Janney, Elster Associates, Inc.)  
Richard P. Knight, P.E. (Dynamic Isolation Systems, Inc.)  
Louisiana Department of Transportation and Development  
Merriman, Inc.  
William R. Mochel, P.E. (Illinois Department of Transportation)  
Pennsylvania Department of Transportation  
Professional Service Industries, Inc.-Pittsburgh Testing Laboratory Division  
Schupack Suarez Engineers, Inc.  
David Severns, P.E. (Nevada DOT)  
Paul W. Verrill (Maine Department of Transportation)  
Watson Bowman Associates, Inc.  
Stewart C. Watson (Stafford/Watson, Inc.)  
Western Wood Structures, Inc.  
Weston Geophysical Corporation

We would like to acknowledge the contributing staff for the BITM 90 and FHWA-NHI 130055:

Edward J. Adamczyk, P.E.  
William J. Amrhein, P.E.  
Dennis R. Baughman, P.E.  
Robert W. Bondi, P.E.  
Jeffery J. Campbell, P.E.  
Paul L. Coblentz, P.E.  
Raymond A. Hartle, P.E.  
Thomas L. Hooks  
Stephen J. Hoyer  
Gerald J. Jones, P.E.  
Guy R. Lang,  
Karen G. Lucci  
Thomas P. Macioce  
Susan Maines-Harrison  
J. Eric Mann, P.E.  
Robert M. Marchak  
Kelly A. McKindley  
Krisha E. Medziuch  
Edward E. Moldovan  
Charles L. Molnar  
Charles M. Schubert, P.E.  
J. Keith Seibel  
John J. Tkacs, P.E.  
Terrence J. Tiberio, P.E.  
Scott D. Vannoy, P.E.  
Terri A. Vojnovich  
Ruth Williams  
Kenneth E. Wilson, III, P.E., S.E.  
Lori A. Wittebort

We would like to acknowledge the contributing staff for the 2006 BIRM and FHWA-NHI 130055:

Justin W. Bouscher, P.E.  
Jeffery J. Campbell, P.E.  
Karen D. Ciccone  
Maureen Kanfoush  
J. Eric Mann, P.E.  
Linda Montagna  
Joseph R. McKool, P.E.  
Mary P. Rosick, P.E.  
Scott D. Vannoy, P.E.  
Kenneth E. Wilson III, P.E., S.E.

We would like to acknowledge the contributing staff for the 2002 BIRM and FHWA-NHI 130055:

Justin W. Bouscher, P.E.  
Jeffery J. Campbell, P.E.  
David Chang  
Karen D. Ciccone  
Maureen Kanfoush  
Linda M. Ketterer  
Patrick A Leach, P.E.  
Guy R. Lang, P.E.  
J. Eric Mann, P.E.  
Linda Montagna  
Sean A. Patrick, P.E.  
Timothy J. Pintar, P.E.  
Heather Proya  
James Shroads  
William B. Sosko  
Jorge M. Suarez, P.E.  
Scott D. Vannoy, P.E.  
Laura E. Volle  
Kenneth E. Wilson, III, P.E., S.E.

We would like to acknowledge the contributing staff for the 2012 BIRM and FHWA-NHI 130055:

Sherry Bellan  
Jeffrey J. Campbell, P.E.  
Karen D. Ciccone  
Phillip Fish, P.E.  
Sandy F. Fitzgerald  
Ronald Gardner, P.E.  
Tom Harvey  
Edward Hilker  
Maureen Kanfoush  
Matthew A. Kolis, P.E.  
Guy R. Lang, P.E.  
Carol A. Palmer  
Heather Partozoti  
Eric Schiemer  
Richard M. Schoedel, P.E.  
Weidong Shi  
Scott D. Vannoy, P.E.  
Kenneth E. Wilson III, P.E., S.E.



Publication No. FHWA NHI 12-050  
October, 2002  
Revised December, 2006  
Revised February, 2012

U.S. Department  
of Transportation

**Federal Highway  
Administration**

---

# Bridge Inspector's Reference Manual



***BIRM***  
**Volume 2**



**NATIONAL HIGHWAY INSTITUTE**

*Training Solutions for Transportation Excellence*







<b>1. Report No.</b> FHWA NHI 12-050	<b>2. Government Accession No.</b>	<b>3. Recipient's Catalog No.</b>
<b>4. Title and Subtitle</b>  Bridge Inspector's Reference Manual (BIRM)		<b>5. Report Date</b> October 2002/November 2006/February 2012
<b>7. Author (s)</b> Thomas W. Ryan, P.E, J. Eric Mann, P.E., Zachary M. Chill, E.I.T., Bryan T. Ott		<b>6. Performing Organization Code</b>  <b>8. Performing Organization Report No.</b> 23104 / 106915-HRS/118802
<b>9. Performing Organization Name and Address</b> Michael Baker, Jr., Inc. Airside Business Park, 100 Airside Drive Moon Township, PA 15108		<b>10. Work Unit No. (TRAIS)</b>  <b>11. Contract or Grant No.</b> DTFH61-06-T-00009-T09-B07
<b>12. Sponsoring Agency Name and Address</b> Federal Highway Administration National Highway Institute (HNHI-10) 1300 N. Courthouse Road Arlington, Virginia 22201		<b>13. Type of Report and Period Covered</b> Final Manual: October 2002  Revised Manual: December 2006  Revised Manual: February 2012
<b>15. Supplementary Notes</b> Baker Principle Investigator: Raymond A. Hartle, P.E. (2002, 2006) Baker Principle Investigator: Mary P. Rosick, P.E. (2012) Baker Project Manager: Thomas W. Ryan, P.E. (2002, 2006, 2012) FHWA Contracting Officer's Technical Representative: Larry E. Jones (2002, 2006) FHWA Contracting Officer's Technical Representative : Louisa M. Ward, E.I.T. (2012) Team Leader, Technical Review Team: John M. Hooks, P.E. (2002) Team Leader, Technical Review Team: Thomas D. Everett, P.E (2006) Team Leader, Technical Review Team: Gary E. Moss, P.E. (2012)		<b>14. Sponsoring Agency Code</b>
<b>16. Abstract</b> <p>This document, the <i>Bridge Inspector's Reference Manual (BIRM)</i>, is a comprehensive manual on programs, procedures, and techniques for inspecting and evaluating a variety of in-service highway bridges. It is intended to replace the <i>BITM 90</i> which was first published in 1991 to assist in training highway personnel for the new discipline of bridge safety inspection. <i>BITM 90</i> replaced <i>BITM 70</i> which had been in use for 20 years and has been the basis for several training programs varying in length from a few days to two weeks. Comprehensive supplements to <i>BITM 70</i> have been developed to cover inspection of fracture critical bridge members, and culverts are now covered in the <i>BIRM</i>.</p> <p>The <i>BIRM</i> is a revision and upgrading of the previous manual. Improved Bridge Inspection techniques are presented, and state-of-the-art inspection equipment is included. New or expanded coverage is provided on culverts, fracture critical members, cable-stayed bridges, prestressed segmental bridges, moveable bridge inspection, underwater inspection, and non-destructive evaluation and critical findings.</p> <p>A three-week comprehensive training program on bridge inspection, based on the <i>BIRM</i>, has been developed. The program consists of a one-week course, FHWA-NHI Course No 130054, "Engineering Concepts for Bridge Inspectors," and a two-week course, FHWA-NHI Course No 130055, "Safety Inspection of In-Service Bridges." Together, these two courses meet the definition of a comprehensive training program in bridge inspection as defined in the National Bridge Inspection Standards. Successful completion of the prerequisite FHWA-NHI Course No. 130054 is required to register for this FHWA-NHI 130055 Course. FHWA-NHI Course No. 130101, Introduction to Safety Inspection of In-Service Bridges, web based training or FHWA-NHI Course No. 130101a web based training assessment may be substituted for FHWA-NHI Course No. 130054.</p> <p>The catalogue for NHI Courses including the schedule, description and course request form can be found on the National Highway Institute web site: <a href="http://www.nhi.fhwa.dot.gov">www.nhi.fhwa.dot.gov</a></p>		

<b>17. Key Words</b> Bridge Inspection, Bridge Evaluation, Element Level Evaluation, Component Rating, Culvert Inspection, Critical Findings, Fracture Critical Members, Underwater Inspection		<b>18. Distribution Statement</b> This report is available to the public from the National Technical Information Service in Springfield, Virginia 22161 and from the Superintendent of Documents, U.S. Government Printing Office, Washington, D.C. 20402.	
<b>19. Security Classif. (of this report)</b> Unclassified	<b>20. Security Classif. (of this page)</b> Unclassified	<b>21. No. of Pages</b> 984	<b>22. Price</b>

Form DOT F 1700.7 (8-72)

Reproduction of completed page authorized

## ACKNOWLEDGEMENTS

We would like to express appreciation to the following individuals and organizations who contributed to the development and review of the BITM 90 Manual program:

Applied Science Associates, Inc.  
Association of Diving Contractors, Inc. (Messrs. Castle, Harter, Hazelbaker, Hux, Maggard, McGeehan, and McGovern)  
R. Richard Avent, Ph.D., P.E. (Louisiana State University)  
William D. Domico, P.E. (Figg Engineering Group)  
John W. Fisher, Ph.D. (Lehigh University)  
Robert J. Hoyle, Jr., P.E., S.E.  
Heinz P. Koretzky, P.E. (Pennsylvania DOT-Retired)  
KTA-Tator, Inc.  
John A. Schultz, Jr., S.E. (Hazelet and Erdal, Inc.)  
Frieder Seible, Ph.D., P.E. (SEQAD Consulting Engineers, Inc.)  
Daryl B. Simons, Ph.D., P.E. (Simons and Associates, Inc.)  
Robert K. Simons, Ph.D., P.E. (Simons and Associates, Inc.)

Special thanks to the FHWA Technical Review Committee and NHI Instructional Development Review Committee:

John Bargo (2006)	Ken Foster (2011)	Claude Napier (2006)
Steve Belcher (2002)	Carl Highsmith (2006)	Larry O'Donnell (2006, 2011)
Douglas Blades (2011)	John Hooks (2002)	Jorge Pagan (2002)
Gary Bowling (2011)	Calvin Karoer (2006)	Meredith Perkins (2011)
Barry Brecto (2002, 2011)	Greg Kolle (2006)	George Romack (2002)
Eric Brown (2011)	Joe Krolak (2006)	Luc Saroufim (2006)
Shay Burrows (2006)	Gerald LaCosta (2011)	Lou Triandafilou (2002)
Milo Cress (2002)	Everett Matias (2006)	John Thiel (2002)
Shelia Dawadi (2002)	Gary Moss (2006)	Glenn Washer (2002)
Doug Edwards (2006)	Raymond McCormick (2002)	Robert Zaffetti (2011)
Thomas Everett (2006, 2011)	Curtis Monk (2002)	

We would also like to thank the following individuals and organizations for providing information or visual aids for the BITM 90 Manual:

Kathleen H. Almand (American Iron and Steel Institute)  
American Traffic Safety Services Association  
Bridge Grid Flooring Manufacturers Association  
The D.S. Brown Company  
Concrete Reinforcing Steel Institute  
Cosmec, Inc.  
Barry Dickson (West Virginia University)  
Dynamic Isolation Systems, Inc.  
Carl Edwards (Maine DOT)  
Elgard Corporation  
Thomas D. Everett (FHWA)  
Exodermic Bridge Deck Institute  
Paul S. Fisk (NDT Corporation)  
Geerhard Haaijer, Ph.D. (American Institute of Steel Construction, Inc.)  
John M. Hanson, Ph.D. (Wiss, Janney, Elster Associates, Inc.)  
Richard P. Knight, P.E. (Dynamic Isolation Systems, Inc.)  
Louisiana Department of Transportation and Development  
Merriman, Inc.  
William R. Mochel, P.E. (Illinois Department of Transportation)  
Pennsylvania Department of Transportation  
Professional Service Industries, Inc.-Pittsburgh Testing Laboratory Division  
Schupack Suarez Engineers, Inc.  
David Severns, P.E. (Nevada DOT)  
Paul W. Verrill (Maine Department of Transportation)  
Watson Bowman Associates, Inc.  
Stewart C. Watson (Stafford/Watson, Inc.)  
Western Wood Structures, Inc.  
Weston Geophysical Corporation

We would like to acknowledge the contributing staff for the BITM 90 and FHWA-NHI 130055:

Edward J. Adamczyk, P.E.  
William J. Amrhein, P.E.  
Dennis R. Baughman, P.E.  
Robert W. Bondi, P.E.  
Jeffery J. Campbell, P.E.  
Paul L. Coblenz, P.E.  
Raymond A. Hartle, P.E.  
Thomas L. Hooks  
Stephen J. Hoyer  
Gerald J. Jones, P.E.  
Guy R. Lang,  
Karen G. Lucci  
Thomas P. Macioce  
Susan Maines-Harrison  
J. Eric Mann, P.E.  
Robert M. Marchak  
Kelly A. McKindley  
Krisha E. Medziuch  
Edward E. Moldovan  
Charles L. Molnar  
Charles M. Schubert, P.E.  
J. Keith Seibel  
John J. Tkacs, P.E.  
Terrence J. Tiberio, P.E.  
Scott D. Vannoy, P.E.  
Terri A. Vojnovich  
Ruth Williams  
Kenneth E. Wilson, III, P.E., S.E.  
Lori A. Wittebort

We would like to acknowledge the contributing staff for the 2006 BIRM and FHWA-NHI 130055:

Justin W. Bouscher, P.E.  
Jeffery J. Campbell, P.E.  
Karen D. Ciccone  
Maureen Kanfoush  
J. Eric Mann, P.E.  
Linda Montagna  
Joseph R. McKool, P.E.  
Mary P. Rosick, P.E.  
Scott D. Vannoy, P.E.  
Kenneth E. Wilson III, P.E., S.E.

We would like to acknowledge the contributing staff for the 2002 BIRM and FHWA-NHI 130055:

Justin W. Bouscher, P.E.  
Jeffery J. Campbell, P.E.  
David Chang  
Karen D. Ciccone  
Maureen Kanfoush  
Linda M. Ketterer  
Patrick A. Leach, P.E.  
Guy R. Lang, P.E.  
J. Eric Mann, P.E.  
Linda Montagna  
Sean A. Patrick, P.E.  
Timothy J. Pintar, P.E.  
Heather Proya  
James Shroads  
William B. Sosko  
Jorge M. Suarez, P.E.  
Scott D. Vannoy, P.E.  
Laura E. Volle  
Kenneth E. Wilson, III, P.E., S.E.

We would like to acknowledge the contributing staff for the 2012 BIRM and FHWA-NHI 130055:

Sherry Bellan  
Jeffery J. Campbell, P.E.  
Karen D. Ciccone  
Phillip Fish, P.E.  
Sandy F. Fitzgerald  
Ronald Gardner, P.E.  
Tom Harvey  
Edward Hilker  
Maureen Kanfoush  
Matthew A. Kolis, P.E.  
Guy R. Lang, P.E.  
Carol A. Palmer  
Heather Partozoti  
Eric Schiemer  
Richard M. Schoedel, P.E.  
Weidong Shi  
Scott D. Vannoy, P.E.  
Kenneth E. Wilson III, P.E., S.E.

# BI

## **Bridge Inspector's Reference Manual**

**October, 2002  
Revised December, 2006  
Revised February, 2012**

**FHWA NHI Publication  
No. 12-049**

### **Volume 1**

# RM

## **Bridge Inspector's Reference Manual**

**October, 2002  
Revised December, 2006  
Revised February, 2012**

**FHWA NHI Publication  
No. 12-050**

### **Volume 2**



## Table of Contents

### TOPIC

- Chapter 1: Bridge Inspection Programs
- 1.1 History of the National Bridge Inspection Program
- 1.2 Responsibilities of the Bridge Inspector
- 1.3 Quality Control and Quality Assurance
  
- Chapter 2: Safety Fundamentals for Bridge Inspectors
- 2.1 Duties of the Bridge Inspection Team
- 2.2 Safety Fundamentals for Bridge Inspectors
- 2.3 Temporary Traffic Control
- 2.4 Inspection Equipment
- 2.5 Methods of Access
  
- Chapter 3: Basic Bridge Terminology
- 3.1 Basic Bridge Terminology
  
- Chapter 4: Bridge Inspection Reporting
- 4.1 Structure Inventory
- 4.2 Condition and Appraisal
- 4.3 Introduction to Element Level Evaluation
- 4.4 Record Keeping and Documentation
- 4.5 Critical Findings
- 4.6 The Inspection Report
  
- Chapter 5: Bridge Mechanics
- 5.1 Bridge Mechanics

TOPIC

Chapter 6: Bridge Materials

- 6.1 Timber
- 6.2 Concrete
- 6.3 Steel/ Metal
- 6.4 Fatigue and Fracture in Steel
- 6.5 Stone Masonry
- 6.6 Fiber Reinforced Polymer(FRP)

Chapter 7: Inspection and Evaluation Bridges Decks and Areas Adjacent To Bridge Decks

- 7.1 Timber Decks
- 7.2 Concrete Decks
- 7.3 Fiber Reinforced Polymer (FRP) Decks
- 7.4 Steel Decks
- 7.5 Deck Joints, Drainage Systems, Lighting and Signs
- 7.6 Safety Features

Chapter 8: Inspection and Evaluation of Timber Superstructures

- 8.1 Solid Sawn Timber Bridges
- 8.2 Glulam Timber Bridges
- 8.3 Stress-Laminated Timber Bridges

Chapter 9: Inspection and Evaluation of Concrete Superstructures

- 9.1 Cast-In-Place Slabs
- 9.2 Cast-In-Place Tee Beams
- 9.3 Conventionally Reinforced Concrete Two-Girder System
- 9.4 Concrete Channel Beams
- 9.5 Concrete Arches
- 9.6 Concrete Rigid Frames
- 9.7 Precast and Prestressed Slabs
- 9.8 Prestressed Double Tees
- 9.9 Prestressed I-Beams and Bulb Tees
- 9.10 Prestressed Box Beams
- 9.11 Concrete Box Girders



TOPIC

	<u>Chapter 10: Inspection and Evaluation of Steel Superstructures</u>
10.1	Rolled Steel Multi-Beams and Fabricated Steel Multi-Girders
10.2	Steel Two-Girder Systems
10.3	Steel Box Beams and Girders
10.4	Steel Trusses
10.5	Steel Arches
10.6	Steel Rigid Frames
10.7	Pin-and-Hanger Assemblies
10.8	Gusset Plates
10.9	Steel Eyebars
	<u>Chapter 11: Inspection and Evaluation of Bridge Bearings</u>
11.1	Bridge Bearings
	<u>Chapter 12: Inspection and Evaluation of Substructures</u>
12.1	Abutments and Wingwalls
12.2	Piers and Bents
	<u>Chapter 13: Inspection and Evaluation of Waterways</u>
13.1	Waterway Elements
13.2	Inspection of Waterways
13.3	Underwater Inspection
	<u>Chapter 14: Characteristics, Inspection and Evaluation of Culverts</u>
14.1	Culvert Characteristics
14.2	Rigid Culverts
14.3	Flexible Culverts
	<u>Chapter 15: Advanced Inspection Methods</u>
15.1	Timber
15.2	Concrete
15.3	Steel
15.4	Advanced Bridge Evaluation
	<u>Chapter 16: Complex Bridges</u>
16.1	Cable-Supported Bridges
16.2	Movable Bridges
16.3	Floating Bridges

Appendix A: Sample Inspection Report

Appendix B: National Bridge Inspection Standards

Glossary

---

# List of Figures

	<b>Figure Nos.</b>		<b>Page Nos.</b>
<b>Topic 1.1 History of the National Bridge Inspection Program</b>			
	1.1.1	Number of Bridges Built since 1900.....	1.1.2
	1.1.2	Collapse of the Silver Bridge .....	1.1.2
	1.1.3	Federal Funding Levels (1979 – 2003).....	1.1.6
<b>Topic 1.2 Responsibilities of the Bridge Inspector</b>			
	1.2.1	Mianus Bridge Failure .....	1.2.2
<b>Topic 1.3 Quality Control and Quality Assurance</b>			
		<b>None</b>	
<b>Topic 2.1 Duties of the Bridge Inspection Team</b>			
	2.1.1	Sample Bridge Numbering Sequence .....	2.1.3
	2.1.2	Sample Truss Numbering Scheme .....	2.1.4
	2.1.3	Sample Inspection Sequence.....	2.1.6
	2.1.4	Temporary Traffic Control Operation.....	2.1.7
	2.1.5	Inspection for Scour and Undermining .....	2.1.12

	<b>Figure Nos.</b>		<b>Page Nos.</b>
<b>Topic 2.2</b>			
<b>Safety</b>			
<b>Fundamentals</b>			
<b>for Bridge</b>			
<b>Inspectors</b>			
	2.2.1	Inspector Wearing a Hard Hat.....	2.2.3
	2.2.2	Inspector Wearing A Reflective Safety Vest .....	2.2.4
	2.2.3	Inspector Wearing Safety Goggles and Gloves .....	2.2.5
	2.2.4	Inspector Wearing a Life Jacket.....	2.2.5
	2.2.5	Inspector Wearing a Respirator.....	2.2.6
	2.2.6	Inspector with Safety Harness with a Lanyard .....	2.2.7
	2.2.7	Inspection Involving Extensive Climbing.....	2.2.11
	2.2.8	Proper Use of Ladder .....	2.2.12
	2.2.9	Bucket Truck.....	2.2.13
	2.2.10	Inspection Catwalk.....	2.2.14
	2.2.11	Inspection Rigging .....	2.2.15
	2.2.12	Inclement Weather Causing Slippery Bridge Members and Poor Visibility for Motorists .....	2.2.18
<b>Topic 2.3</b>			
<b>Temporary</b>			
<b>Traffic Control</b>			
	2.3.1	Temporary Traffic Control Operation.....	2.3.1
	2.3.2	Work Zone .....	2.3.3
	2.3.3	Inspection Vehicles with Flashing Light.....	2.3.4
	2.3.4	Regulatory Sign.....	2.3.7
	2.3.5	Warning Sign .....	2.3.7
	2.3.6	Examples of Guide Signs .....	2.3.7
	2.3.7	Arrow Board .....	2.3.8
	2.3.8	Changeable Message Sign .....	2.3.8
	2.3.9	Cones.....	2.3.10
	2.3.10	Drums .....	2.3.10
	2.3.11	Tubular Marker .....	2.3.11
	2.3.12	Vertical Panel.....	2.3.11
	2.3.13	Temporary Traffic Barriers .....	2.3.12
	2.3.14	Warning Lights.....	2.3.13
	2.3.15	Use of Hand Signaling Devices by Flagger (from Manual on Uniform Traffic Control Devices (MUTCD)) .....	2.3.15
	2.3.16	Stopping Sight Distance as a Function of Speed (from Manual on Uniform Traffic Control Devices (MUTCD)) .....	2.3.16
	2.3.17	Flagger with Stop/Slow Paddle.....	2.3.17

<b>Figure Nos.</b>		<b>Page Nos.</b>
2.3.18	Shadow Vehicle with Attenuator .....	2.3.19

**Topic 2.4  
Inspection  
Equipment**

2.4.1	Tools for Cleaning .....	2.4.1
2.4.2	Tools for Inspection .....	2.4.2
2.4.3	Tools for Visual Aid .....	2.4.2
2.4.4	Tools for Measuring.....	2.4.3
2.4.5	Rotary Percussion .....	2.4.6
2.4.6	Scour Monitoring Collar .....	2.4.8
2.4.7	Scour Monitoring Collar Schematic .....	2.4.9
2.4.8	Remote Camera.....	2.4.10
2.4.9	High Speed Underclearance Measurement System ....	2.4.11
2.4.10	Tablet PC Used to collect inspection data .....	2.4.12

**Topic 2.5  
Methods of  
Access**

2.5.1	Inspectors using a Ladder with the Proper 1H to 4V Ratio .....	2.5.1
2.5.2	Inspector using a Hook-ladder .....	2.5.2
2.5.3	Rigging for Substructure Inspection .....	2.5.3
2.5.4	Rigging for Superstructure Inspection .....	2.5.3
2.5.5	Scaffold .....	2.5.4
2.5.6	Inspection Operations from a Barge .....	2.5.5
2.5.7	Climber.....	2.5.5
2.5.8	Inspector Using Float .....	2.5.6
2.5.9	Inspector Rappelling Substructure Unit .....	2.5.6
2.5.10	Climbing.....	2.5.7
2.5.11	Catwalk .....	2.5.8
2.5.12	Traveler Platform .....	2.5.9
2.5.13	Handrail on Girder Bridge .....	2.5.10
2.5.14	Handrail on Suspension Bridge.....	2.5.10
2.5.15	Manlift.....	2.5.11
2.5.16	Scissor Lift .....	2.5.12
2.5.17	Bucket Truck.....	2.5.13
2.5.18	Track-mounted Man-lift in a Stream.....	2.5.13
2.5.19	Track-mounted Man-lift on a Slope .....	2.5.14
2.5.20	Under Bridge Inspection Vehicle with Bucket .....	2.5.14
2.5.21	Under Bridge Inspection Vehicle with Platform.....	2.5.15

<b>Topic 3.1</b>	<b>Figure</b>	<b>Page</b>
<b>Basic Bridge</b>	<b>Nos.</b>	<b>Nos.</b>
<b>Terminology</b>		
3.1.1	NBIS Structure Length.....	3.1.1
3.1.2	NBIS Bridge Length (Coding Guide Item 112).....	3.1.2
3.1.3	Major Bridge Components.....	3.1.3
3.1.4	Timber Members.....	3.1.4
3.1.5	Timber Beams.....	3.1.5
3.1.6	Unusual Concrete Shapes.....	3.1.5
3.1.7	Reinforced Concrete Shapes.....	3.1.6
3.1.8	Prestressed Concrete Shapes.....	3.1.7
3.1.9	Non-prestressed Mild Steel Reinforced Concrete vs. Precast Prestressed Concrete.....	3.1.8
3.1.10	Concrete Pile Bent.....	3.1.9
3.1.11	Steel Making Operation.....	3.1.11
3.1.12	Common Rolled Steel Shapes.....	3.1.12
3.1.13	Bracing Members Made from Angles, Bars, and Plates.....	3.1.13
3.1.14	Riveted Plate Girder.....	3.1.15
3.1.15	Riveted Box Shapes.....	3.1.15
3.1.16	Welded I-Beam.....	3.1.16
3.1.17	Welded Box Shapes.....	3.1.16
3.1.18	Cable Cross-Sections.....	3.1.17
3.1.19	Cable-Supported Bridge: Suspension Cables and Hangers.....	3.1.17
3.1.20	Cable-Supported Bridge: Cable Stayed.....	3.1.18
3.1.21	Sizes of Bridge Pins.....	3.1.19
3.1.22	Pin-Connected Eyebars.....	3.1.19
3.1.23	Types of Rivet Heads.....	3.1.20
3.1.24	Shop Rivets and Field Bolts.....	3.1.21
3.1.25	Close-up of Tack Weld on a Riveted Built-up Truss Member.....	3.1.22
3.1.26	Pin and Hanger Assembly.....	3.1.23
3.1.27	Bolted Field Splice.....	3.1.24
3.1.28	Bridge Deck with a Smooth Riding Surface.....	3.1.24
3.1.29	Underside View of a Bridge Deck.....	3.1.25
3.1.30	Composite Deck and Steel Superstructure.....	3.1.26
3.1.31	Shear Studs on Top Flange of Girder (before Concrete Deck is Placed).....	3.1.26
3.1.32	Plank Deck.....	3.1.27
3.1.33	Concrete Deck.....	3.1.28
3.1.34	Steel Grid Deck.....	3.1.28
3.1.35	Fiber Reinforced Polymer (FRP) Deck.....	3.1.29

<b>Figure Nos.</b>		<b>Page Nos.</b>
3.1.36	Asphalt Wearing Surface on a Concrete Deck.....	3.1.30
3.1.37	Strip Seal Expansion Joint.....	3.1.31
3.1.38	Top View of an Armored Compression Seal in Place .....	3.1.32
3.1.39	Top View of a Finger Plate Joint.....	3.1.32
3.1.40	New Jersey Barrier .....	3.1.34
3.1.41	Weight Limit Sign and Object Marker Signs.....	3.1.35
3.1.42	Bridge Lighting .....	3.1.35
3.1.43	Four Basic Bridge Types.....	3.1.36
3.1.44	Slab Bridge.....	3.1.37
3.1.45	Beam Bridge.....	3.1.37
3.1.46	Multi-Girder Bridge .....	3.1.38
3.1.47	Girder Floorbeam Stringer Bridge .....	3.1.38
3.1.48	Curved Girder Bridge.....	3.1.39
3.1.49	Tee Beam Bridge.....	3.1.39
3.1.50	Adjacent Box Beam Bridge.....	3.1.40
3.1.51	Box Girder Bridge.....	3.1.40
3.1.52	Deck Truss Bridge.....	3.1.41
3.1.53	Through Truss Bridge .....	3.1.41
3.1.54	Deck Arch Bridge.....	3.1.42
3.1.55	Through Arch Bridge .....	3.1.42
3.1.56	Rigid Frame.....	3.1.43
3.1.57	Suspension Bridge.....	3.1.44
3.1.58	Cable-stayed Bridge .....	3.1.44
3.1.59	Bascule Bridge .....	3.1.45
3.1.60	Swing Bridge.....	3.1.45
3.1.61	Lift Bridge .....	3.1.46
3.1.62	Floating Bridge.....	3.1.46
3.1.63	Floor System and Main Supporting Members .....	3.1.47
3.1.64	Main Supporting Members of Deck Arch.....	3.1.48
3.1.65	Diaphragms .....	3.1.48
3.1.66	Cross or X-Bracing.....	3.1.49
3.1.67	Top Lateral Bracing and Sway Bracing .....	3.1.49
3.1.68	Steel Roller Bearing Showing Four Basic Elements...	3.1.51
3.1.69	Abutment.....	3.1.52
3.1.70	Pier.....	3.1.52
3.1.71	Cantilever Abutment (or Full Height Abutment)	3.1.53
3.1.72	Stub Abutment.....	3.1.54
3.1.73	Spill-Through or Open Abutment .....	3.1.54
3.1.74	Integral Abutment.....	3.1.55
3.1.75	Solid Shaft Pier.....	3.1.56
3.1.76	Solid Shaft Pier.....	3.1.56
3.1.77	Column Pier.....	3.1.57

<b>Figure Nos.</b>		<b>Page Nos.</b>
3.1.78	Column Pier with Web Wall and Cantilevered Pier Caps.....	3.1.57
3.1.79	Cantilever or Hammerhead Pier .....	3.1.58
3.1.80	Column Bent .....	3.1.58
3.1.81	Pile Bent .....	3.1.59
3.1.82	Schematic of Common Abutment Types .....	3.1.60
3.1.83	Rigid Culvert .....	3.1.62
3.1.84	Flexible Culvert.....	3.1.62

**Topic 4.1  
Structure  
Inventory**

4.1.1	Example SI&A Sheet with Element Level Data.....	4.1.3
4.1.2	Typical SI&A Sheet with NBI Data Only.....	4.1.4
4.1.3	Oregon Bridge Inspection Report with Element Level Data .....	4.1.5
4.1.4	Arizona Structural Inventory and Appraisal Sheet .....	4.1.7
4.1.5	Florida Structural Inventory and Appraisal Sheet.....	4.1.8
4.1.6	Portable Computer .....	4.1.12
4.1.7	Inspector Using Portable Computer .....	4.1.12
4.1.8	Wearable Computer with Case.....	4.1.13
4.1.9	Inspector Using Wearable Computer .....	4.1.13

**Topic 4.2  
Condition and  
Appraisal**

None

**Topic 4.3  
Introduction to  
Element Level  
Evaluation**

4.3.1	AASHTO Guide Manual for Bridge Element Inspection .....	4.3.4
4.3.2	Decks/Slabs National Bridge Elements in the AASHTO Guide.....	4.3.6
4.3.3	Superstructure National Bridge Elements in the AASHTO Guide.....	4.3.7
4.3.4	Substructure National Bridge Elements in the AASHTO Guide.....	4.3.7
4.3.5	Decks/Slabs Bridge Management Elements in the AASHTO .....	4.3.8



	<b>Figure Nos.</b>		<b>Page Nos.</b>
	4.3.6	Wearing Surfaces and Protective Systems in the AASHTO Guide.....	4.3.8
<b>Topic 4.4</b>			
<b>Record Keeping</b>			
<b>and</b>			
<b>Documentation</b>			
	4.4.1	Sample Photo Log .....	4.4.3
	4.4.2	Accident Involving Construction Equipment and a Bridge.....	4.4.4
	4.4.3	Posted Bridge .....	4.4.4
	4.4.4	Flood Event .....	4.4.5
	4.4.5	Element Level Example Inspection Form.....	4.4.8
	4.4.6	Example Load Rating Summary Sheet .....	4.4.9
	4.4.7	Inspector Taking Notes .....	4.4.10
	4.4.8	Electronic Data Collection .....	4.4.11
	4.4.9	Sample Span Numbering Scheme .....	4.4.13
	4.4.10	Sample Typical Section Numbering Scheme.....	4.4.13
	4.4.11	Sample Structure Orientation Sketch .....	4.4.13
	4.4.12	Sample Truss Numbering Scheme .....	4.4.14
	4.4.13	Steel Superstructure Dimensions .....	4.4.14
	4.4.14	Truss Member and Field Splice Dimensions .....	4.4.15
	4.4.15	Framing Plan .....	4.4.16
	4.4.16	Girder Elevation .....	4.4.17
	4.4.17	Typical Prepared Culvert Sketches .....	4.4.17
	4.4.18	Sample General Plan Sketch .....	4.4.18
	4.4.19	Sample General Elevation Sketch.....	4.4.18
	4.4.20	Sample Deck Inspection Notes .....	4.4.20
	4.4.21	Sample Superstructure Inspection Notes .....	4.4.21
	4.4.22	Sample Substructure Inspection Notes .....	4.4.22
	4.4.23	Sample Channel Inspection Notes .....	4.4.22
	4.4.24	Example Inspection Form – PennDOT Form D-450	4.4.23
<b>Topic 4.5</b>			
<b>Critical</b>			
<b>Findings</b>			
	4.5.1	Missouri DOT Critical Inspection Finding Form.....	4.5.3
	4.5.2	Washington State DOT "Critical Damage - Bridge Repair Report".....	4.5.4
	4.5.3	Pennsylvania DOT Critical and High Priority Maintenance Items – Flowchart for Plan of Action ....	4.5.10
	4.5.4	Washington State DOT Flowchart for Field Inspection Procedure.....	4.5.11

	<b>Figure Nos.</b>		<b>Page Nos.</b>
<b>Topic 4.6</b>			
<b>Inspection</b>			
<b>Report</b>			
	4.6.1	Near Approach - Toward Bridge.....	4.6.6
	4.6.2	Downstream Elevation.....	4.6.6
<b>Topic 5.1</b>			
<b>Bridge</b>			
<b>Mechanics</b>			
	5.1.1	Permanent Load on a Bridge.....	5.1.2
	5.1.2	Vehicle Transient Load on a Bridge.....	5.1.3
	5.1.3	AASHTO H20 Truck.....	5.1.4
	5.1.4	AASHTO HS20 Truck.....	5.1.5
	5.1.5	AASHTO Lane Loadings.....	5.1.6
	5.1.6	AASHTO LRFD Loading.....	5.1.7
	5.1.7	Alternate Military Loading.....	5.1.7
	5.1.8	Permit Vehicle.....	5.1.8
	5.1.9	Axial Forces.....	5.1.10
	5.1.10	Positive and Negative Moment.....	5.1.12
	5.1.11	Girder Cross Section Resisting Positive Moment.....	5.1.12
	5.1.12	Shear Forces in a Member Element.....	5.1.13
	5.1.13	Torsion.....	5.1.14
	5.1.14	Torsional Distortion.....	5.1.15
	5.1.15	Types of Supports.....	5.1.15
	5.1.16	Basic Force Components.....	5.1.16
	5.1.17	Stress-Strain Diagram.....	5.1.19
	5.1.18	Rating Vehicles.....	5.1.25
	5.1.19	Bridge Weight Limit Posting.....	5.1.26
	5.1.20	Damaged Bridge due to Failure to Comply with Bridge Posting.....	5.1.27
	5.1.21	Simple Bridge.....	5.1.28
	5.1.22	Continuous Bridge.....	5.1.29
	5.1.23	Cantilever Span.....	5.1.30
	5.1.24	Cantilever Bridge.....	5.1.31
	5.1.25	Non-Composite or Composite Concrete Deck on Steel Beams and Pretressed Concrete Beams.....	5.1.32
	5.1.26	Integral Bridge.....	5.1.33
	5.1.27	Cross Section of an Integral Bridge.....	5.1.33
	5.1.28	Orthotropic Bridge Deck.....	5.1.34
	5.1.29	Spread Footing.....	5.1.36
	5.1.30	Deep Foundation.....	5.1.36

	<b>Figure Nos.</b>		<b>Page Nos.</b>
<b>Topic 6.1 Timber</b>	6.1.1	Glued-laminated Modern Timber Bridge.....	6.1.2
	6.1.2	Timber Shapes.....	6.1.3
	6.1.3	Built-up Timber Shapes .....	6.1.3
	6.1.4	Anatomy of Timber.....	6.1.5
	6.1.5	3-D Close-up of Softwood Timber Anatomy (Source: Society of Wood Science and Technology) .	6.1.6
	6.1.6	Three Principal Axes of Wood.....	6.1.7
	6.1.7	Inherent Timber Defects .....	6.1.11
	6.1.8	Decay of Wood by Fungi .....	6.1.11
	6.1.9	Mold and Stain on Underside of Timber Bridge.....	6.1.13
	6.1.10	Brown and White Rot .....	6.1.13
	6.1.11	Termites .....	6.1.15
	6.1.12	Powder Post Beetle .....	6.1.15
	6.1.13	Carpenter Ants .....	6.1.16
	6.1.14	Caddis fly Larva.....	6.1.17
	6.1.15	Marine Borer Damage to Wood Piling .....	6.1.18
	6.1.16	Shipworm (Mollusk).....	6.1.18
	6.1.17	Limnoria (Wood Louse).....	6.1.19
	6.1.18	Delamination in a Glue Laminated Timber Member..	6.1.20
	6.1.19	Loose Hanger Connection Between the Timber Truss and Floorbeam.....	6.1.20
	6.1.20	Fire Damaged Timber Members .....	6.1.21
	6.1.21	Impact/Collision Damage to a Timber Member .....	6.1.22
	6.1.22	Wear of a Timber Deck.....	6.1.22
	6.1.23	Horizontal Shear Failure in Timber Member.....	6.1.23
	6.1.24	Failed Timber Floor Beam due to Excessive Bending Moment.....	6.1.23
	6.1.25	Timber Substructure Member Subjected to Crushing and Overstress .....	6.1.24
	6.1.26	Weathering on Timber Deck.....	6.1.24
	6.1.27	Bridge Timber Member Showing Penetration Depth of Preservative Treatment .....	6.1.26
	6.1.28	Coal-Tar Creosote Treated Timber Beams (Source: Barry Dickson, West Virginia University).....	6.1.26
	6.1.29	Inspector Performing a Pick Test.....	6.1.30
	6.1.30	Timber Boring and Drilling Locations.....	6.1.31
	6.1.31	Gage Used to Measure Coating Dry Film Thickness .	6.1.32
	<b>Topic 6.2 Concrete</b>	6.2.1	Round Concrete Members .....

<b>Figure Nos.</b>		<b>Page Nos.</b>
6.2.2	Rectangular Concrete Members.....	6.2.5
6.2.3	Strength Properties of Concrete (3500 psi Concrete) .	6.2.6
6.2.4	FHWA’s Strategic Highway Research Program (SHRP) Implemented HPC Mix Designs.....	6.2.7
6.2.5	Concrete Member with Tensile Steel Reinforcement Showing.....	6.2.8
6.2.6	Standard Deformed Reinforcing Bars (Source: Concrete Reinforcing Steel Institute).....	6.2.9
6.2.7	Standard Deformed Reinforcing Bars (Source: Concrete Reinforcing Steel Institute) (Continued) .....	6.2.10
6.2.8	Prestressed Concrete Beam.....	6.2.12
6.2.9	Pretensioned Concrete I-Beams .....	6.2.13
6.2.10	Post-tensioned Concrete Box Girders .....	6.2.13
6.2.11	Structural Cracks.....	6.2.16
6.2.12	Flexural Crack on a Tee Beam.....	6.2.17
6.2.13	Shear Crack on a Slab .....	6.2.17
6.2.14	Crack Comparator Card .....	6.2.18
6.2.15	Temperature Cracks .....	6.2.20
6.2.16	Shrinkage Cracks .....	6.2.20
6.2.17	Transverse Cracks .....	6.2.22
6.2.18	Longitudinal Cracks.....	6.2.22
6.2.19	Pattern or Map Cracks.....	6.2.23
6.2.20	Light or Minor Scaling.....	6.2.24
6.2.21	Medium or Moderate Scaling.....	6.2.24
6.2.22	Heavy Scaling .....	6.2.24
6.2.23	Severe Scaling.....	6.2.24
6.2.24	Spalling on a Concrete Deck.....	6.2.25
6.2.25	Efflorescence.....	6.2.27
6.2.26	Alkali-Silica Reaction (ASR).....	6.2.28
6.2.27	Honeycomb .....	6.2.29
6.2.28	Concrete Column Collision Damage .....	6.2.30
6.2.29	Substructure Abrasion.....	6.2.31
6.2.30	Overload Damage .....	6.2.32
6.2.31	Loss of Bond: Concrete / Corroded Reinforcing Bar..	6.2.33
6.2.32	Anti-Graffiti Coating on Lower Area of Bridge Piers.....	6.2.38
6.2.33	Inspector Using a Chain Drag.....	6.2.41

<b>Topic 6.3</b>	<b>Figure Nos.</b>	<b>Page Nos.</b>
<b>Steel/Metal</b>		
	6.3.1.	Prestressing Strands for a Box Beam ..... 6.3.2
	6.3.2	Steel Cables with Close-up of Cable Cross-Section ... 6.3.3
	6.3.3	Steel Plate Welded to Girder..... 6.3.3
	6.3.4	Welded I-Girder ..... 6.3.4
	6.3.5	Steel Reinforcement Bars..... 6.3.4
	6.3.6	Steel Eyebars ..... 6.3.5
	6.3.7	Rolled Beams ..... 6.3.5
	6.3.8	Built-up Girder ..... 6.3.6
	6.3.9	High Performance Steel Bridge ..... 6.3.8
	6.3.10	Steel Corrosion and Complete Section Loss on Girder Webs ..... 6.3.9
	6.3.11	Fatigue Crack ..... 6.3.10
	6.3.12	Distortion Induced Fatigue..... 6.3.11
	6.3.13	Collision Damage on a Steel Bridge ..... 6.3.12
	6.3.14	Heat Damage..... 6.3.13
	6.3.15	Paint Wrinkling ..... 6.3.14
	6.3.16	Rust Undercutting at Scratched Area..... 6.3.14
	6.3.17	Pinpoint Rusting..... 6.3.15
	6.3.18	Paint Peeling from Steel Bridge Members..... 6.3.15
	6.3.19	Mudcracking Paint ..... 6.3.15
	6.3.20	Corrosion of Steel ..... 6.3.23
	6.3.21	Fatigue Crack ..... 6.3.23
	6.3.22	Paint Failure on Edge of Steel Truss Member ..... 6.3.24
	6.3.23	Water and Salt Runoff Near Expansion Joint ..... 6.3.25
	6.3.24	Corroding Rivet Head ..... 6.3.25
	6.3.25	Roadway Spray Zone Deficiency..... 6.3.26
	6.3.26	Color of Oxide Film is Critical in the Inspection of Weathering Steel; Dark Black Color in an Indication of Non-protective Oxide ..... 6.3.27
	6.3.27	Yellow Orange – Early Development of the Oxide Film (Patina) ..... 6.3.27
	6.3.28	Light Brown – Early Development of the Oxide Film (Patina) ..... 6.3.28
	6.3.29	Chocolate Brown to Purple Brown - Fully Developed Oxide Film ..... 6.3.28
	6.3.30	Black – Non-protective Oxide ..... 6.3.29
	6.3.31	Correlation Between Weathering Steel Texture and Condition..... 6.3.30

**Topic 6.4  
Fatigue and  
Fracture in  
Steel**

<b>Figure Nos.</b>		<b>Page Nos.</b>
6.4.1	Silver Bridge Collapse .....	6.4.1
6.4.2	Mianus River Bridge Collapse .....	6.4.2
6.4.3	I-35W Mississippi River Bridge Collapse .....	6.4.2
6.4.4	Load Path Redundant Multi-Girder Bridge.....	6.4.4
6.4.5	Structurally Redundant Continuous Span Bridge .....	6.4.5
6.4.6	Internally Redundant Riveted I-Beam .....	6.4.6
6.4.7	Internally Redundant Riveted Box Shapes .....	6.4.6
6.4.8	Patch Plate Welded on Riveted Girder Web along Flange Angle .....	6.4.7
6.4.9	Nonredundant Two-Girder.....	6.4.8
6.4.10	Brittle Fracture of Cast Iron Specimen .....	6.4.9
6.4.11	Ductile Fracture of Cold Rolled Steel Specimen .....	6.4.10
6.4.12	Charpy V-notch Testing Machine.....	6.4.11
6.4.13	Groove Weld Nomenclature .....	6.4.13
6.4.14	Fillet Weld Nomenclature .....	6.4.13
6.4.15	Plug Weld Schematic .....	6.4.14
6.4.16	Tack Weld .....	6.4.15
6.4.17	Types of Welded Joints.....	6.4.16
6.4.18	Exposed Lamination in Steel Slab .....	6.4.16
6.4.19	Shrinkage Cavity in Steel Billet.....	6.4.17
6.4.20	Incomplete Penetration of a Double V-Groove Weld.	6.4.18
6.4.21	Crack Initiation from Lack of Fusion in Heat Affected Zone of Electroslag Groove Weld of a Butt Joint.....	6.4.18
6.4.22	Web to Flange Crack due to Fillet Weld Slag Inclusion.....	6.4.19
6.4.23	Crack Initiation from Porosity in Longitudinal Web- to-Flange Fillet Weld of Plate Girder.....	6.4.19
6.4.24	Crack Resulting from Plug Welded Holes .....	6.4.20
6.4.25	Undercut of a Fillet Weld.....	6.4.21
6.4.26	Overlap of a Fillet Weld.....	6.4.21
6.4.27	Incomplete Penetration of a V-Groove Weld.....	6.4.22
6.4.28	Crack Initiation at Coped Web in Stringer to Floorbeam .....	6.4.23
6.4.29	Insufficiently Ground Flame Cut of Gusset Plate for Arch to Tie Girder Connection.....	6.4.23
6.4.30	Thick plate with Two Plates Welded to it and Showing a Lamellar Tear .....	6.4.24
6.4.31	Severe Collision Damage on a Fascia Girder .....	6.4.25

<b>Figure Nos.</b>		<b>Page Nos.</b>
6.4.32	Applied Tensile and Compressive Stress Cycles .....	6.4.26
6.4.33	Part-Through Crack at a Cover Plated Flange .....	6.4.27
6.4.34	Part-Through Crack Growth at Cover Plate Welded to Flange.....	6.4.28
6.4.35	Through Crack Growth at Cover Plate Welded to Flange.....	6.4.29
6.4.36	Through Crack at a Cover Plated Flange .....	6.4.29
6.4.37	Through Crack has Propagated into the Web .....	6.4.30
6.4.38	Brittle Fracture – Herringbone Pattern.....	6.4.30
6.4.39	Crack Growth at Transverse Stiffener Welded to Web .....	6.4.31
6.4.40	Part-Through Web Crack .....	6.4.32
6.4.41	Through Crack in the Web.....	6.4.32
6.4.42	Through-Crack Ready to Propagate into the Flange...	6.4.33
6.4.43	<i>AASHTO LRFD Bridge Design Specifications, 5<sup>th</sup></i> Edition, with 2010 Interim Revisions, Table 6.6.1.2.3-1 - Detail Categories for Load-Induced Fatigue.....	6.4.34
6.4.43	<i>AASHTO LRFD Bridge Design Specifications, 5<sup>th</sup></i> Edition, with 2010 Interim Revisions, Table 6.6.1.2.3-1 - Detail Categories for Load-Induced Fatigue, continued.....	6.4.35
6.4.43	<i>AASHTO LRFD Bridge Design Specifications, 5<sup>th</sup></i> Edition, with 2010 Interim Revisions, Table 6.6.1.2.3-1 - Detail Categories for Load-Induced Fatigue, continued.....	6.4.36
6.4.43	<i>AASHTO LRFD Bridge Design Specifications, 5<sup>th</sup></i> Edition, with 2010 Interim Revisions, Table 6.6.1.2.3-1 - Detail Categories for Load-Induced Fatigue, continued.....	6.4.37
6.4.43	<i>AASHTO LRFD Bridge Design Specifications, 5<sup>th</sup></i> Edition, with 2010 Interim Revisions, Table 6.6.1.2.3-1 - Detail Categories for Load-Induced Fatigue, continued.....	6.4.38
6.4.43	<i>AASHTO LRFD Bridge Design Specifications, 5<sup>th</sup></i> Edition, with 2010 Interim Revisions, Table 6.6.1.2.3-1 - Detail Categories for Load-Induced Fatigue, continued.....	6.4.39
6.4.43	<i>AASHTO LRFD Bridge Design Specifications, 5<sup>th</sup></i> Edition, with 2010 Interim Revisions, Table 6.6.1.2.3-1 - Detail Categories for Load-Induced Fatigue, continued.....	6.4.40

<b>Figure Nos.</b>		<b>Page Nos.</b>
6.4.43	<i>AASHTO LRFD Bridge Design Specifications, 5<sup>th</sup> Edition, with 2010 Interim Revisions, Table 6.6.1.2.3-1 - Detail Categories for Load-Induced Fatigue, continued</i> .....	6.4.41
6.4.43	<i>AASHTO LRFD Bridge Design Specifications, 5<sup>th</sup> Edition, with 2010 Interim Revisions, Table 6.6.1.2.3-1 - Detail Categories for Load-Induced Fatigue, continued</i> .....	6.4.42
6.4.44	Riveted Gusset Plate Connection.....	6.4.44
6.4.45	Poor Quality Welds Inside Cross Girder.....	6.4.45
6.4.46	Intersecting Welds.....	6.4.45
6.4.47	Local Triaxial Constraint Condition Resulting in Fracture on the Hoan Bridge, Milwaukee, Wisconsin	6.4.49
6.4.48	Potential Crack Formation due to Intersecting Welds	6.4.50
6.4.49	Potential Crack Formation for Various Cover Plate End Treatments .....	6.4.51
6.4.50	Potential Crack Formation for Cantilever Suspended Span (Potential Cracks Shown in Red) .....	6.4.52
6.4.51	Potential Crack Formation in Vertical Web Weld at Haunch .....	6.4.53
6.4.52	Potential Crack Formation in Vertical Web Weld at End of Span.....	6.4.53
6.4.53	Field Welds Perpendicular to Bending Stresses are Susceptible to Cracking .....	6.4.54
6.4.54	Intermittent or Stitch Welded Transverse Stiffeners...	6.4.55
6.4.55	Out-of-Plane Distortion in Web Gap at Diaphragm Connections.....	6.4.56
6.4.56	Web Crack due to Out-of-Plane Distortion at Top Flange.....	6.4.59
6.4.57	Web Crack due to Out-of-Plane Distortion at Bottom Flange.....	6.4.59
6.4.58	Skewed Bridge Producing Out-of-Plane Bending due to Differential Deflection of Floorbeams and Girders.....	6.4.60
6.4.59	Lateral Bracing Deflections Producing Out-of-Plane Bending .....	6.4.60
6.4.60	Cantilevered Floorbeam Producing Out-of-Plane Bending due to Differential Deflection of Stringer.....	6.4.61
6.4.61	Cracks at Top of Floorbeam Connection to Girder.....	6.4.61
6.4.62	Back-Up Bars Tack Welded to Web and Flange Potentially Producing Abrupt Stress Reversal and Stress Risers .....	6.4.62
6.4.63	Bolted Field Splice .....	6.4.63
6.4.64	Welded Attachment in Tension Zone of a Beam.....	6.4.64



	<b>Figure Nos.</b>		<b>Page Nos.</b>
	6.4.65	Flange Termination .....	6.4.64
	6.4.66	Fracture of a Coped Member .....	6.4.65
	6.4.67	Blocked Floorbeam Flange .....	6.4.66
	6.4.68	Cracks Perpendicular or Parallel to Applied Stress ....	6.4.67
<b>Topic 6.5 Stone Masonry</b>			
	6.5.1	Stone Masonry Arch .....	6.5.1
	6.5.2	Splitting in Stone Masonry .....	6.5.2
<b>Topic 6.6 Fiber Reinforced Polymer (FRP)</b>			
	6.6.1	Concrete Beam Repaired Using FRP .....	6.6.1
	6.6.2	Seismic Retrofit of Concrete Columns Using FRP Composites .....	6.6.2
	6.6.3	CFRP Post-tensioned Steel Girder .....	6.6.3
	6.6.4	Externally Bonded CFRP Plates to Steel Girder Bottom Flange .....	6.6.4
	6.6.5	CFRP Plate and GFRP Reinforcing Bars .....	6.6.5
	6.6.6	Steel I-Beam (back) and Pultruded FRP I-Beam (front) .....	6.6.6
	6.6.7	Pultruded FRP Double-Web Beam .....	6.6.6
	6.6.8	Spools of Continuous Roving .....	6.6.8
	6.6.9	Discontinuous Roving .....	6.6.8
	6.6.10	Woven Roving Fabric .....	6.6.9
	6.6.11	Discontinuous Roving Mat Fabric .....	6.6.9
	6.6.12	Non-Crimp Fabric .....	6.6.10
	6.6.13	Fiber Reinforced Concrete (FRC) .....	6.6.13
	6.6.14	Blistering on a Laminated Surface .....	6.6.14
	6.6.15	Voids Resulting in Surface Cracks .....	6.6.15
	6.6.16	Wrinkling of Fabric in Laminated Facesheet .....	6.6.16
	6.6.17	Fiber Exposure from Improper Handling and Erection Methods .....	6.6.16
	6.6.18	Scratches on FRP Surface .....	6.6.17
	6.6.19	Cracks and Discoloration Around Punched Area .....	6.6.18
	6.6.20	Electronic Tap Testing Device .....	6.6.20
	6.6.21	Thermographic Image of Bridge Deck .....	6.6.21
	6.6.22	Acoustic Testing Technique .....	6.6.21
<b>Topic 7.1 Timber Decks</b>			
	7.1.1	Plank Deck .....	7.1.2
	7.1.2	Section of a Nailed Laminated Deck .....	7.1.2

<b>Figure Nos.</b>		<b>Page Nos.</b>
7.1.3	Glue Laminated Deck Panels .....	7.1.3
7.1.4	Stress-laminated Deck.....	7.1.4
7.1.5	Structural Composite Lumber Deck using Box Sections .....	7.1.5
7.1.6	Timber Wearing Surface on a Timber Plank Deck.....	7.1.6
7.1.7	Inspector Probing Timber with a Pick at Reflective Cracks in the Asphalt Wearing Surface .....	7.1.8
7.1.8	Wear and Weathering on a Timber Deck.....	7.1.10
7.1.9	Bearing and Shear Area on a Timber Deck .....	7.1.10
7.1.10	Edge of Deck Exposed to Drainage, Resulting in Plant Growth .....	7.1.11
7.1.11	Broken Prestressing Anchors .....	7.1.11

**Topic 7.2  
Concrete Decks**

7.2.1	CIP concrete Deck with Stay-in-Place Forms.....	7.2.2
7.2.2	Precast Deck Panels (with Lifting Lugs Evident and Top Beam Flange Exposed) .....	7.2.3
7.2.3	Shear Connectors Welded to the Top Flange of a Steel Girder for Composite Deck.....	7.2.4
7.2.4	Prestressed Concrete Beams with Shear Connectors Protruding.....	7.2.4
7.2.5	Spall Showing Deck Reinforcing Steel Perpendicular to Traffic .....	7.2.6
7.2.6	Cathodic Protection: Deck Wires Connected to Direct Current Rectifier .....	7.2.10
7.2.7	Sounding for Delaminated Areas of Concrete .....	7.2.12
7.2.8	Underside View of Longitudinal Deck Crack.....	7.2.15
7.2.9	Deteriorated Stay-in-Place Form.....	7.2.15

**Topic 7.3 Fiber Reinforced Polymer (FRP) Decks**

7.3.1	Fiber Reinforced Polymer (FRP) Deck.....	7.3.1
7.3.2	Honeycomb sandwich configuration (Photograph from NCHRP Report 564-field Inspection of In-Service FRP Bridge Decks) .....	7.3.2
7.3.3	Solid core sandwich configuration (Photograph from NCHRP Report 564 – Field Inspection of In-Service FRP Bridge Decks) .....	7.3.2

<b>Figure Nos.</b>		<b>Page Nos.</b>
7.3.4	Hollow core sandwich configuration (Photograph from NCHRP Report 564 – Field Inspection of In-Service FRP Bridge Decks) .....	7.3.2
7.3.5	Use of Truck for Visual Inspection of FRP Deck .....	7.3.3
7.3.6	Electronic Tap Testing Device.....	7.3.4
7.3.7	Deck expansion joint.....	7.3.6
7.3.8	FRP Deck Underside near Superstructure Beam .....	7.3.6
7.3.9	Clip-type Connection between FRP Deck and Steel Superstructure .....	7.3.7
7.3.10	Condition rating of FRP deck structure (Source: NCHRP Report 564: <i>Field Inspection of In-Service FRP Bridge Decks: Inspection Manual</i> : Table 7.1.2-1).....	7.3.9

**Topic 7.4  
Steel Decks**

7.4.1	Orthotropic Bridge Deck.....	7.4.1
7.4.2	Underside View of Buckle Plate Deck.....	7.4.2
7.4.3	Corrugated Steel Floor .....	7.4.2
7.4.4	Various Patterns of Welded Steel Grid Decks .....	7.4.3
7.4.5	Riveted Grate Deck.....	7.4.4
7.4.6	Steel Grid Deck with Slotted Holes (to eliminate welding and riveting) .....	7.4.5
7.4.7	Concrete-Filled Grid Deck.....	7.4.6
7.4.8	Filled and Un-filled Steel Grid Deck .....	7.4.6
7.4.9	Schematic of Exodermic Composite Profile .....	7.4.7
7.4.10	Broken Members of an Open Steel Grid Deck .....	7.4.11

**Topic 7.5  
Deck Joints,  
Drainage  
Systems,  
Lighting and  
Signs**

7.5.1	Strip Seal (Drawing Courtesy of the D.S. Brown Co. ....	7.5.2
7.5.2	Pourable Joint Seal.....	7.5.3
7.5.3	Cross Section of a Pourable Joint Seal.....	7.5.3
7.5.4	Compression Joint Seal with Steel Angle Armoring ..	7.5.4
7.5.5	Cross Section of a Compression Joint Seal with Steel Angle Armoring .....	7.5.4
7.5.6	Cross Section of a Cellular Seal.....	7.5.5
7.5.7	Modular Seal .....	7.5.5
7.5.8	Schematic Cross Section of a Modular Seal .....	7.5.6
7.5.9	Plank Seal.....	7.5.6

<b>Figure Nos.</b>		<b>Page Nos.</b>
7.5.10	Sheet Seal .....	7.5.7
7.5.11	Asphaltic Expansion Joint.....	7.5.8
7.5.12	Open Expansion Joint .....	7.5.8
7.5.13	Cross Section of a Open Expansion Joint .....	7.5.9
7.5.14	Finger Plate Joint .....	7.5.10
7.5.15	Cross Section of a Cantilever Finger Plate Joint.....	7.5.10
7.5.16	Supported Finger Plate Joint .....	7.5.11
7.5.17	Sliding Plate Joint .....	7.5.12
7.5.18	Cross Section of a Sliding Plate Joint .....	7.5.12
7.5.19	Bridge Deck Scupper (left) and Deck Drain (right)....	7.5.14
7.5.20	Outlet Pipe.....	7.5.15
7.5.21	Downspout Pipe .....	7.5.15
7.5.22	Drainage Trough .....	7.5.15
7.5.23	Weep Holes .....	7.5.16
7.5.24	Debris Lodged in a Sliding Plate Joint.....	7.5.20
7.5.25	Dirt in a Compression Seal Joint.....	7.5.20
7.5.26	Improper Vertical Alignment at a Finger Plate Joint..	7.5.21
7.5.27	Failed Compression Seal.....	7.5.22
7.5.28	Asphalt Wearing Surface over an Expansion Joint.....	7.5.22
7.5.29	Support System under a Finger Plate Joint .....	7.5.23
7.5.30	Clogged Scupper .....	7.5.25
7.5.31	Outlet Pipe with Cleanout Plugs .....	7.5.26
7.5.32	Drainage Trough with Debris Accumulation.....	7.5.27
7.5.33	Sign and Light Structures Attached to a Bridge.....	7.5.28
7.5.34	Sign Attachment Exhibiting Anchor Pullout .....	7.5.28
7.5.35	Sign Mount with Loose Adhesive Anchorage .....	7.5.29

**Topic 7.6  
Safety Features**

7.6.1	Bridge Safety Feature.....	7.6.1
7.6.2	Traffic Safety Features.....	7.6.3
7.6.3	Bridge Railing, Transition, Approach Guardrail and Approach Guardrail End .....	7.6.3
7.6.4	2010 AASHTO LRFD Bridge Specifications Test Level Index (based on the NCHRP Report 350 Test Level Index) .....	7.6.7
7.6.5	2009 AASHTO Manual for Assessment of Safety Hardware (MASH) Test Level Index.....	7.6.7
7.6.6	Acceptable Bridge Rail .....	7.6.11
7.6.7	Bridge Rail Guide .....	7.6.11
7.6.8	Acceptable Transition .....	7.6.12
7.6.9	Approach Guardrail System and Approved Plastic Offset Block .....	7.6.13

<b>Figure Nos.</b>		<b>Page Nos.</b>
7.6.10	W-Shaped Guardrail End Flared and Buried into an Embankment .....	7.6.14
7.6.11	Unacceptable Blunt Ends .....	7.6.15
7.6.12	Deficiency Steel Post Bridge Railing.....	7.6.17
7.6.13	Approach Guardrail Collision Damage.....	7.6.18
7.6.14	Erosion Reducing Post Embedment.....	7.6.18
7.6.15	Proper Nesting of Guardrail at Transition.....	7.6.19
7.6.16	Impact Attenuator .....	7.6.20
7.6.17	Timber Traffic Safety Features, Rocky Mountain National Park.....	7.6.20

**Topic 8.1  
Solid Sawn  
Timber Bridges**

8.1.1	Elevation View of a Solid Sawn Multi-Beam Bridge.	8.1.1
8.1.2	Underside View of a Solid Sawn Multi-Beam Bridge.....	8.1.2
8.1.3	Elevation View of Covered Bridge .....	8.1.3
8.1.4	Inside View of Covered Bridge Showing King Post Truss Design .....	8.1.4
8.1.5	Town Truss Covered Bridge .....	8.1.5
8.1.6	Common Covered Bridge Trusses .....	8.1.5
8.1.7	Schematic of Burr Arch-truss Covered Bridge .....	8.1.6
8.1.8	Burr Arch-truss Covered Bridge .....	8.1.6
8.1.9	Inside View of Covered Bridge with Burr Arch-truss Design .....	8.1.7
8.1.10	Town Truss Design .....	8.1.7
8.1.11	Bearing Area of Typical Solid Sawn Beam .....	8.1.9
8.1.12	Horizontal Shear Crack in a Timber Beam .....	8.1.10
8.1.13	Decay in a Timber Beam .....	8.1.11
8.1.14	Typical Timber End Diaphragm .....	8.1.12

**Topic 8.2  
Glulam Timber  
Bridges**

8.2.1	Elevation View of a Glulam Multi-beam Bridge .....	8.2.1
8.2.2	Underside View of a Glulam Multi-beam Bridge.....	8.2.2
8.2.3	Timber Through Truss Typical Section .....	8.2.3
8.2.4	Bowstring Truss Pedestrian Bridge.....	8.2.4
8.2.5	Parallel Chord Truss Pedestrian Bridge (Eagle River, Alaska) .....	8.2.4
8.2.6	Glulam Arch Bridge over Glulam Multi-beam Bridge (Keystone Wye Interchange, South Dakota)...	8.2.5
8.2.7	Glulam Arch Bridge (West Virginia).....	8.2.5

<b>Figure Nos.</b>		<b>Page Nos.</b>
8.2.8	Typical Glulam Diaphragm.....	8.2.6
8.2.9	Bearing Area of Typical Glulam Beam .....	8.2.8
8.2.10	Close-up View of Glulam Bridge Showing Laminations.....	8.2.9
8.2.11	Elevation View of Beam of Glulam Multi-beam Bridge.....	8.2.9
8.2.12	Decay on Glulam Bridge.....	8.2.10
8.2.13	Typical Diaphragm for a Glulam Multi-beam Bridge	8.2.11
8.2.14	Glulam Beams with Numerous Fastener Locations....	8.2.11

**Topic 8.3  
Stress-  
Laminated  
Timber Bridges**

8.3.1	Stress-Laminated Timber Slab Bridge Carrying a 90,000-Pound Logging Truck (Source: Barry Dickson, West Virginia University).....	8.3.1
8.3.2	Typical Section of Stress-Laminated Timber Slab Bridge.....	8.3.2
8.3.3	Stress-Laminated Timber Slab Bridge .....	8.3.2
8.3.4	Glulam Stress-Laminated Timber Slab Bridge.....	8.3.3
8.3.5	Typical Section of Stress-Laminated Timber Tee Beam Bridge (Source: Barry Dickson, West Virginia University) .....	8.3.3
8.3.6	Elevation View of Stress-Laminated Timber Tee Beam Bridge (West Virginia) .....	8.3.4
8.3.7	Typical Section of Stress-Laminated Timber Box Beam (Source: Barry Dickson, West Virginia University) .....	8.3.4
8.3.8	Stress-Laminated Timber Box Beam Bridge Being Erected .....	8.3.5
8.3.9	Stress-Laminated Timber K-Frame Bridge.....	8.3.5
8.3.10	Broken Stressing Rods .....	8.3.7
8.3.11	Close-up View of End of a Stress-Laminated Timber Bridge Showing Laminations.....	8.3.8

**Topic 9.1  
Cast-in-Place  
Slabs**

9.1.1	Typical Simple Span Cast-in-Place Slab Bridge.....	9.1.1
9.1.2	Typical Multi-Span Cast-in-Place Slab Bridge.....	9.1.2
9.1.3	Steel Reinforcement in a Simply Supported Concrete Slab .....	9.1.3
9.1.4	Bearing Area: Cast-in-Place Slab.....	9.1.6

<b>Figure Nos.</b>		<b>Page Nos.</b>
9.1.5	Diagonal Shear Cracks Close to the Ends of a Slab Bridge.....	9.1.6
9.1.6	Shear Zone on the Underside of a Continuous Slab Bridge Near a Pier.....	9.1.7
9.1.7	Inspector Examining and Documenting Deficiencies in Concrete Slab.....	9.1.8
9.1.8	Concrete Slab Tension Zone: Delamination, Efflorescence, Rust and Stains.....	9.1.7
9.1.9	Deteriorated Slab Fascia due to Roadway Deicing Agents.....	9.1.9

**Topic 9.2  
Cast-In-Place  
Tee Beams**

9.2.1	Simple Span Tee Beam Bridge.....	9.2.1
9.2.2	Typical Tee Beam Cross Section.....	9.2.2
9.2.3	Typical Tee Beam Layout.....	9.2.2
9.2.4	Comparison Between Tee Beam and Concrete Encased Steel I-beam.....	9.2.3
9.2.5	Concrete Encased Steel I-beam.....	9.2.3
9.2.6	Tee Beam Primary and Secondary Members.....	9.2.4
9.2.7	Steel Reinforcement in a Concrete Tee Beam.....	9.2.5
9.2.8	Bearing Area of Typical Cast-in-Place Concrete Tee Beam Bridge.....	9.2.7
9.2.9	Spalled Tee Beam End.....	9.2.8
9.2.10	Deteriorated Tee Beam Bearing Area.....	9.2.8
9.2.11	Steel Bearing Supporting a Cast-in-Place Concrete Tee Beam.....	9.2.9
9.2.12	Shear Zone of Cast-in-Place Concrete Tee Beam Bridge.....	9.2.9
9.2.13	Flexure Cracks on a Tee Beam Stem.....	9.2.10
9.2.14	Flexure Cracks in Tee Beam Flange/Deck.....	9.2.10
9.2.15	Stem of a Cast-in-Place Concrete Tee Beam with Cracking and Efflorescence.....	9.2.11
9.2.16	Spall on the Bottom of the Stem of a Cast-in-Place Tee Beam with Corroded Main Steel Exposed.....	9.2.12
9.2.17	Asphalt Covered Tee Beam Deck.....	9.2.13
9.2.18	Deteriorated Tee Beam Stem Adjacent to Drain Hole.....	9.2.13
9.2.19	Deteriorated Tee Beam End Due to Drainage.....	9.2.14
9.2.20	Collision damage to Tee Beam Bridge Over a Highway.....	9.2.14
9.2.21	Components/Elements for Evaluation.....	9.2.15

	<b>Figure Nos.</b>	<b>Page Nos.</b>
<b>Topic 9.3</b>		
<b>Conventionally Reinforced Concrete Two-Girder System</b>		
9.3.1	Concrete Deck Two-Girder Bridge.....	9.3.1
9.3.2	Concrete Through Two-Girder Bridge .....	9.3.2
9.3.3	Concrete Deck Two-Girder, Underside View.....	9.3.2
9.3.4	Concrete Through Two-Girder Elevation View .....	9.3.3
9.3.5	Steel Reinforcement in a Concrete Through Two-Girder .....	9.3.4
9.3.6	Bearing Area of a Through Two-Girder Bridge .....	9.3.6
9.3.7	Typical Elevation View of a Through Two-Girder Bridge with Tension Zones Indicated .....	9.3.7
9.3.8	Exposed Reinforcement in a Through Two-Girder (under hammer).....	9.3.8
9.3.9	Close-up of an Interior Face of a Through Two-Girder with Heavy Scaling Due to Deicing Agents ....	9.3.9
<b>Topic 9.4</b>		
<b>Concrete Channel Beams</b>		
9.4.1	Underside View of Precast Channel Beam Bridge .....	9.4.1
9.4.2	Underside View of a Cast-in-Place Channel Beam Bridge.....	9.4.1
9.4.3	General View of a Precast Channel Beam Bridge .....	9.4.2
9.4.4	Cross Section of a Typical Channel Beam.....	9.4.3
9.4.5	Joint Leakage Between Channel Beams .....	9.4.7
9.4.6	Top of Deck View of Precast Channel Beam Bridge .	9.4.8
9.4.7	Stem Tie-Bolts .....	9.4.8
9.4.8	Close-up of Stem Tie-Bolts.....	9.4.9
9.4.9	Close-up of Intermediate Diaphragm.....	9.4.9
9.4.10	Components/Elements for Evaluation.....	9.4.11
<b>Topic 9.5</b>		
<b>Concrete Arches</b>		
9.5.1	Open Spandrel Arch Bridge .....	7.5.1
9.5.2	Multi-Span Closed Spandrel Arch Bridge .....	7.5.2
9.5.3	Concrete Through Arch Bridge.....	7.5.3
9.5.4	Precast Concrete Arch with Integral Vertical Legs.....	7.5.4
9.5.5	Precast Segmental Concrete Arch.....	7.5.4



<b>Figure Nos.</b>		<b>Page Nos.</b>
9.5.6	Precast Post-tensioned Concrete Arch without Spandrel Columns .....	7.5.5
9.5.7	Primary and Secondary Members of an Open Spandrel Arch .....	9.5.6
9.5.8	Primary Members of a Closed Spandrel Arch .....	9.5.7
9.5.9	Open Spandrel Arch and Spandrel Bent Column Reinforcement .....	9.5.8
9.5.10	Spandrel Bent Cap Reinforcement.....	9.5.8
9.5.11	Reinforcement in a Closed Spandrel Arch.....	9.5.9
9.5.12	Arch/Skewback Interface .....	9.5.12
9.5.13	Spandrel Column Bent Cap Interface .....	9.5.12
9.5.14	Spandrel Bent Tension Zones .....	9.5.13
9.5.15	Deteriorated Arch/Spandrel Wall Interface .....	9.5.14
9.5.16	Severe Scaling and Spalling on a Spandrel Column...	9.5.14
9.5.17	Inspection and Documentation of Arch Strut Deficiencies.....	9.5.15
9.5.18	Scaling and Contamination on an Arch Rib Due to a Failed Drainage System .....	9.5.15
9.5.19	Measurements for Open and Closed Spandrel Arches .....	9.5.18

**Topic 9.6  
Concrete Rigid  
Frames**

9.6.1	Multi-span Concrete Rigid Frame Bridges .....	9.6.1
9.6.2	Single-span Rectangular Concrete Rigid Frame Bridge.....	9.6.2
9.6.3	Three Span Concrete K-frame Bridge.....	9.6.2
9.6.4	Elevation of a Single Frame .....	9.6.3
9.6.5	Elevation of a K-frame.....	9.6.3
9.6.6	Deflected Simply Supported Slab versus Deflected Frame Shape.....	9.6.4
9.6.7	Primary Reinforcement in a Single Span Frame.....	9.6.4
9.6.8	Primary Reinforcement in a Multi-span Slab or Beam Frame .....	9.6.5
9.6.9	Primary Reinforcement in a K-frame.....	9.6.5
9.6.10	Shear Zones in Single Span and Multi-span Frames ..	9.6.8
9.6.11	Tension and Compression Zones in a Single Span Frame .....	9.6.9
9.6.12	Tension and Compression Zones in a Multi-span Frame .....	9.6.9
9.6.13	Roadway of a Rigid Frame Bridge with Asphalt Wearing Surface.....	9.6.10
9.6.14	Longitudinal Joint Between Slab Beam Frames .....	9.6.10

	<b>Figure Nos.</b>		<b>Page Nos.</b>
<b>Topic 9.7</b>			
<b>Precast and Prestressed Slabs</b>			
	9.7.1	Typical Prestressed Slab Beam Bridge .....	9.7.1
	9.7.2	Cross Section of a Typical Voided Slab .....	9.7.2
	9.7.3	Poutre Dalle Precast Slab Bridge .....	9.7.3
	9.7.4	Poutre Dalle Bridge Schematic .....	9.7.3
	9.7.5	Slab Beam Bridge Tension and Shear Reinforcement	9.7.4
	9.7.6	Leaking Joint between Adjacent Slab Units .....	9.7.7
	9.7.7	Exposed Strands in a Prestressed Slab Beam.....	9.7.8
<b>Topic 9.8</b>			
<b>Prestressed Double Tees</b>			
	9.8.1	Typical Prestressed Double Tee Beam .....	9.8.1
	9.8.2	Prestressed Double Tee Beam Typical Section .....	9.8.2
	9.8.3	Dapped End of a Prestressed Double Tee Beam.....	9.8.2
	9.8.4	Steel Reinforcement in a Prestressed Double Tee Beam .....	9.8.4
	9.8.5	Crack Locations for Dapped End Double Tee Beams	9.8.6
	9.8.6	Components/Elements for Evaluation.....	9.8.10
<b>Topic 9.9</b>			
<b>Prestressed I-Beams and Bulb-Tees</b>			
	9.9.1	Prestressed I-beam Superstructure .....	9.9.1
	9.9.2	AASHTO Cross Sections of Prestressed I-beams.....	9.9.2
	9.9.3	AASHTO Prestressed I-beam Bridge .....	9.9.2
	9.9.4	Cross Section of AASHTO-PCI Bulb-Tee Beams .....	9.9.3
	9.9.5	Placement of an AASHTO-PCI Bulb-Tee Beam.....	9.9.3
	9.9.6	Cross Section of AASHTO-PCI Bulb-Tee Beams .....	9.9.4
	9.9.7	Reactive Powder Concrete (RPC) Prestressed X-beam.....	9.9.5
	9.9.8	Continuous Prestressed I-beam Schematic .....	9.9.6
	9.9.9	Continuous Prestressed I-beam Bridge .....	9.9.6
	9.9.10	Spliced Bulb-Tees with Haunched Girder Sections Over Piers.....	9.9.7
	9.9.11	Extended Stirrups to Obtain Composite Action.....	9.9.7
	9.9.12	Concrete Intermediate and End Diaphragms .....	9.9.8
	9.9.13	Prestressed I-beam Reinforcement.....	9.9.9
	9.9.14	Prestressed Bulb-Tee Beam Reinforcement.....	9.9.9

<b>Figure Nos.</b>		<b>Page Nos.</b>
9.9.15	Bearing Area of a Typical Prestressed I-beam.....	9.9.12
9.9.16	Spalling Due to Poor Concrete Placement .....	9.9.12
9.9.17	Flexure Crack .....	9.9.14
9.9.18	Concrete End Diaphragm .....	9.9.15
9.9.19	Leakage of Water at Joint between Spans.....	9.9.15
9.9.20	Inspectors Evaluating Collision Damage on Prestressed Concrete I-beam .....	9.9.16
9.9.21	Collision Damage Repair on Prestressed Concrete I-beam: Note Epoxy Injection Ports and Gunit Repair .....	9.9.17

**Topic 9.10  
Prestressed  
Box Beams**

9.10.1	Typical Box Beam Bridge.....	9.10.1
9.10.2	Box Beam Cross Section.....	9.10.2
9.10.3	Box Beams at Fabrication Plant Showing Stirrups Extended as Shear Connectors and Extended Reinforcement for Continuity .....	9.10.3
9.10.4	Prestressed Box Beam Cross Sections: Adjacent and Spread Box Beams .....	9.10.4
9.10.5	Adjacent Box Beams: Top Flanges Acting as the Deck .....	9.10.5
9.10.6	Transverse Post-tensioning of an Adjacent Box Beam Bridge .....	9.10.6
9.10.7	Underside of a Typical Spread Box Beam.....	9.10.7
9.10.8	End and Intermediate Diaphragms on a Spread Box Beam Bridge .....	9.10.8
9.10.9	Schematic of Internal Diaphragms.....	9.10.8
9.10.10	Typical Prestressed Box Beam Reinforcement.....	9.10.9
9.10.11	Spalled Beam Ends with Exposed Prestressing Reinforcement.....	9.10.12
9.10.12	Exposed Shear Reinforcement at End of Box Beam ..	9.10.12
9.10.13	Longitudinal Cracks in Bottom Flange at Beam.....	9.10.13
9.10.14	Diagonal Shear Crack in Web of Beam .....	9.10.13
9.10.15	Spall and Exposed/Corroded Reinforcement .....	9.10.15
9.10.16	Close-up of Failed Strands due to Corrosion .....	9.10.15
9.10.17	Joint Leakage and Rust Stain .....	9.10.17
9.10.18	Close-up of Box Beam Collision Damage .....	9.10.17
9.10.19	Components/Elements for Evaluation.....	9.10.20
9.10.20	View Northeast of I-70 EB from Beneath Span 3.....	9.10.20
9.10.21	View East (Ahead Segments) from SR1014 Above Pier 2 .....	9.10.21
9.10.22	Post-Collapse Material Testing Assessment .....	9.10.22

<b>Figure Nos.</b>		<b>Page Nos.</b>
9.10.23	Post-Collapse Prestressing Strand Wire Fracture Laboratory Assessment .....	9.10.23
9.10.24	Prestressing Strand Corrosion and Section Loss Caused by Moisture Through Longitudinal Cracking	9.10.24
9.10.25	Prestressing Strand Corrosion and Section Loss Caused by Moisture Through Longitudinal Cracking and Shear Reinforcement Bars Transferring Moisture to Adjacent Longitudinal Reinforcement ....	9.10.24
9.10.26	Longitudinal Cracks (Top) and Corresponding Corroded Prestressing Strands after Concrete Removed (Bottom).....	9.10.24
9.10.27	Laboratory Testing of Torsion-Shear Cracking Near Barrier Joints .....	9.10.25
9.10.28	Cracking Near Barrier Joints.....	9.10.25
9.10.29	Water Leakage Through Parapet Deflection Joints ....	9.10.26
9.10.30	Unforeseen Fabrication Problems .....	9.10.27

**Topic 9.11  
Concrete Box  
Girders**

9.11.1	Segmental Precast Concrete Box Girder Bridge .....	9.11.1
9.11.2	Cast-in-place Concrete Box Girder Bridge .....	9.11.2
9.11.3	Multi-cell Girder Post Tensioned.....	9.11.2
9.11.4	Cast-in-place Concrete Box Girder Bridge .....	9.11.3
9.11.5	High Level Casting Formwork on Falsework.....	9.11.3
9.11.6	At-Grade Formwork with Post-tensioning Ducts .....	9.11.4
9.11.7	At-grade Casting – After Supporting Earth Removed	9.11.4
9.11.8	Basic Components/Elements of a Concrete Box Girder .....	9.11.5
9.11.9	Replaceable Deck on a Multiple Cell Cast-in-place Box Girder.....	9.11.5
9.11.10	Primary and Secondary Reinforcement in a Concrete Box Girder.....	9.11.6
9.11.11	Post-tensioning Spiral Anchorage Reinforcement Prior to Concrete Placement .....	9.11.7
9.11.12	Three-Dimensional Model Illustrating Confinement Reinforcement Around Anchorage and Deviation Blocks (Click to Open Interactive Model) .....	9.11.7
9.11.13	Adjacent Single Cell Boxes with Closure Pour .....	9.11.8
9.11.14	Segmental Concrete Bridge.....	9.11.9
9.11.15	Close-up of Box Girder Segments .....	9.11.9
9.11.15	Cast-in-place Box Girder Segment .....	9.11.10
9.11.16	Box Girder Segment.....	9.11.10
9.11.17	Cast-in-place Box Girder Segment .....	9.11.11

<b>Figure Nos.</b>		<b>Page Nos.</b>
9.11.18	Box Girder Segment During Construction with Temporary and Permanent Post-Tensioning (PT) Bars .....	9.11.11
9.11.19	Two Balanced Cantilever Methods – Using Cranes with Stability Towers At Each Pier and Using An Overhead Launching Gantry .....	9.11.12
9.11.20	Balanced Cantilever Construction Using an Overhead Launching Gantry .....	9.11.13
9.11.21	Typical Features of Precast Cantilever Box Girder Segments .....	9.11.13
9.11.22	Span-by-Span Construction (with Erection Truss) .....	9.11.14
9.11.23	Span-by-Span Construction (with Erection Truss) .....	9.11.14
9.11.24	Span-by-Span Total Span Erection (Lifting) .....	9.11.15
9.11.25	Progressive Placement Construction.....	9.11.16
9.11.26	Incremental Launching Method .....	9.11.16
9.11.27	Incremental Launching Overview (Note Temporary Pile Bent).....	9.11.17
9.11.28	Bearing Area of a Box Girder Bridge .....	9.11.20
9.11.29	Box Girder Cracks Induced by Shear.....	9.11.20
9.11.30	Box Girder Cracks Induced by Direct Tension.....	9.11.21
9.11.31	Box Girder Cracks Induced by Flexure (Positive Moment).....	9.11.22
9.11.32	Box Girder Cracks Induced by Flexure (Negative Moment).....	9.11.22
9.11.33	Box Girder Cracks Induced by Flexure Shear .....	9.11.23
9.11.34	Web Splitting Near an Anchorage Block.....	9.11.24
9.11.35	Deviation Block Used as a Hold-Down Point for External Post-Tensioning .....	9.11.24
9.11.36	Temporary Deviation Blocks Used to Maintain Tendon Alignment During Construction .....	9.11.25
9.11.37	Concrete Box Girder Drain Hole with Screen .....	9.11.26
9.11.38	Box Girder Cracks Induced by Torsion and Shear .....	9.11.27
9.11.39	Thermally Induced Transverse Cracks in Box Girder Flanges .....	9.11.28
9.11.40	Thermally Induced Longitudinal Cracks at Change in Box Girder Cross Section .....	9.11.28
9.11.41	Post-Tensioning Tendon Duct .....	9.11.29
9.11.42	Interior Formwork Left in Place .....	9.11.30
9.11.43	Location of Observation Points Across the Top Flange.....	9.11.31
9.11.44	Segmental Box Girder Bearings at Intermediate Pier.	9.11.33
9.11.45	Segmental Box Girder Cracks Adjacent to Anchorage Block.....	9.11.33
9.11.46	Close-up View of Box Girder Joint .....	9.11.34

<b>Figure Nos.</b>		<b>Page Nos.</b>
9.11.47	View of Box Girder Joint (Shear Keys) and Deviation Block .....	9.11.35
9.11.48	Box Girder Interior (End) Diaphragm and Post- Tensioning Ducts .....	9.11.35
9.11.49	Components/Elements for Evaluation.....	9.11.38

**Topic 10.1  
Rolled Steel  
Multi-Beams  
and Fabricated  
Steel Multi-  
Girders**

10.1.1	Simple Span Rolled Multi-Beam Bridge .....	10.1.2
10.1.2	Continuous Span Rolled Multi-Beam Bridge with Pin & Hanger .....	10.1.2
10.1.3	Rolled Multi-Beam Bridge with a Cover Plate .....	10.1.3
10.1.4	Built-up Riveted Plate Girder .....	10.1.3
10.1.5	Welded Plate Girder .....	10.1.4
10.1.6	Single Span Fabricated Multi-girder Bridge .....	10.1.4
10.1.7	Continuous Span Fabricated Multi-girder Bridge.....	10.1.5
10.1.8	Curved Fabricated Multi-girder Bridge .....	10.1.5
10.1.9	Fabricated Multi-girder Bridge with Pin & Hanger Connection .....	10.1.6
10.1.10	Combination Rolled Beams and Fabricated Girders...	10.1.6
10.1.11	Web Insert Plate for Multi-beam.....	10.1.7
10.1.12	Fabricated Variable Depth Girder Bridge .....	10.1.8
10.1.13	Rolled Beam (Primary Member) with Diaphragm (Secondary Member).....	10.1.9
10.1.14	Curved Multi-Girder Bridge .....	10.1.10
10.1.15	Straight Multi-Girder Bridge .....	10.1.10
10.1.16	Corroded Shear Zone on a Rolled Multi-beam Bridge .....	10.1.13
10.1.17	Flexural Zone on a Multi-Span Simple Span Rolled Multi-Beam Bridge .....	10.1.14
10.1.18	Flexural Zone on a Fabricated Continuous Span Multi-Girder Bridge .....	10.1.14
10.1.19	Negative Moment Region on a Continuous Span Rolled Multi-Beam Bridge.....	10.1.15
10.1.20	Negative Moment Region on a Continuous Span Fabricated Multi-Girder Bridge .....	10.1.15
10.1.21	End Diaphragm .....	10.1.16
10.1.22	Intermediate Diaphragm .....	10.1.17
10.1.23	Collision Damage on a Rolled Multi-Beam Bridge....	10.1.18

	<b>Figure Nos.</b>		<b>Page Nos.</b>
	10.1.24	Collision Damage on a Fabricated Multi-Girder Bridge.....	10.1.18
 <b>Topic 10.2 Steel Two- Girder Systems</b>			
	10.2.1	General View of a Dual Deck Girder Bridge.....	10.2.1
	10.2.2	Through Girder Bridge.....	10.2.2
	10.2.3	Through Girder Bridge with Limited Underclearance.....	10.2.2
	10.2.4	Through Girder Bridge with Three Girders .....	10.2.3
	10.2.5	Two-Girder Bridge with Girder-Floorbeam System...	10.2.4
	10.2.6	Two-Girder Bridge with Girder-Floorbeam-Stringer System.....	10.2.4
	10.2.7	Two-Girder Bridge with GFS System with Stacked Floorbeam and Stringers .....	10.2.5
	10.2.8	Underside View of Deck Girder Bridge with Lateral Bracing System .....	10.2.6
	10.2.9	Underside View of Through Girder Bridge with Lateral Bracing.....	10.2.6
	10.2.10	Two-Girder Bridge with Pin-and-Hanger Assembly ..	10.2.7
	10.2.11	Shear Zone on a Deck Girder Bridge.....	10.2.10
	10.2.12	Web Area Near Support on a Through Girder Bridge	10.2.10
	10.2.13	Flexural Zone on a Two-Girder Bridge .....	10.2.11
	10.2.14	Longitudinal Stiffener in Tension Zone on a Two-Girder Bridge .....	10.2.11
	10.2.15	Flexural Zone on a Through Girder Bridge .....	10.2.12
	10.2.16	Lateral Bracing Connection on a Deck Girder Bridge.....	10.2.12
	10.2.17	Lateral Bracing Connection on a Through Girder Bridge.....	10.2.13
	10.2.18	Collision Damage to a Deck Girder Bridge .....	10.2.14
	10.2.19	Collision Damage to a Through Girder Bridge.....	10.2.14
 <b>Topic 10.3 Steel Box Beams and Girders</b>			
	10.3.1	Simple Span Box Girder Bridge .....	10.3.1
	10.3.2	Curved Box Girder Bridge .....	10.3.1
	10.3.3	Box Girders with Multiple Interior Webs .....	10.3.2
	10.3.4	Spread Box Girders.....	10.3.2
	10.3.5	Diaphragms – K-Bracing Internal Transverse Stiffeners .....	10.3.3

<b>Figure Nos.</b>		<b>Page Nos.</b>
10.3.6	External Diaphragm .....	10.3.4
10.3.7	Box Girder Access Door .....	10.3.4
10.3.8	Box Girder Cross Section with Composite Deck.....	10.3.5
10.3.9	Box Girder Cross Section (at floorbeam) with Orthotropic Steel Plate Deck.....	10.3.5
10.3.10	Box Girder Shear Zone .....	10.3.8
10.3.11	Continuous Box Girders.....	10.3.8
10.3.12	Non-Redundant Box Girder Bridges.....	10.3.11
10.3.13	Redundant Box Girder Bridge .....	10.3.11

## **Topic 10.4 Steel Trusses**

10.4.1	Single Span Truss.....	10.4.1
10.4.2	Through-Pony-Deck Truss Comparisons.....	10.4.2
10.4.3	Through Truss .....	10.4.2
10.4.4	Pony Truss.....	10.4.3
10.4.5	Deck Truss .....	10.4.3
10.4.6	Suspension Bridge with Stiffening Truss.....	10.4.4
10.4.7	Deck Arch Bridge with Stiffening Truss .....	10.4.4
10.4.8	Vertical Lift Bridge .....	10.4.5
10.4.9	Various Truss Designs .....	10.4.5
10.4.10	Single (Simple) Span Camel Back Pratt Truss .....	10.4.6
10.4.11	Single (Simple) Span Through Truss .....	10.4.6
10.4.12	Multiple Span Pony Truss .....	10.4.7
10.4.13	Multiple Span Through Truss .....	10.4.7
10.4.14	Continuous Through Truss.....	10.4.8
10.4.15	Cantilever Deck Truss.....	10.4.8
10.4.16	Cantilever Through Truss .....	10.4.9
10.4.17	Pin-and-Hanger Assembly for Cantilevered Truss .....	10.4.9
10.4.18	Truss Members, Floor systems and Bracing .....	10.4.10
10.4.19	Rolled Steel Shapes.....	10.4.10
10.4.20	Built-Up Sections .....	10.4.11
10.4.21	Axial Loads in Truss Chord Members .....	10.4.12
10.4.22	“Imaginary Cable – Imaginary Arch” .....	10.4.13
10.4.23	Vertical Member Stress Prediction Method.....	10.4.14
10.4.24	Vertical Member Stress Prediction Method	10.4.15
10.4.25	Vertical Member Stress Prediction Method	10.4.15
10.4.26	Truss Panel Point using Shop Rivets and Field Bolts	10.4.16
10.4.27	Pin Connected Truss .....	10.4.17
10.4.28	Truss Panel Point Numbering System .....	10.4.17
10.4.29	Deck Truss .....	10.4.18
10.4.30	A Pennsylvania Truss, a Subdivided Pratt Truss with a Camel Back Top Chord.....	10.4.18
10.4.31	Floorbeam Stringer Floor System .....	10.4.19



<b>Figure Nos.</b>		<b>Page Nos.</b>
10.4.32	Floorbeam Floor System .....	10.4.20
10.4.33	Inspection of Upper Lateral Bracing.....	10.4.20
10.4.34	Lower Lateral Bracing .....	10.4.21
10.4.35	Lateral Bracing Gusset Plate .....	10.4.21
10.4.36	Sway Bracing .....	10.4.22
10.4.37	Sway Bracing .....	10.4.22
10.4.38	Portal Bracing with Attached Load Posting Sign .....	10.4.23
10.4.39	Pony Truss “Sway Bracing” .....	10.4.23
10.4.40	Truss Design Drawings: Member Load Table .....	10.4.27
10.4.41	Corrosion and Section Loss on Truss Bottom Chord	10.4.28
10.4.42	Inside of Box Chord Member .....	10.4.29
10.4.43	Cracked Forge Zone on an Eyebars.....	10.4.29
10.4.44	Cracked Forge Zone on a Loop Rod.....	10.4.30
10.4.45	Bottom Chord with Eyebars.....	10.4.30
10.4.46	Welded Repair to Loop Rod .....	10.4.31
10.4.47	Bowed Bottom Chord Eyebars Member.....	10.4.31
10.4.48	Buckled Bottom Chord Member Due to Abutment Movement .....	10.4.32
10.4.49	Collision Damage to Truss members Due to Overheight Vehicle .....	10.4.33
10.4.50	Buckled End Post .....	10.4.33
10.4.51	Gusset Plate Connection with Coating System Failure .....	10.4.34
10.4.52	Corroded Floorbeam End and Connection with Deicing Chemical Residue.....	10.4.35
10.4.53	Corroded Stringers under an Open Grid Deck.....	10.4.36
10.4.54	Corroded End of Stringer .....	10.4.36
10.4.55	Corroded Floorbeams and Stringers.....	10.4.37
10.4.56	Collision Damage to Portal .....	10.4.38
10.4.57	Lateral Bracing with Corrosion.....	10.4.39
10.4.58	Sway Bracing with Pack Rust .....	10.4.38
10.4.59	Other Elements.....	10.4.40

**Topic 10.5  
Steel Arches**

10.5.1	Deck Arch Bridge .....	10.5.1
10.5.2	Through Arch Bridge .....	10.5.1
10.5.3	Tied Arch Bridge .....	10.5.2
10.5.4	Deck Arch .....	10.5.3
10.5.5	Solid Ribbed Deck Arch .....	10.5.3
10.5.6	Braced Rib Deck Arch, New River Gorge, WV .....	10.5.4
10.5.7	Spandrel Braced Deck Arch with Six Arch Ribs .....	10.5.4
10.5.8	Hinge Pin at Skewback for Spandrel Braced Deck.....	10.5.5
10.5.9	Solid Ribbed Deck Arch Primary Members .....	10.5.5

<b>Figure Nos.</b>		<b>Page Nos.</b>
10.5.10	Solid Ribbed Deck Arch Secondary Members .....	10.5.6
10.5.11	Elevation View of a Braced Ribbed Through Arch ....	10.5.7
10.5.12	Through Arch Primary Members .....	10.5.8
10.5.13	Through Arch Secondary Members .....	10.5.8
10.5.14	Three-Span Tied Arch Bridge.....	10.5.9
10.5.15	Tied Arch Primary Members .....	10.5.10
10.5.16	Tied Arch Secondary Members .....	10.5.10
10.5.17	Tied Arch Bridge with Fracture Critical Eyebar Tie Members.....	10.5.11
10.5.18	Floor System on a Through Arch.....	10.5.14
10.5.19	Through Truss Arch Members .....	10.5.14
10.5.20	Braced Rib Deck Arch Showing Spandrel Columns ..	10.5.15
10.5.21	Hanger Connection on a Through Arch.....	10.5.15
10.5.22	Performing Baseline Hardness Test on Fire Damaged Arch Cables .....	10.5.16
10.5.23	Bracing Members in Deck Arch Bridge .....	10.5.19
10.5.24	Through Arch Member Exposed to Traffic .....	10.5.20

**Topic 10.6  
Steel Rigid  
Frames**

10.6.1	Typical Rigid K-Frame Constructed of Two Frames .	10.6.1
10.6.2	Typical Rigid Frame Constructed of Multiple Frames .....	10.6.2
10.6.3	Connection between Legs and Girder Portion .....	10.6.3
10.6.4	Delta Frame.....	10.6.4
10.6.5	Bearings .....	10.6.5
10.6.6	Transverse, Longitudinal, and Radial Stiffeners on a Frame Knee .....	10.6.5
10.6.7	Two Frame Bridge with Floorbeam-Stringer Floor System.....	10.6.6
10.6.8	Lateral Bracing for Frame Legs .....	10.6.7
10.6.9	Lateral Bracing and Diaphragms .....	10.6.8
10.6.10	Stress Zones in a Frame .....	10.6.8
10.6.11	Fracture Critical Structure - No Load Path Redundancy.....	10.6.9
10.6.12	Multiple Frame Rigid Frame – Not a Fracture Critical Structure .....	10.6.9
10.6.13	Bearing Area of a Two Frame Bridge.....	10.6.12
10.6.14	Flexural Zones (Greatest Bending Moment).....	10.6.12

	<b>Figure Nos.</b>		<b>Page Nos.</b>
<b>Topic 10.7</b>			
<b>Pin and Hanger Assemblies</b>			
10.7.1	Typical Pin-and-Hanger Assembly .....	10.7.1	10.7.1
10.7.2	Single Pin with Riveted Pin Plate .....	10.7.2	10.7.2
10.7.3	Pin-and-Hanger Assembly Locations Relative to Piers.....	10.7.2	10.7.2
10.7.4	Pin-and-Hanger Assembly .....	10.7.3	10.7.3
10.7.5	Pin Cap with Through Bolt .....	10.7.4	10.7.4
10.7.6	Threaded Pin with Retaining Nut.....	10.7.5	10.7.5
10.7.7	Plate Hanger and Eyebar Shape Hanger Link.....	10.7.5	10.7.5
10.7.8	Pin Cap, Through Bolt and Nut .....	10.7.6	10.7.6
10.7.9	Retaining Nut .....	10.7.6	10.7.6
10.7.10	Web Doubler Plates.....	10.7.7	10.7.7
10.7.11	Design Stress in a Hanger Link (Tension Only) .....	10.7.8	10.7.8
10.7.12	Actual Stress in a Hanger Link (Tension and Bending).....	10.7.8	10.7.8
10.7.13	Design Stress in a Pin (Shear and Bearing) .....	10.7.9	10.7.9
10.7.14	Actual Stress in a Pin (Shear, Bearing and Torsion)...	10.7.9	10.7.9
10.7.15	Mianus River Bridge Failure.....	10.7.10	10.7.10
10.7.16	Multi-girder Bridge with Pin-and-Hanger Assemblies .....	10.7.11	10.7.11
10.7.17	Ultrasonic Testing of a Pin.....	10.7.13	10.7.13
10.7.18	Alternate Hanger Link Retaining System .....	10.7.14	10.7.14
10.7.19	Pin Measurement Locations .....	10.7.15	10.7.15
10.7.20	Rust Stains from Pin Corrosion .....	10.7.16	10.7.16
10.7.21	Corroded Hanger Plate.....	10.7.17	10.7.17
10.7.22	Bowing Due to Out-of-Plane Distortion of Hanger ....	10.7.18	10.7.18
10.7.23	Fatigue Cracks in Pin-and-Hanger Assemblies.....	10.7.18	10.7.18
10.7.24	Corroded Pin and Hanger Assembly.....	10.7.19	10.7.19
10.7.25	Underslung Catcher Retrofit .....	10.7.21	10.7.21
10.7.26	Stainless Steel Pin-and-Hanger Assembly .....	10.7.21	10.7.21
<b>Topic 10.8</b>			
<b>Gusset Plates</b>			
10.8.1	Steel Truss Superstructure with Gusset Plates .....	10.8.1	10.8.1
10.8.2	Steel Deck Arch Superstructure with Stiffening Truss and Gusset Plates.....	10.8.2	10.8.2
10.8.3	Steel Gusset Plate with Riveted Connections .....	10.8.3	10.8.3
10.8.4	Steel Gusset Plate with Welded Connections .....	10.8.3	10.8.3
10.8.5	Steel Gusset Plate with Riveted, Bolted and Welded Connections.....	10.8.3	10.8.3

<b>Figure Nos.</b>		<b>Page Nos.</b>
10.8.6	Steel Gusset Plates Connecting Timber Primary Truss Members.....	10.8.4
10.8.7	Odd-Shaped Gusset Plate Connecting Primary Load- Carrying Truss Members .....	10.8.5
10.8.8	Gusset Plate Connecting Primary Load-Carrying Truss Members.....	10.8.5
10.8.9	Potential Block Shear Rupture Planes for Gusset Plates in Tension .....	10.8.7
10.8.10	Examples of Gross Section Shear Yielding Planes.....	10.8.8
10.8.11	Examples of Net Section Shear Fracture Planes.....	10.8.8
10.8.12	Example Showing the Unbraced Length and Effective Width for a Gusset Plate in Compression ...	10.8.9
10.8.13	Examples of Combined Flexural and Axial Load Planes .....	10.8.10
10.8.14	Gusset Plate Connecting Secondary (Bracing) Members to a Primary Load-Carrying Truss Member .....	10.8.11
10.8.15	Gusset Plate Connecting Secondary (Bracing) Members on a Steel Two-Girder Bridge.....	10.8.11
10.8.16	Gusset Plate Field Measurements .....	10.8.14
10.8.17	General Corrosion of Gusset Plates .....	10.8.15
10.8.18	Corrosion Line Viewed from Inside and Outside of Gusset Plate.....	10.8.16
10.8.19	Inspector Using a D-meter to Measure the Thickness of the Gusset Plate.....	10.8.17
10.8.20	Inspector Using Calipers Measure the Thickness of the Gusset Plate.....	10.8.18
10.8.21	Inspector Using a Straightedge and Tape to Measure the Section Loss of the Gusset Plate .....	10.8.18
10.8.22	V-WAC Gage and Inspector Using the V-WAC in the Field to Measure the Section Loss of the Gusset Plate.....	10.8.19
10.8.23	Inspector Using a Portable Ultrasonic Testing Inspection System .....	10.8.20
10.8.24	Phased Array Data Acquisition Software .....	10.8.20
10.8.25	Cracked Gusset Plate and Point of Crack Initiation....	10.8.21
10.8.26	Partial Length Cracked Tack Weld.....	10.8.22
10.8.27	Gusset Plate Buckling (Compression) Failure due to Major Gusset Plate Section Loss .....	10.8.23
10.8.28	Gusset Plate with Paint Failure .....	10.8.24
10.8.29	Missing Bolts on Gusset Plate .....	10.8.25
10.8.30	Plate Thickening and Free Edge Stiffening on Gusset Plate.....	10.8.27
10.8.31	Poorly Designed Welded Retrofit.....	10.8.27

<b>Figure Nos.</b>		<b>Page Nos.</b>
10.8.32	Unbraced Gusset Plate Edges and Reference Line .....	10.8.28
10.8.33	Inspector Measuring Out-of-Plane Distortion Using String Line and Tape Measure .....	10.8.29
10.8.34	Collapsed I-35W Mississippi River Bridge .....	10.8.32

**Topic 10.9  
Steel Eyebars**

10.9.1	Typical Eyebars Tension Member on an Arch .....	10.9.1
10.9.2	Eyebars Cantilevered Truss Bridge (Queensboro Bridge, NYC) .....	10.9.1
10.9.3	Eyebars Chain Suspension Bridge .....	10.9.2
10.9.4	Anchorage Eyebars .....	10.9.2
10.9.5	Collapsed Silver Bridge .....	10.9.3
10.9.6	Inspection of Eyebars .....	10.9.4
10.9.7	Retrofit of Eyebars to Add Redundancy .....	10.9.4
10.9.8	Eyebars Connection with Corrosion .....	10.9.5
10.9.9	Eads Bridge, St. Louis .....	10.9.6
10.9.10	Forged Loop Rod .....	10.9.7
10.9.11	Close-up of the End of a Loop Rod .....	10.9.7
10.9.12	Forged Eyebars by Mechanical forge Press .....	10.9.8
10.9.13	Eyebars Pin Hole (Disassembled Connection) .....	10.9.8
10.9.14	Eyebars Dimensions .....	10.9.9
10.9.15	Loosely Packed Eyebars Connection .....	10.9.10
10.9.16	Tightly Packed Eyebars Connection .....	10.9.10
10.9.17	Steel Pin Spacer or Filling Ring .....	10.9.11
10.9.18	Non-redundant Eyebars Member .....	10.9.12
10.9.19	Close-up of the Forge Zone on an Eyebars (Arrow denotes crack) .....	10.9.15
10.9.20	Forge Loop is completely apart .....	10.9.15
10.9.21	Bowed Eyebars Member .....	10.9.16
10.9.22	Buckled Eyebars due to Abutment Movement .....	10.9.17
10.9.23	Corroded Spacer .....	10.9.18
10.9.24	Asymmetry at an Eyebars Connection .....	10.9.18
10.9.25	Eyebars Member with Unequal Load Distribution .....	10.9.19
10.9.26	Welds on Loop Rods .....	10.9.20
10.9.27	Welded Repair to Loop Rods .....	10.9.20
10.9.28	Turnbuckle on a Truss Diagonal .....	10.9.21
10.9.29	Welded Repair to Turnbuckles .....	10.9.21
10.9.30	Ultrasonic Inspection of Eyebars Pin .....	10.9.22
10.9.31	Fracture Critical Bottom Chord Truss Member: Internally Non-redundant Eyebars .....	10.9.23
10.9.32	Fracture Critical Top Chord Truss Member: Internally Redundant Eyebars .....	10.9.23

<b>Topic 11.1</b>	<b>Figure Nos.</b>	<b>Page Nos.</b>
<b>Bridge Bearings</b>		
11.1.1	Three Functions of a Bearing.....	11.1.1
11.1.2	Fixed and Movable Expansion Bearings.....	11.1.2
11.1.3	Elements of a Typical Bridge Bearing .....	11.1.3
11.1.4	Lubricated Steel Plate Bearing.....	11.1.5
11.1.5	Bronze Sliding Plate Bearing .....	11.1.6
11.1.6	Self-Lubricating Bronze Sliding Plate Bearing .....	11.1.7
11.1.7	Single Roller Bearing.....	11.1.8
11.1.8	Roller Nest Bearing.....	11.1.9
11.1.9	Rocker Bearing .....	11.1.8
11.1.10	Segmental Rocker Bearing.....	11.1.10
11.1.11	Segmental Rocker Nest Bearing .....	11.1.11
11.1.12	Pinned Rocker Bearing .....	11.1.12
11.1.13	Plain Neoprene Bearing Pad .....	11.1.13
11.1.14	Laminated Neoprene Bearing Pad .....	11.1.14
11.1.15	Neoprene Pot Bearing with Guide Bars .....	11.1.15
11.1.16	Disc Bearing.....	11.1.16
11.1.17	Fixed Bearing.....	11.1.16
11.1.18	Enclosed or Concealed Bearing .....	11.1.17
11.1.19	Pin and Link Bearing .....	11.1.18
11.1.20	Restraining Bearing.....	11.1.19
11.1.20	Restraining Bearing.....	11.1.19
11.1.21	Sketch of a Lead Core Isolation Bearing .....	11.1.22
11.1.22	Lead Core Isolation Bearing .....	11.1.20
11.1.23	Friction Pendulum Bearing .....	11.1.21
11.1.24	Sketch of a Friction Pendulum Bearing .....	11.1.22
11.1.25	Spherical Pot Bearing.....	11.1.23
11.1.26	Spalling of Concrete Bridge Seat Due to High Edge Stress .....	11.1.25
11.1.27	Ultrasonic Testing Inspection of a Pin in a Bearing ...	11.1.26
11.1.28	Bent Anchor Bolt due to Excessive Horizontal Movement .....	11.1.24
11.1.26	Uplift at Bridge Bearing.....	11.1.25
11.1.27	Sliding Plate Bearing Inspection Checklist Items.....	11.1.26
11.1.28	Heavy Corrosion on a Steel Rocker Bearing .....	11.1.27
11.1.29	Rocker Bearing with Excessive Horizontal Movement .....	11.1.28
11.1.30	Bent Anchor Bolt due to Excessive Horizontal Movement .....	11.1.29
11.1.31	Uplift at Bridge Bearing.....	11.1.29
11.1.32	Longitudinal Misalignment in Bronze Sliding Plate Bearing .....	11.1.30

<b>Figure Nos.</b>		<b>Page Nos.</b>
11.1.33	Sliding Plate Bearing Inspection Checklist Items .....	11.1.31
11.1.34	Damaged Roller Nest Bearing .....	11.1.32
11.1.35	Rocker Bearing Inspection Checklist Items .....	11.1.33
11.1.36	Excessive Tilt in a Segmental Rocker.....	11.1.34
11.1.37	Frozen Rocker Nest.....	11.1.35
11.1.38	Frozen Rocker Nest.....	11.1.35
11.1.39	Elastomeric Bearing Inspection Checklist Items .....	11.1.37
11.1.40	Neoprene Bearing Pad Excessive Bulging.....	11.1.38
11.1.41	Lead Core Isolation Bearing .....	11.1.39
11.1.42	Serious Bearing Condition .....	11.1.41

**Topic 12.1  
Abutments and  
Wingwalls**

12.1.1	Schematic of Common Abutment Types .....	12.1.3
12.1.2	Section View of Less Common Abutment Types (Mechanically Stabilized Earth .....	12.1.4
12.1.3	Section View of Less Common Abutment Types (Geosynthetic Reinforced Soil).....	12.1.5
12.1.4	Full Height Abutment .....	12.1.6
12.1.5	Stub Abutment .....	12.1.6
12.1.6	Open Abutment .....	12.1.7
12.1.7	Integral Abutment .....	12.1.8
12.1.9	Mechanically Stabilized Earth Abutment (Note Precast Concrete Panels).....	12.1.10
12.1.10	Mechanically Stabilized Earth Wall Under Construction .....	12.1.10
12.1.11	GRS Bridge Abutment at the FHWA Turner- Fairbank Highway Research Center.....	12.1.11
12.1.12	View of the Founders/Meadows Bridge Supported by GRS Abutments .....	12.1.12
12.1.13	Plain Unreinforced Concrete Gravity Abutment.....	12.1.12
12.1.14	Reinforced Concrete Cantilever Abutment.....	12.1.13
12.1.15	Stone Masonry Gravity Abutment .....	12.1.13
12.1.14	Combination: Timber Pile Bent Abutment with Reinforced Concrete Cap .....	12.1.12
12.1.17	Steel Abutment.....	12.1.14
12.1.18	Primary Reinforcement in Concrete Abutments .....	12.1.15
12.1.19	Secondary Reinforcement in Concrete Abutments .....	12.1.15
12.1.20	Cheek Wall.....	10.1.16
12.1.21	Spread Footing/Deep Foundations.....	12.1.17
12.1.22	Stub Abutment on Piles with Piles Exposed.....	12.1.18
12.1.23	Typical Wingwall.....	12.1.19
12.1.24	Straight Wingwall .....	12.1.19

<b>Figure Nos.</b>		<b>Page Nos.</b>
12.1.25	Flared Wingwall.....	12.1.20
12.1.26	U-Wingwall.....	12.1.20
12.1.27	Integral Wingwall.....	12.1.21
12.1.28	Independent MSE Wingwall.....	12.1.21
12.1.29	Masonry Wingwall.....	12.1.22
12.1.30	Primary Reinforcement in Concrete Cantilever Wingwall.....	12.1.22
12.1.31	Cracking in Bearing Seat of Concrete and Stone Abutment.....	12.1.24
12.1.32	Spalled Concrete Wingwall.....	12.1.25
12.1.33	Cracking and Efflorescence in Abutment Backwall ...	12.1.25
12.1.34	Stone Masonry Abutment with Deteriorated Joints ....	12.1.26
12.1.35	Steel Abutment.....	12.1.26
12.1.36	Decay caused by insects in Timber Abutment.....	12.1.27
12.1.37	Local Failure in Timber Pile due to Lateral Movement of Abutment .....	12.1.28
12.1.38	Decayed Lagging and Abrasion Caused by Scour of a Timber Pile Bent Abutment .....	12.1.28
12.1.39	Differential Settlement between Different Substructure Units.....	12.1.33
12.1.40	Differential Settlement Under an Abutment .....	12.1.33
12.1.41	Crack in Abutment due to Settlement .....	12.1.34
12.1.42	Lateral Movement of an Abutment due to Slope Failure .....	12.1.34
12.1.43	Excessive Rocker Bearing Displacement Indicating Possible Lateral Displacement of Abutment.....	12.1.35
12.1.44	Vertical Misalignment between Approach Slab (left) and Bridge Deck (right) .....	12.1.36
12.1.45	Erosion at Abutment Exposing Footing.....	12.1.36
12.1.46	Rotational Movement of an Abutment.....	12.1.37
12.1.47	Rotational Movement at Abutment.....	12.1.38
12.1.48	Rotational Movement due to “Lateral Squeeze” of Embankment Material.....	12.1.38
12.1.49	Rotational Movement at Concrete Wingwall.....	12.1.39
12.1.50	Abutment with Undermining due to Scour .....	12.1.41
12.1.51	Inspector Checking for Scour .....	12.1.41
12.1.52	Scour and Possible Undermining of Concrete Wingwall.....	12.1.42

**Topic 12.2  
Piers and Bents**

12.2.1	Example of Piers as Intermediate Supports for a Bridge.....	12.2.1
12.2.2	Solid Shaft Pier .....	12.2.2



<b>Figure Nos.</b>		<b>Page Nos.</b>
12.2.3	Column Pier .....	12.2.2
12.2.4	Column Pier with Web Wall .....	12.2.3
12.2.5	Column Pier with Web Wall .....	12.2.3
12.2.6	Single Stem Pier (Cantilever or Hammerhead).....	12.2.4
12.2.7	Cantilever Pier.....	12.2.4
12.2.8	Column Bent or Open Bent.....	12.2.5
12.2.9	Concrete Pile Bent.....	12.2.5
12.2.10	Concrete Pier with Integral Steel Pier Cap .....	12.2.6
12.2.11	Integral Concrete Pier and Pier Cap.....	12.2.7
12.2.12	Integral Concrete Pier and Pier Cap.....	12.2.7
12.2.13	Reinforced Concrete Piers under Construction.....	12.2.8
12.2.14	Stone Masonry Pier .....	12.2.8
12.2.15	Steel Bent .....	12.2.9
12.2.16	Timber Pile Bent .....	12.2.9
12.2.17	Combination: Reinforced Concrete Column with Steel Pier Cap.....	12.2.10
12.2.18	Primary Reinforcement in Column Bent with Web Wall .....	12.2.11
12.2.19	Secondary Reinforcement in Column Bent with Web Wall .....	12.2.11
12.2.20	Primary Reinforcement in Column Bents .....	12.2.12
12.2.21	Primary Reinforcement for a Cantilevered Pier.....	12.2.12
12.2.22	Cantilevered Piers Joined by a Web Wall.....	12.2.13
12.2.23	Pile Bent .....	12.2.14
12.2.24	Collision Wall .....	12.2.15
12.2.25	Collision Wall .....	12.2.15
12.2.26	Concrete Block Dolphin.....	12.2.16
12.2.27	Timber Dolphin.....	12.2.16
12.2.28	Pier Fender .....	12.2.17
12.2.29	Fender System.....	12.2.17
12.2.30	Concrete Spalling due to Contaminated Drainage .....	12.2.19
12.2.31	Crack in Concrete Bent Cap.....	12.2.20
12.2.32	Concrete Spalling on Bent Cap.....	12.2.20
12.2.33	Collision Damage to Concrete Pier Column.....	12.2.21
12.2.34	Deteriorated and Missing Stone at Masonry Pier .....	12.2.22
12.2.35	Deterioration of Steel Bent Leg .....	12.2.23
12.2.36	Corrosion of Steel Pile Bent at Water Surface.....	12.2.23
12.2.37	Steel Column Pile Bent with Cantilever - High Stress Areas for Moment, Shear and Bearing .....	12.2.24
12.2.38	Decay in Timber Bent Cap (Note “Protective” Cover / Flashing) .....	12.2.25
12.2.39	Timber Bent Columns in Water .....	12.2.25
12.2.40	Decay of Timber Bent Column at Ground Line/Loose Connection .....	12.2.26

<b>Figure Nos.</b>		<b>Page Nos.</b>
12.2.41	Timber Pile Bent with Overstress-Partial “Brooming” Failure at First Pile .....	12.2.26
12.2.42	Timber Pile Damage due to Limnoria Marine Borers	12.2.27
12.2.43	Timber Bent Damage due to Shipworm Marine Borers .....	12.2.27
12.2.44	Differential Settlement between Different Substructure Units .....	12.2.31
12.2.45	Differential Settlement Under a Pier.....	12.2.31
12.2.46	Superstructure Evidence of Pier Settlement.....	12.2.32
12.2.47	Cracks in Bent Cap due to Lateral Movement of Bent during Earthquake .....	10.2.33
12.2.48	Pier Movement and Superstructure Damage due to Scour/Undermining .....	12.2.33
12.2.49	Tipping of Bent due to Scour/Undermining .....	12.2.34
12.2.50	Repaired Concrete Column Bent .....	12.2.36
12.2.51	Fracture Critical Steel Bent.....	12.2.37
12.2.52	Concrete Dolphins.....	12.2.38
12.2.53	Steel Fender.....	12.2.38
12.2.54	Timber Fender System with Deteriorated Piles .....	12.2.39

**Topic 13.1  
Waterway  
Elements**

13.1.1	Failure Due to High Water Levels During Hurricane: Aerial View .....	13.1.2
13.1.2	Failure Due to High Water Levels During Hurricane: Close-Up View.....	13.1.2
13.1.3	Pier Foundation Failure.....	13.1.3
13.1.4	Typical Waterway Cross Section Showing Well Defined Channel Depression.....	13.1.5
13.1.5	Plan View of Rivers .....	13.1.6
13.1.6	Meandering River.....	13.1.7
13.1.7	Typical Floodplain .....	13.1.8
13.1.8	Hydraulic Waterway Opening.....	13.1.8
13.1.9	Crushed Stone Riprap .....	13.1.10
13.1.10	Spurs.....	13.1.11
13.1.11	Guide Banks Constructed on Kickapoo Creek Near Peoria, Illinois .....	13.1.11
13.1.12	Gabion Basket Serving as Slope Protection.....	13.1.12
13.1.13	Slope Stabilization .....	13.1.12
13.1.14	Concrete Revetment Mat.....	13.1.13
13.1.15	Formed Concrete Channel Lining.....	13.1.13
13.1.16	Concrete Footing Apron on a Masonry Abutment.....	13.1.14

<b>Figure Nos.</b>		<b>Page Nos.</b>
13.1.17	Concrete Footing Apron to Protect a Spread Footing from Undermining.....	13.1.14
 <b>Topic 13.2 Inspection of Waterways</b>		
13.2.1	Flood Flow Around a Pier Showing High Streamflow Velocity .....	13.2.2
13.2.2	Streambed Aggradation.....	13.2.4
13.2.3	Streambed Degradation.....	13.2.4
13.2.4	General Scour.....	13.2.5
12.2.5	Close-up of General Scour of a Pier .....	13.2.6
13.2.6	Stream Contraction Schematic.....	13.2.7
13.2.7	Contraction Scour Photograph .....	13.2.8
13.2.8	Large number of Piers Combine to Reduce the Hydraulic Opening .....	13.2.8
13.2.9	Vegetation Constricting the Waterway .....	13.2.9
13.2.10	Sediment Deposits Within the Waterway Opening ....	13.2.9
13.2.11	Ice in Stream Resulting in Possible Contraction Scour .....	13.2.10
13.2.12	Debris Build-up in the Waterway .....	13.2.10
13.2.13	Local Scour at a Pier .....	13.2.12
13.2.14	Local Scour at a Pier .....	13.2.12
13.2.15	Wide Pier.....	13.2.13
13.2.16	Long Pier.....	13.2.13
13.2.17	Lateral Stream Migration endangering an Abutment..	13.2.15
13.2.18	Streambank Damage .....	13.2.16
13.2.19	Sloughing Streambank .....	13.2.16
13.2.20	Undermined Streambank.....	13.2.17
13.2.21	Stream Meander Changes .....	13.2.17
13.2.22	Channel Widening.....	13.2.18
13.2.23	Schematic of Noncohesive Bank Material.....	13.2.19
13.2.24	Schematic of Cohesive Bank Material.....	13.2.19
13.2.25	Schematic of Cohesive Bank Material.....	13.2.19
13.2.26	End and Side View of Scour and Undermining .....	13.2.21
13.2.27	Pier Settlement due to Undermining .....	13.2.22
13.2.28	Probing Rod and Waders .....	13.2.24
13.2.29	Surface Supplied Air Diving Equipment .....	13.2.25
13.2.30	Rapid Flow Velocity .....	13.2.26
13.2.31	Navigable Waterway.....	13.2.26
13.2.32	Streambed Cross-Section .....	13.2.27
13.2.33	Streambed Profile.....	13.2.28
13.2.34	Scour Monitoring Collar .....	13.2.29

<b>Figure Nos.</b>		<b>Page Nos.</b>
13.2.35	Pile Bent Deterioration Normally Hidden Underwater .....	13.2.30
13.2.36	Out of Plumb Pier Column.....	13.2.30
13.2.37	Superstructure Misalignment .....	13.2.31
13.2.38	Drift Lodged in a Superstructure .....	13.2.32
13.2.39	Multi-Span Simply Supported Bridge.....	13.2.32
13.2.40	Failed Riprap.....	13.2.33
13.2.41	Severe Streambed Degradation Evident at Low Water .....	13.2.34
13.2.42	Approach Roadway Built in the Floodplain.....	13.2.35
13.2.43	Stable Banks.....	13.2.35
13.2.44	Sediment Accumulation Redirecting Streamflow.....	13.2.36
13.2.45	Fence in Stream at Bridge.....	13.2.37
13.2.46	Waterway Alignment 1990 – 2006 .....	13.2.38
13.2.47	Approach Spans in the Floodplain .....	13.2.39
13.2.48	Debris and Sediment in the Channel.....	13.2.40
13.2.49	Upstream Dam .....	13.2.41
13.2.50	Scour at a Pile Abutment.....	13.2.42
13.2.51	Fast Flowing Stream .....	13.2.43
13.2.52	Scour Rates vs. Velocity for Common Streambed Materials.....	13.2.43
13.2.53	Typical Misaligned Waterway .....	13.2.44
13.2.54	Typical Large Floodplain.....	13.2.44
13.2.55	Lateral Stream Migration .....	13.2.45
13.2.56	Stream Alignment Not Parallel with Abutments .....	13.2.46
13.2.57	Rotational Movement and Failure Due to Undermining .....	13.2.46
13.2.58	Exposed Piling Due to Scour .....	13.2.47
13.2.59	Accelerated Flow Due to Constricted Waterway.....	13.2.47
13.2.60	Scour Assessment – Safe .....	13.2.49
13.2.61	Scour Assessment – Evaluate .....	13.2.50
13.2.61	Scour Assessment – Fix .....	13.2.50
13.2.63	(Exhibit 63) Culvert Failure Due to Overtopping.....	13.2.54
13.2.64	(Exhibit 64) Culvert Almost Completely Blocked by Sediment Accumulation.....	13.2.54
13.2.65	(Exhibit 65) Drift and Debris Inside Timber Box Culvert.....	13.2.55

**Topic 13.3  
Underwater  
Inspection**

13.3.1	Schoharie Creek Bridge Failure.....	13.3.1
13.3.2	Liberty Bridge over Monongahela River .....	13.3.2
13.3.3	Level II Cleaning of a Steel Pile .....	13.3.5

<b>Figure Nos.</b>		<b>Page Nos.</b>
13.3.4	Diver Cleaning Pier Face For Inspection .....	13.3.5
13.3.5	Channel Cross-Section (Current Inspection Versus Original Channel).....	13.3.7
13.3.6	Pier Sounding Grid.....	13.3.7
13.3.7	Permanent Reference Point (Bolt Anchored in Nose of the Pier, Painted Orange) .....	13.3.8
13.3.8	Local Scour; Causing Undermining of a Pier .....	13.3.8
13.3.9	Bascule Bridge on the Saint Croix River .....	13.3.9
13.3.10	Flood Conditions: Pier Settlement .....	13.3.11
13.3.11	Buildup of Debris At Pier .....	13.3.11
13.3.12	Movement of a Substructure Unit .....	13.3.12
13.3.13	Bridge Owner's Underwater Inspection Plan Checklist.....	13.3.17
	Bridge Owner's Underwater Inspection Plan Checklist (cont'd.) .....	13.3.18
	Bridge Owner's Underwater Inspection Plan Checklist (cont'd.) .....	13.3.19
	Bridge Owner's Underwater Inspection Plan Checklist (cont'd.) .....	13.3.20
13.3.14	Timber Pile Bent .....	13.3.21
13.3.15	Steel Pile Bent .....	13.3.22
13.3.16	Concrete Pile Bent.....	13.3.22
13.3.17	Column Pier with Solid Web Wall .....	13.3.23
13.3.18	Cantilever or Hammerhead Pier.....	13.3.23
13.3.19	Solid Shaft Pier .....	13.3.24
13.3.20	Severe Flood-Induced Abutment Scour .....	13.3.25
13.3.21	Damaged Protective System .....	13.3.26
13.3.22	Inspection of Culvert With Limited Freeboard and Ice Cover .....	13.3.27
13.3.23	Concrete Deterioration .....	13.3.28
13.3.24	Deteriorated Timber Piling .....	13.3.29
13.3.25	Deteriorated Steel Piles at Splash Zone .....	13.3.30
13.3.26	Sample Underwater Inspection Form.....	13.3.33
13.3.26	Sample Underwater Inspection Form (Continued) .....	13.3.34
13.3.27	Diving Inside a Cofferdam.....	13.3.35
13.3.28	Excessive Current .....	13.3.36
13.3.29	Debris .....	13.3.36
13.3.30	Cleaning a Timber Pile .....	13.3.37
13.3.31	Commercial Marine Traffic .....	13.3.38
13.3.32	Alpha (top) and Sport Diver (bottom) Flags .....	13.3.39
13.3.33	Inspector Performing a Wading Inspection .....	13.3.40
13.3.34	SCUBA Inspection Diver.....	13.3.40
13.3.35	Surface-Supplied Diving Inspection .....	13.3.41
13.3.36	Vulcanized Rubber Dry Suit .....	13.3.43

<b>Figure Nos.</b>		<b>Page Nos.</b>
13.3.37	Full Face Lightweight Diving Mask with Communication System .....	13.3.43
13.3.38	Surface-Supplied Air Equipment, Including Air Compressor, Volume Tank With Air Filters, and Umbilical Hoses .....	13.3.44
13.3.39	Surface-Supplied Diving Equipment Including Helmet or Hard Hat .....	13.3.44
13.3.40	Pneumofathometer Gauge .....	13.3.45
13.3.41	Surface-Supplied Diver with a Reserve Air Tank.....	13.3.45
13.3.42	Wireless Communication Box System .....	13.3.46
13.3.43	Surface Communication With Inspection Team Leader.....	13.3.47
13.3.44	Access Barge and Exit Ladder .....	13.3.47
13.3.45	Access From Dive Boat .....	13.3.48
13.3.46	Diver with a Pry Bar and Diver with Hand Scraper....	13.3.49
13.3.47	Cleaning with a Water Blaster .....	13.3.50
13.3.48	Coring Equipment .....	13.3.51
13.3.49	Concrete Coring Taking Place .....	13.3.52
13.3.50	Concrete Core.....	13.3.52
13.3.51	Timber Core .....	13.3.53
13.3.52	Various Waterproof Camera Housings .....	13.3.54
13.3.53	Diver Using a Camera in a Waterproof Housing .....	13.3.54
13.3.54	Diver Using a Clearwater Box .....	13.3.55
13.3.55	Underwater Video Inspection .....	13.3.56
13.3.56	Remotely Operated Vehicle (ROV) .....	13.3.56
13.3.57	Acoustic Imaging of a Pier.....	13.3.57
13.3.58	Ground Penetrating Radar Record .....	13.3.59
13.3.59	Tuned Transducer Record .....	13.3.60
13.3.60	Pier Undermining, Exposing Timber Foundation Pile .....	13.3.61

**Topic 14.1  
Culvert  
Characteristics**

14.1.1	Culvert Structure .....	14.1.1
14.1.2	Box Culvert with Shallow Cover .....	14.1.5
14.1.3	AASHTO Wheel Loads and Wheel Spacings.....	14.1.7
14.1.4	AASHTO Wheel Load Surface Contact Area (Foot Print).....	14.1.8
14.1.5	Spread Load Area (Single Dual Wheel).....	14.1.8
14.1.6	Culvert Construction and Installation Requirements ..	14.1.10
14.1.7	Circular Culvert Structure .....	14.1.11
14.1.8	Pipe Arch Culvert.....	14.1.12
14.1.9	Arch Culvert.....	14.1.12

<b>Figure Nos.</b>		<b>Page Nos.</b>
14.1.10	Concrete Box Culvert.....	14.1.13
14.1.11	Multiple Cell Concrete Culvert.....	14.1.14
14.1.12	Frame Culvert .....	14.1.14
14.1.13	Large Structural Plate Pipe Arch Culvert .....	14.1.16
14.1.14	Large Structural Plate Box Culvert.....	14.1.16
14.1.15	Stone Masonry Arch Culvert .....	14.1.17
14.1.16	Timber Box Culvert .....	14.1.17
14.1.17	Schematic of a Single Walled Plastic Culvert.....	14.1.18
14.1.18	Culvert End Projection.....	14.1.19
14.1.19	Culvert Mitered End.....	14.1.19
14.1.20	Culvert Skewed End.....	14.1.20
14.1.21	Culvert Headwall and Wingwalls .....	14.1.20
14.1.22	Apron .....	14.1.21
14.1.23	Riprap Basin.....	14.1.22
14.1.24	Factors Affecting Culvert Discharge (Source: Concrete Pipe Design Manual, American Concrete Pipe Association, April 2007 .....	14.1.24
14.1.25	Bending or Shear Failure .....	14.1.26
14.1.26	Cracking of Culvert End Treatment Due to Foundation Settlement .....	14.1.27
14.1.27	Scour and Undermining at Culvert Inlet.....	14.1.27
14.1.28	Debris and Sediment Buildup .....	14.1.28
14.1.29	Approach Roadway at a Culvert Site.....	14.1.29
14.1.30	Repaired Roadway Over a Culvert .....	14.1.30
14.1.31	Slide Failure .....	14.1.31
14.1.32	Headwall and Wingwall End Treatment on Box Culvert.....	14.1.32
14.1.33	Potential for Tilted Wingwalls.....	14.1.32
14.1.34	Skewed End.....	14.1.33
14.1.35	Culvert Headwall and Wingwall End Treatment.....	14.1.35
14.1.36	Apron .....	14.1.34
14.1.37	Energy Dissipater .....	14.1.34

**Topic 14.2  
Rigid Culverts**

14.2.1	Rigid Culvert.....	14.2.1
14.2.2	Concrete Box Culvert.....	14.2.2
14.2.3	Multi-Cell Concrete Box Culvert.....	14.2.2
14.2.4	Precast Concrete Box Culvert .....	14.2.3
14.2.5	Concrete Pipe Culvert .....	14.2.4
14.2.6	Twin Concrete Pipe Culvert.....	14.2.4
14.2.7	Concrete Arch Culvert .....	14.2.5
14.2.8	Concrete Frame Culvert .....	14.2.6
14.2.9	Stone Masonry Arch Culvert .....	14.2.6

<b>Figure Nos.</b>		<b>Page Nos.</b>
14.2.10	Timber Box Culvert .....	14.2.7
14.2.11	Loads on a Concrete and Timber Box Culvert .....	14.2.8
14.2.12	Steel Reinforcement in a Concrete Box Culvert .....	14.2.10
14.2.13	Precast Box Section with Post-tensioning Steel Ducts .....	14.2.10
14.2.14	Steel Reinforcement in a Concrete Arch Culvert.....	14.2.10
14.2.15	Steel Reinforcement in a Concrete Pipe Culvert.....	14.2.11
14.2.16	Sighting Along Culvert Sidewall to Check Horizontal Alignment.....	14.2.17
14.2.17	Spalls and Delaminations on Top Slab of Concrete Box Culvert .....	14.2.18
14.2.18	Missing Stones in Masonry Culvert.....	14.2.18
14.2.19	Precast Concrete Box Culvert Joint .....	14.2.20
14.2.20	Longitudinal Cracks in Pipe Culvert.....	14.2.20
14.2.21	Transverse Cracks in Pipe Culvert.....	14.2.21
14.2.22	Shear Slabbing (Source: FHWA Culvert Inspection Manual) .....	14.2.22
14.2.23	Cast-in-Place Concrete Headwall and Wingwall.....	14.2.23
14.2.25 a	Standard Sizes for Concrete Pipe (Source: American Concrete Pipe Association) .....	14.2.27
14.2.25 b	Standard Sizes for Concrete Pipe (Source: American Concrete Pipe Association) .....	14.2.28
14.2.25 c	Standard Sizes for Concrete Pipe (Source: American Concrete Pipe Association) .....	14.2.29
14.2.26	Standard Concrete Pipe Shapes (Source: FHWA Culvert Inspection Manual, Supplement to the BIRM, July 1986) .....	14.2.31

**Topic 14.3  
Flexible  
Culverts**

14.3.1	Pipe Arch Flexible Culvert.....	14.3.1
14.3.2	Flexible Box Culvert.....	14.3.2
14.3.3	Flexible Culvert: Load vs. Shape .....	14.3.2
14.3.4	Formula for Ring Compression.....	14.3.3
14.3.5	(Exhibit 11 Culvert Inspection Manual Report No. FHWA-IP-86-2) Standard Corrugated Steel Culvert Shapes (Source: Handbook of Steel Drainage and Highway Construction Products, American Iron and Steel Institute) .....	14.3.4
14.3.6	Schematic of a Single Walled Culvert .....	14.3.6
14.3.7	Schematics of Dual Walled Culverts .....	14.3.6
14.3.8	(Exhibit 66) Checking Curvature by Curve and Middle Ordinate .....	14.3.14



<b>Figure Nos.</b>		<b>Page Nos.</b>
14.3.9	(Exhibit 67) Surface Indications of Infiltration.....	14.3.15
14.3.10	(Exhibit 68) Surface Hole Above Open Joint .....	14.3.16
14.3.11	(Exhibit 69) Close-Up of Loose and Missing Bolts at a Cusped Seam; Loose Fasteners are Usually Detected by Tapping the Nuts with a Hammer .....	14.3.17
14.3.12	(Exhibit 70) Cocked Seam with Cusp Effect .....	14.3.18
14.3.13	(Exhibit 71) Cracking Due to Deflection .....	14.3.19
14.3.14	(Exhibit 72) Circumferential Seam Failure Due to Embankment Slippage .....	14.3.20
14.3.15	(Exhibit 73) Suggested Rating Criteria for Condition of Corrugated Metal .....	14.3.22
14.3.16	(Exhibit 74) Perforation of the Invert Due to Corrosion.....	14.3.22
14.3.17	(Exhibit 75) Invert Deterioration .....	14.3.23
14.3.18	(Exhibit 76) Differential Footing Settlement .....	14.3.24
14.3.19	(Exhibit 77) Footing Rotation Due to Undermining ...	14.3.24
14.3.20	(Exhibit 78) Erosion of Invert Undermining footing of Arch .....	14.3.25
14.3.21	(Exhibit 79) Erosion Damage to Concrete Invert .....	14.3.26
14.3.22	(Exhibit 80) Excessive Side Deflection .....	14.3.28
14.3.23	(Exhibit 81) Shape Inspection Circular and Vertical Elongated Pipe .....	14.3.29
14.3.24	(Exhibit 82) Condition Rating Guidelines .....	14.3.31
14.3.25	(Exhibit 83) Bottom Distortion in Pipe Arches.....	14.3.32
14.3.26	(Exhibit 84) Bottom and Corners of this Pipe Arch have Settled.....	14.3.33
14.3.27	(Exhibit 85) Shape Inspection Structural Plate Pipe Arch.....	14.3.34
14.3.28	(Exhibit 86) Condition Rating Guidelines .....	14.3.35
14.3.29	(Exhibit 87) Arch Deflection During Installation .....	14.3.36
14.3.30	(Exhibit 88) Racked and Peaked Arch .....	14.3.37
14.3.31	(Exhibit 89) Shape Inspection Structural Plate Arch ..	14.3.38
14.3.32	(Exhibit 90) Condition Rating Guidelines .....	14.3.39
14.3.33	(Exhibit 91) Shape Inspection Structural Plate Box Culverts .....	14.3.40
14.3.34	(Exhibit 92) Condition Rating Guidelines .....	14.3.42
14.3.35	(Exhibit 93) Typical Long-Span Shapes .....	14.3.43
14.3.36	(Exhibit 94) Erosion Damage to Concrete Invert .....	14.3.44
14.3.37	(Exhibit 95) Shape Inspection Crown Section of Long Span Structures .....	14.3.45
14.3.38	(Exhibit 96) Shape Inspection Low Profile Long Span Arch.....	14.3.47
14.3.39	(Exhibit 97) Condition Rating Guidelines .....	14.3.48

<b>Figure Nos.</b>		<b>Page Nos.</b>
14.3.40	(Exhibit 98) Shape Inspection High Profile Long-Span Arch.....	14.3.50
14.3.41	(Exhibit 99) Condition Rating Guidelines .....	14.3.51
14.3.42	(Exhibit 100) Shape Inspection Long-Span Horizontal Ellipse.....	14.3.52
14.3.43	(Exhibit 101) Condition Rating Guidelines .....	14.3.53
14.3.44	(Exhibit 102) Potential for Differential Settlement in Horizontal Ellipse.....	14.3.54
14.3.45	(Exhibit 103) Shape Inspection Long-Span Horizontal Ellipse.....	14.3.55
14.3.46	(Exhibit 104) Condition Rating Guidelines .....	14.3.56
14.3.47	Standard Sizes for Corrugated Steel Culverts (Source: American Iron and Steel Institute).....	14.3.57
14.3.47	Standard Sizes for Corrugated Steel Culverts (Source: American Iron and Steel Institute), continued.....	14.3.58
14.3.47	Standard Sizes for Corrugated Steel Culverts (Source: American Iron and Steel Institute), continued.....	14.3.59
14.3.47	Standard Sizes for Corrugated Steel Culverts (Source: American Iron and Steel Institute), continued.....	14.3.59
14.3.47	Standard Sizes for Corrugated Steel Culverts (Source: American Iron and Steel Institute), continued.....	14.3.60
14.3.47	Standard Sizes for Corrugated Steel Culverts (Source: American Iron and Steel Institute), continued.....	14.3.61
14.3.47	Standard Sizes for Corrugated Steel Culverts (Source: American Iron and Steel Institute), continued.....	14.3.62
14.3.47	Standard Sizes for Corrugated Steel Culverts (Source: American Iron and Steel Institute), continued.....	14.3.63
14.3.47	Standard Sizes for Corrugated Steel Culverts (Source: American Iron and Steel Institute), continued.....	14.3.64
14.3.47	Standard Sizes for Corrugated Steel Culverts (Source: American Iron and Steel Institute), continued.....	14.3.65
14.3.47	Standard Sizes for Corrugated Steel Culverts (Source: American Iron and Steel Institute), continued.....	14.3.66

<b>Figure Nos.</b>		<b>Page Nos.</b>
14.3.47	Standard Sizes for Corrugated Steel Culverts (Source: American Iron and Steel Institute), continued.....	14.3.67
14.3.47	Standard Sizes for Corrugated Steel Culverts (Source: American Iron and Steel Institute), continued.....	14.3.68
14.3.47	Standard Sizes for Corrugated Steel Culverts (Source: American Iron and Steel Institute), continued.....	14.3.69
14.3.47	Standard Sizes for Corrugated Steel Culverts (Source: American Iron and Steel Institute), continued.....	14.3.70
14.3.47	Standard Sizes for Aluminum Culvert (Source: American Iron and Steel Institute), continued .....	14.3.71
14.3.48	Standard Sizes for Aluminum Culvert (Source: Aluminum Association), continued .....	14.3.72
14.3.48	Standard Sizes for Aluminum Culvert (Source: Aluminum Association), continued .....	14.3.73
14.3.48	Standard Sizes for Aluminum Culvert (Source: Aluminum Association), continued .....	14.3.74
14.3.48	Standard Sizes for Aluminum Culvert (Source: Aluminum Association), continued .....	14.3.75
14.3.48	Standard Sizes for Aluminum Culvert (Source: Aluminum Association), continued .....	14.3.76
14.3.48	Standard Sizes for Aluminum Culvert (Source: Aluminum Association), continued .....	14.3.77
14.3.48	Standard Sizes for Aluminum Culvert (Source: Aluminum Association), continued .....	14.3.78
14.3.48	Standard Sizes for Aluminum Culvert (Source: Aluminum Association), continued .....	14.3.79
14.3.48	Standard Sizes for Aluminum Culvert (Source: Aluminum Association), continued .....	14.3.80
14.3.48	Standard Sizes for Aluminum Culvert (Source: Aluminum Association), continued .....	14.3.81
14.3.48	Standard Sizes for Aluminum Culvert (Source: Aluminum Association), continued .....	14.3.82
14.3.48	Standard Sizes for Aluminum Culvert (Source: Aluminum Association), continued .....	14.3.83
14.3.48	Standard Sizes for Aluminum Culvert (Source: Aluminum Association), continued .....	14.3.84
14.3.48	Standard Sizes for Aluminum Culvert (Source: Aluminum Association), continued .....	14.3.85
14.348	Standard Sizes for Aluminum Culvert (Source: Aluminum Association), continued .....	14.3.86

	<b>Figure Nos.</b>	<b>Page Nos.</b>
<b>Topic 15.1 Timber</b>		
15.1.1	Sonic Testing Equipment .....	15.1.2
15.1.2	Stress Wave Timer .....	15.1.3
15.1.3	Ultrasonic Testing Equipment.....	15.1.4
15.1.4	Vibration Testing Equipment.....	15.1.5
15.1.5	Timber Boring Tool .....	15.1.6
15.1.6	Inspector Using Decay Detection Device .....	15.1.7
15.1.7	Moisture Content Equipment .....	15.1.8
15.1.8	Pick Test: Sound Wood, Decayed Wood.....	15.1.9
15.1.9	Field Ohmmeter Equipment.....	15.1.9
 <b>Topic 15.2 Concrete</b>		
15.2.1	Portable Hand Held Sonic/Ultrasonic Testing Sensor Array System.....	15.2.2
15.2.2	Acoustic Emission Sensors .....	15.2.2
15.2.3	Half-Cell Potential .....	15.2.3
15.2.4	Delamination Detection Machinery .....	15.2.4
15.2.5	Schematic of Ground Penetrating Radar.....	15.2.5
15.2.6	The HERMES Bridge Inspector (Outside) .....	15.2.6
15.2.7	The HERMES Bridge Inspector (Inside) .....	15.2.7
15.2.8	Impact-Echo Testing Equipment.....	15.2.8
15.2.9	Deck with Area of Delamination (Warmer Colors)....	15.2.9
15.2.10	Infrared Thermography Testing Equipment.....	15.2.9
15.2.11	Schematic of Thermal Imaging.....	15.2.10
15.2.12	Pachometer Testing Equipment .....	15.2.11
15.2.13	Remote Video Inspection Device.....	15.2.13
 <b>Topic 15.3 Steel</b>		
15.3.1	Acoustic Sensors Used to Determine Crack Propagation .....	15.3.2
15.3.2	Inspector Using Acoustic Emissions to Determine Crack Propagation .....	15.3.3
15.3.3	Detection of a Crack Using Dye Penetrant .....	15.3.4
15.3.4	Magnetic Particle Device Used to Detect Subsurface Flaws .....	15.3.5
15.3.5	Schematic of Magnetic Field Disturbance .....	15.3.6
15.3.6	Radiographic Testing .....	15.3.7
15.3.7	Robotic Inspection: Unmanned and Underwater Inspection Vehicles .....	15.3.8
15.3.8	Ultrasonic Testing of a Pin in a Moveable Bridge.....	15.3.9

<b>Figure Nos.</b>		<b>Page Nos.</b>
15.3.9	Ultrasonic Thickness Depth Meter (D-meter).....	15.3.10
15.3.10	Ultrasonic Testing of a Gusset Plate Using a Phased Array .....	15.3.10
15.3.11	Hand Held Eddy Current Testing (ET) Instruments ...	15.3.11
15.3.12	Electrochemical Fatigue Sensor .....	15.3.12
15.3.13	Charpy V-Notch Test .....	15.3.13
15.3.14	Brittle Failure of Cast Iron Specimen .....	15.3.15
15.3.15	Ductile Failure of Cold Rolled Steel.....	15.3.15

**Topic 15.4  
Advanced Asset  
Assessment**

15.4.1	Installation of Sensors .....	15.4.1
15.4.2	Viewing Real time Data .....	15.4.2
15.4.3	Strain Gage Used on the Hoan Bridge Milwaukee, Wisconsin.....	15.4.3
15.4.4	Dynamic Load Testing Vehicle .....	15.4.5
15.4.5	Structural Model.....	15.4.6

**Topic 16.1  
Cable  
Supported  
Bridges**

16.1.1	Golden Gate Bridge.....	16.1.1
16.1.2	Maysville Cable-Stay Bridge .....	16.1.2
16.1.3	Roebing Bridge .....	16.1.3
16.1.4	Sunshine Skyway Cable-Stayed Bridge in Tampa Bay, Florida.....	16.1.3
16.1.5	Parallel Wire .....	16.1.5
16.1.6	Structural Wire Strand .....	16.1.5
16.1.7	Structural Wire Rope .....	16.1.5
16.1.8	Parallel Strand Cable.....	16.1.5
16.1.9	Locked Coil Strand Cross-Section.....	16.1.6
16.1.10	Parallel Wire .....	16.1.6
16.1.11	Parallel Strand .....	16.1.7
16.1.12	Cable Wrapping on the Wheeling Suspension Bridge.....	16.1.7
16.1.13	Shapes of Towers Used for Cable Stay Bridges .....	16.1.8
16.1.14	Tower Types: Concrete “Portal Tower” and “A-Frame Tower” .....	16.1.8
16.1.15	Tower Types: Steel “Portal Tower” and Concrete “Single Column Tower” .....	16.1.9
16.1.16	Three-Span Suspension Bridge Schematic .....	16.1.9
16.1.17	Anchor Block Schematic .....	16.1.10

<b>Figure Nos.</b>		<b>Page Nos.</b>
16.1.18	Cable Saddles for the Manhattan Bridge, NYC (Main span 1,480 ft).....	16.1.11
16.1.19	Grooved Cable Band.....	16.1.11
16.1.20	Open Socket Suspender Cable Connection.....	16.1.12
16.1.21	Cable Vibrations Local System Schematic.....	16.1.12
16.1.22	Cable Vibrations Global System Schematic.....	16.1.12
16.1.23	Cable Damping System - Wheeling Suspension Bridge – (Photo Courtesy of Geoffrey H. Goldberg, 1999).....	16.1.13
16.1.24	Cable Tie Damper System.....	16.1.13
16.1.25	Radial or Converging Cable System Schematic.....	16.1.14
16.1.26	Harp or Parallel Cable System Schematic.....	16.1.15
16.1.27	Fan or Intermediate Cable System Schematic.....	16.1.15
16.1.28	Star Cable System Schematic.....	16.1.16
16.1.29	Single Vertical Plane Cable System.....	16.1.16
16.1.30	Double Vertical Plane Cable System.....	16.1.17
16.1.31	Double Inclined Plane Cable System.....	16.1.18
16.1.32	Cable Saddle.....	16.1.19
16.1.33	Cable Deck Anchorage.....	16.1.20
16.1.34	Anchor Inspection on Veteran’s Bridge.....	16.1.20
16.1.35	Damper on Cable Stayed Bridge.....	16.1.21
16.1.36	Anchor Block Schematic.....	16.1.23
16.1.37	Anchorage Interior of Ben Franklin Bridge, Philadelphia, PA.....	16.1.24
16.1.38	Tape and Rubber Seal Torn Around Cable Allowing Water Penetration into Top of Sheath.....	16.1.25
16.1.39	Form for Recording Deficiencies in the Cable System of a Suspension Bridge.....	16.1.26
16.1.40	Cable-Stayed Bridge.....	16.1.27
16.1.41	Cable-Stayed Bridge Cables.....	16.1.28
16.1.42	Cable Wrapping Placement.....	16.1.29
16.1.43	Deformed Cable Wrapping.....	16.1.29
16.1.44	Corrosion of Steel Sheathing.....	16.1.30
16.1.45	Bulging of Cable Sheathing.....	16.1.30
16.1.46	Cracking of Cable Sheathing.....	16.1.31
16.1.47	Splitting of Cable Sheathing.....	16.1.31
16.1.48	Shock Absorber Damper System.....	16.1.32
16.1.49	Shock Absorber Damper System.....	16.1.32
16.1.50	Cable Tie Type Damper System.....	16.1.33
16.1.51	Tuned Mass Damper System.....	16.1.34
16.1.52	Neoprene Boot at Steel Anchor Pipe Near Anchor.....	16.1.35
16.1.53	Split Neoprene Boot.....	16.1.35
16.1.54	Corrosion of the Anchor System.....	16.1.36

<b>Figure Nos.</b>		<b>Page Nos.</b>
16.1.55	Form for Recording Deteriorations in Cable System of a Cable-Stayed Bridge .....	16.1.37
 <b>Topic 16.2 Movable Bridges</b>		
16.2.1	Movable Bridge.....	16.2.1
16.2.2	Typical “Permit Drawing” Showing Channel Width and Underclearance in Closed and Open Position .....	16.2.2
16.2.3	The First All-Iron Movable Bridge in the Midwest was Completed in 1859 (Photo on File at the Chicago Historical Society) .....	16.2.3
16.2.4	Center-Bearing Swing Bridge.....	16.2.4
16.2.5	Center-Bearing Swing Span in Closed Position .....	16.2.5
16.2.6	Layout of Center-Bearing Type Swing Span with Machinery on the Span.....	16.2.5
16.2.7	Bascule Bridge in the Open Position .....	16.2.6
16.2.8	Rolling Lift Bascule Bridge Schematic .....	16.2.7
16.2.9	Double-Leaf Rolling Lift Bascule.....	16.2.8
16.2.10	Trunnion Bascule Bridge Schematic.....	16.2.9
16.2.11	Double-Leaf Trunnion Bascule Bridge.....	16.2.9
16.2.12	Each Trunnion is Supported on Two Bearings .....	16.2.10
16.2.13	Trunnion Bascule Bridge Machinery (One Quarter Shown) is Located Outside of the Bascule Trusses on the Pier .....	16.2.10
16.2.14	Multi-Trunnion, Strauss Type Bascule Bridge .....	16.2.11
16.2.15	Vertical Lift Bridge Schematic .....	16.2.12
16.2.16	Vertical Lift Bridge Machinery is Located on Top of the Lift Truss Span, and the Operating Drums Rotate to Wind the Up-Haul (Lifting) Ropes as They Simultaneously Unwind the Down-Haul Ropes .....	16.2.13
16.2.17	Vertical Lift Bridge Machinery is Located on the Towers, and the Rim Gears (and Operating Sheaves) are Rotated to Raise and Lower the Bridge .....	16.2.13
16.2.18	Vertical Lift Bridge with Power and Drive System on Towers.....	16.2.14
16.2.19	Open Gearing .....	16.2.14
16.2.20	Speed Reducer.....	16.2.15
16.2.21	Coupling.....	16.2.15
16.2.22	Bearing .....	16.2.16
16.2.23	Shoe Type Break.....	16.2.17
16.2.24	Spring Set Hydraulically Released Disc Break.....	16.2.17
16.2.25	Low Speed High Torque Hydraulic Motor .....	16.2.18
16.2.26	AC Emergency Motor .....	16.2.19

<b>Figure Nos.</b>		<b>Page Nos.</b>
16.2.27	Air Buffer .....	16.2.19
16.2.28	Shock Absorber .....	16.2.20
16.2.29	Typical Air Buffer Schematic .....	16.2.21
16.2.30	Typical Mechanically Operated Span Lock .....	16.2.22
16.2.31	Hydraulic Cylinder that Drives Lock Bars.....	16.2.22
16.2.32	Concrete Counterweight on a Single-Leaf Bascule Bridge.....	16.2.23
16.2.33	Concrete Counterweight on a Vertical Lift Bridge .....	16.2.23
16.2.34	Closed Span Resting on Live Load Shoes .....	16.2.24
16.2.35	Traffic Barrier .....	16.2.24
16.2.36	Center Pivot Bearing .....	16.2.25
16.2.37	Balance Wheel in-place over Circular Rack .....	16.2.26
16.2.38	End Wedge .....	16.2.27
16.2.39	Hydraulic Cylinder Actuator.....	16.2.27
16.2.40	End Wedges Withdrawn and End Latch Lifted .....	16.2.28
16.2.41	Circular Lift Tread and Track Castings .....	16.2.29
16.2.42	Rack Casting and Pinion .....	16.2.30
16.2.43	Rack Casting Ready for Fabrication .....	16.2.31
16.2.44	Drive Pinion .....	16.2.31
16.2.45	Trunnion Bearing .....	16.2.32
16.2.46	Trunnion Design Drawing .....	16.2.32
16.2.47	Rear Lock Assembly .....	16.2.33
16.2.48	Center Lock Jaws .....	16.2.34
16.2.49	Transverse Locks on Underside can be Disengaged...	16.2.35
16.2.50	Wire Rope .....	16.2.36
16.2.51	Wire Rope Sockets and Fittings.....	16.2.36
16.2.52	Drums Wind Up the Up-Haul (Lifting) Ropes as they Simultaneously Unwind the Down-Haul Ropes .	16.2.37
16.2.53	Operator's House with Clear View of Traffic Signals and Lane Gates .....	16.2.40
16.2.54	Traffic Control Gate.....	16.2.40
16.2.55	Navigational Light .....	16.2.41
16.2.56	Marine Two-Way Radio Console .....	16.2.42
16.2.57	Control Panel.....	16.2.45
16.2.58	Stress Reversals in Members .....	16.2.46
16.2.59	Concrete Bearing Areas .....	16.2.47
16.2.60	Pier Protection Systems – Dolphins and Fenders .....	16.2.47
16.2.61	Cracked Speed Reducer Housing.....	16.2.50
16.2.62	Leaking Speed Reducer.....	16.2.50
16.2.63	Hairline Crack Revealed on Shaft from Dye Penetrant Test.....	16.2.51
16.2.64	Leaking Bearing .....	16.2.52
16.2.65	Open Switchboard.....	16.2.57
16.2.66	Hydraulic Power Specialists .....	16.2.59



<b>Figure Nos.</b>		<b>Page Nos.</b>
16.2.67	Example of Notes on Operating Machinery (Gears- General).....	16.2.61
16.2.68	Example of Notes on Operating Machinery (Gears- Teeth) .....	16.2.62
16.2.69	Example of Notes on Operating Machinery (Bearings).....	16.2.63
16.2.70	Example of Notes on Operating Machinery (Mechanical Components) .....	16.2.64
16.2.71	Example of Notes on Electrical Equipment (Motors).	16.2.65
16.2.72	Example of Notes on Electrical Equipment (Limit Switch) .....	16.2.66
16.2.73	Example of Notes on Electrical Equipment (Megger Insulation Test of the Submarine Cables) .....	16.2.67

**Topic 16.3  
Floating  
Bridges**

16.3.1	Floating Bridge, SR 520 Evergreen Point Bridge, Seattle, WA During Stormy Weather.....	16.3.1
16.3.2	Movable Bridge Section of Evergreen Point Bridge, Seattle, WA .....	16.3.2
16.3.3	Elevated Section of Evergreen Point Bridge, Seattle, WA .....	16.3.2
16.3.4	Brookfield, Vermont, Floating Bridge Constructed from Timber .....	16.3.3
16.3.5	Concrete pontoons Under Construction.....	16.3.4
16.3.6	Concrete Pontoons Transported for Hood Canal Project .....	16.3.4
16.3.7	Continuous Pontoon-Type Structure.....	16.3.5
16.3.8	Separate Pontoon Type Structure.....	16.3.6
16.3.9	Bridge Constructed with Separate Pontoons.....	16.3.6
16.3.10	Cross-Section of Anchor Cable.....	16.3.7
16.3.11	Anchor Cable Saddle .....	16.3.7
16.3.12	Precast Concrete Fluke Style Anchor .....	16.3.8
16.3.13	Pile Anchor .....	16.3.9
16.3.14	Open-Cell Gravity Block Anchor .....	16.3.9
16.3.15	Solid Gravity Slab Anchor .....	16.3.11
16.3.16	Inspector Opening Pontoon Access Hatch.....	16.3.13
16.3.17	Sample Pontoon Inspection Plan.....	16.3.14
16.3.18	Frayed Cables Removed from a Floating Bridge.....	16.3.16
16.3.19	Typical View of Heavy Corrosion within Pontoon Port .....	16.3.16

This page intentionally left blank.