1511

PRESTRESSING STRAND

These are Central Lab, Concrete & Metals Lab tests performed in accordance with ASTM A 370.

Dimensions are checked, wire area is calculated and a tensile test is performed.

1512

PLATE BEAM GUARDRAIL

These are Central Lab, Concrete & Metals Lab tests performed in accordance with AASHT0 M 180.

Coating and beam thickness are measured and a tensile test is performed.

1513

SIGN SHEETING

These are Central Lab, Concrete & Metals Lab tests performed in accordance with ASTM A 370.

Tensile strength and thickness are determined. The Central Lab, Chemical Lab performs a chemical analysis.

1514

STEEL CABLE & FITTINGS

These are Central Lab, Concrete & Metals Lab tests performed in accordance with AASHTO T 244.

This category includes guardrail cable and hoisting cable. Dimensions, coating thickness and tensile tests are performed.

