

SHRP2 R21 Composite Pavement Systems – Project Overview

Shreenath Rao, Ph.D., PE
Applied Research Associates, Inc.

August 23, 2010
MnROAD Open House

R21. Composite Pavement Systems

Prime contractor: Applied Research Associates, Inc.
Sub contractors: U. Minnesota, Mn/DOT, U. California, U. Pittsburg
Key Staff: Darter, Rao, Khazanovich, Von Quintus, Harvey, Signore, Worel, Clyne, Watson, Vandenbossche, Tompkins

Duration: 48 months
Contract Start Date: September 2007

This project focuses on two applications of intentionally designed composite pavement systems:

1. Asphalt over concrete (JPC, CRC, RCC)
2. Concrete surface over concrete (wet on wet)

R21. Composite Pavement Systems (Objectives)

- Determine the behavior and identify critical material and performance parameters
- Develop and validate mechanistic-empirical performance models and design procedures consistent with the Mechanistic-Empirical Pavement Design Guide (MEPDG)
- Recommend specifications, construction techniques and quality management procedures and guidelines

European Survey of Composite Pavements

- Europe has built composite pavements for many years
- Why?
 - Excellent surface characteristics
 - High friction
 - Low tire/pavement noise
 - Low splash and spray
 - Rapid renewal (asphalt)
 - Long life (concrete)
 - Economical (**Yes, believe it or not**)
 - Lower layer: thick and low cost (e.g. recycled, low cement, etc.)
 - Upper layer: thin and high quality (e.g. hard aggregate, high cement)
 - Sustainable
 - Recycled lower PCC layer
 - Lower cost aggregates
 - Rapid renewal of top HMA layer



European Survey of Composite Pavements

- Netherlands
- Germany
- Austria

Report published as an online document


http://www.trb.org/Main/Blurbs/2008_Survey_of_European_Composite_Pavements_163693.aspx

Construction of HMA/PCC Test Sections at UCPRC for HVS Testing

Test cells constructed at University of California Pavement Research Center in Davis, CA for accelerated Heavy Vehicle Simulator (HVS) testing

- Subgrade and base constructed Fall 2008.
- JPCP constructed August 2009.
- Extensive instrumentation done at same time.
- HMA construction (and instrumentation) in October 2009.
- Currently being tested using the HVS to obtain pavement responses and measure distresses (rutting, reflection cracking).

Layout of Test Cells at UCPRC



Instrumentation plan for test cells at UCPRC

	1				2				3			
	J	J		J	J	J		J	J	J		J
A	H	5 3 T M	2 D	H	H	5 3 T M	2 D	H	H	5 2 3 T S M	2 D	H
	J	2 5 3 D T M		J	J	5 3 T M		J	J	3 5 2 M T S		J
	J		5 T	J	J		5 T	J	J		5 2 T S	J
B	J	5 2 T S		J	J	5 T		J	J	5 T		J
	H		5 T	H	H		5 T	H	H		5 T	H
	J			J	H	J		J	J			J
C	J	5 T		J	J	5 T		J	J	5 T		J
	H		5 T	H	H		5 T	H	H		5 T	H
	J			J	J			J	J			J
D	J	2 3 5 2 D M T S		J	H	3 5 2 M T S		J	H	3 5 M T		H
	H		2 3 2 5 D M S T	H	J	2 D 3 5 2 M T S	J	H	J	2 D 3 5 2 M T S	J	H
	J			J	J			J	J			J


All nine slabs in each lane are 15 ft. long, center slabs of each group (1,2,3) are widened for display purposes.

T – Thermocouple
 D – Dynamic Strain Gauge

J – Vertical JDMD
 M – Moisture Gauge

H – Horizontal JDMD
 S – Static Strain Gauge

UCPRC Instrumentation: Thermocouples



UCPRC Instrumentation: Strain Gages and Cables



UCPRC Construction: PCC Placement



UCPRC Construction: Texturing, Curing, Saw-Cutting




UCPRC Construction: HMA Placement and Compaction



PG64-28PM (left two lanes) and Gap Graded Rubber mix RHMA-G (right two lanes)




UCPRC HVS Testing



UCPRC HVS Testing – Parametric Analysis


- Effect of various parameters on deflections and strains
- JDMDs (joint deflections) various positions
- Strain gages (tire center and tire edge)
- Various sections
- 50-75 load repetitions at each combination




UCPRC HVS Testing – Parametric Analysis

LOAD kN (lb)	TIRE PRES.(psi)	SPEED km/h (mph)	TEMP. C (F)
40 (9,000)	92.8	8.7 (5.4)	50 (122)
60 (13,500)	104.4	5.9 (3.7)	40 (104)
80 (18,000)		3.1 (1.9)	30 (86)
			20 (68)

JDMD8 (AC)




JDMD1 (AC)



UCPRC HVS Testing – Parametric Analysis


LOAD kN (lb)	TIRE PRES.(psi)	SPEED km/h (mph)	TEMP. C (F)
40 (9,000)	92.8	8.7 (5.4)	50 (122)
60 (13,500)	104.4	5.9 (3.7)	40 (104)
80 (18,000)		3.1 (1.9)	30 (86)
			20 (68)

JDMD2 (PCC)



UCPRC HVS Testing – Parametric Analysis

LOAD kN (lb)	TIRE PRES.(psi)	SPEED km/h (mph)	TEMP. C (F)
40 (9,000)	92.8	8.7 (5.4)	50 (122)
60 (13,500)	104.4	5.9 (3.7)	40 (104)
80 (18,000)		3.1 (1.9)	30 (86)
			20 (68)




Construction of HMA/PCC and PCC/PCC Test Sections at MnROAD

Full-length two-lane test sections constructed at MnROAD in Albertville, MN on Interstate 94.

- Plans, specifications, and estimates were prepared in winter 2008/09.
- Bids let in July 2009 and lowest price (of two bids) was acceptable.
- Construction: April/May 2010.
- Currently open to freeway traffic.

Experimental Plan for Construction at MnROAD




MnROAD Recycling and Salvage Operations




RCA Percent Absorption 2.93%

MnROAD Demonstration Slab



Instrumentation Plan for Construction at MnROAD



MnROAD Instrumentation: Thermocouples, Moisture Gages, Static and Dynamic Strain Gages



MnROAD Instrumentation: Moisture Gages, and Static and Dynamic Strain Gages




MnROAD Paving Wet-on-Wet PCC/PCC



MnROAD Construction: PCC Placement



Exposed Aggregate Concrete Texture



MnROAD HMA/PCC Design

Section		Cell 70 HMA/ PCC (145 m [475 ft])
HMA	Thickness	75 mm (3 in) placed in 2 lifts
	Binder	PG 64-34
	Mix	Superpave wearing course designated SPWEB440F with 12.5 mm (0.5 in) nominal maximum aggregate size (SP 12.5)
PCC	Thickness	150 mm (6 in)
	Mix	Low portland cement (~150 kg/m ³ [250 lb/yd ³]) 60% fly ash
	Aggregate	50% RCA, 50% Mn/DOT Class A Maximum aggregate size 32 mm (1.25 in)
Base		200 mm (8 in) Class 5 unbound
Subgrade		Clay
Joint Spacing		4.6 m (15 ft)
Dowels		32 mm (1.25 in) placed on baskets in driving lane at PCC middepth and undoweled passing lane
Joints		Saw and seal HMA over PCC joints (except last 6 joints)

MnROAD HMA/PCC Construction



MnROAD HMA/PCC Sawing and Sealing



MnROAD Test Sections



Other Field Sites

- **Data collected from many HMA/PCC & PCC/PCC sites in USA, Canada, and Europe**
- **Database set up and sections evaluated**
- **Key sections selected for further field testing and evaluation**
- **Possible construction of HMA/PCC sections at the Illinois Tollway**

What are the next steps for R21?

UCPRC and MnROAD Construction and Field Sections

- **UCPRC - Continue HVS loading and data collection until: Spring/Summer 2011**
- **MnROAD - Monitoring instrumentation and performance data collection (including ride and noise) until: Summer 2011**
- **Field Sections - Field data collection (distress surveys, materials data, IRI, etc.): Fall 2010**

What are the next steps for R21?

Modeling

- **2-layer concrete pavement modeling**
- **PCC lab modeling and materials testing**
- **Rutting model**
- **Reflection cracking model**
- **MEPDG model modifications and calibration
(results from monitoring and instrumentation
@ MnROAD and UCPRC; other field sections)**

Anticipated R21 products?

- a. Refined and validated structural & performance models**
- b. Design procedures and guidelines (manual, recommended additions to AASHTO MEPDG manual)**
- c. Construction specifications (MnROAD, UCPRC, Europe, other)**
- d. Life-cycle cost procedures.**
- e. Composite pavement training materials to aid in implementation**