



Pavement Condition Report

St Cloud Regional Airport (STC)





Prepared for:

Office of Aeronautics Minnesota Department of Transportation 222 East Plato Boulevard Saint Paul, MN 55107 (800) 657-3922

Prepared by:

Applied Research Associates, Inc. 6314 Odana Rd Madison, WI 53719 (608) 274-6409

December 2018



Table of Contents

1.	Intro	oduction	1
	1.1	Project Background	1
	1.2	Pavement Management Approach	1
	1.3	Scope of Work	2
2.	Proj	ect Approach	3
	2.1	Update Pavement Inventory	3
		2.1.1 Pavement Network Definition	
		2.1.2 Naming Scheme	3
	2.2	Pavement Evaluation	7
		2.2.1 Distress Types	8
	2.3	PCI Results	9
	2.4	Projected PCI 1	.6
3.	Reco	ommendations1	
	3.1	Near Term Maintenance1	.7
	3.2	Major Rehabilitation	.8
	3.3	Federal Guidelines 1	.8

Appendix A	-	Sample Unit Maps
Appendix B	-	Pictures
Appendix C	-	PCI Distress Report
Appendix D	-	Distress Identification
Appendix E	-	Maintenance and Major Rehabilitation Policies
Appendix F	-	Localized Maintenance Recommendations
Appendix G	-	Maintenance Repair Guidelines

List of Figures

Figure 1.	Pavement condition life cycle	2
	Network definition map	
-	PCI rating scale and repair levels.	
-	2018 PCI map	
Figure 5.	Condition distribution.	15
Figure 6.	Area-weighted PCI by pavement use	15
Figure 7.	Projected PCI by percent area.	16

List of Tables

Table 1. Branch definition	4
Table 2. PCI distress types	8
Table 3. PCI section summary table	. 11
Table 4. Summary of maintenance work plan.	
Table 5. Recommended 5-year major rehabilitation plan	. 18

Abbreviations and Acronyms

AAC	Asphalt Overlaid with Asphalt
AC	Asphalt Concrete
APC	PCC Overlaid with Asphalt
APMS	Airport Pavement Management System
CAD	Computer-aided Drafting
CIP	Capital Improvement Plan
FAA	Federal Aviation Administration
FOD	Foreign Object Debris
GIS	Geographic Information System
L&T	Longitudinal & Transverse Cracking
LCD	Last Construction Date
Mn/DOT	Minnesota Department of Transportation Office of Aeronautics
PCC	Portland Cement Concrete
PCI	Pavement Condition Index
STC	St Cloud Regional Airport



1. Introduction

Since 1995, Federal grant assurances have required that to continue receiving Federal funding, airports implement a pavement maintenance-management program for any pavement constructed or repaired using Federal money. To help individual airports meet this grant assurance and improve the statewide airport system, the Minnesota Department of Transportation (Mn/DOT) Office of Aeronautics contracted with Applied Research Associates, Inc. (ARA) to provide pavement evaluation and management inspections at local airports. This report contains the results of the 2018 pavement inspections at St Cloud Regional Airport (STC).

Pavement conditions were assessed using the Pavement Condition Index (PCI) procedure, outlined in Federal Aviation Administration (FAA) Advisory Circular (AC) 150/5380 and ASTM D5340 for airfield pavements. The PCI was developed to provide a numerical value indicating overall pavement condition that correlates well with the ratings of experienced engineers. During a PCI survey, visible signs of deterioration within a selected sample unit are recorded and analyzed. The final calculated PCI value is a number from 0 to 100, with 100 representing a pavement in excellent condition. The PCI evaluation makes possible forecasting of future deterioration and allows for accurate projections of maintenance and rehabilitative needs.

The data collected during this project were entered into the MicroPAVER pavement management software program developed by the U.S. Army Corps of Engineers, Construction Engineering Research Laboratory. The capabilities of MicroPAVER were utilized to meet the following project objectives:

- Update and store pavement inventory and condition data.
- Develop models to predict future conditions.
- Develop maintenance and repair recommendations.
- Report the results at the individual and statewide level.

1.1 Project Background

Aviation throughout Minnesota plays a key role in the movement of goods and services with an estimated overall economic impact of \$12.2 billion. Mn/DOT realizes the value in maintaining the paved facilities by implementing and updating an airport pavement management system (APMS). An APMS provides guidance for decisions regarding pavement maintenance and repair policies at an airport and can identify short-, medium-, and long-term rehabilitation needs. Mn/DOT typically has performed PCI inspections at each airport on a 3-year cycle so that the most recent pavement condition data in the APMS reflect the field conditions.

1.2 Pavement Management Approach

The main goal of any pavement management system is to identify pavements that will receive the most benefit from an optimally timed repair. By projecting the rate at which the pavement condition will deteriorate, the optimal time for applying treatments can be determined. Typically, the optimal repair time is the point at which a gradual rate of deterioration begins to increase to a much faster rate, as illustrated in figure 1. It is critical to identify this point in time to avoid higher rehabilitation costs caused by excess deterioration. Figure 1 also shows conceptually how it is cheaper to maintain pavements that are in good to fair condition, rather than wait until the poor condition requires an expensive reconstruction treatment.






Figure 1. Pavement condition life cycle.

Often, the identified needs will cost more than the available budget and will need to be prioritized. The APMS can measure the impact of a limited budget scenario by projecting the future condition of deferred projects. Ultimately, the APMS will provide Mn/DOT and the airport a planning tool that can help identify pavement needs, optimize the selection of projects and treatments over a multi-year period, and understand the consequences of these plans.

1.3 Scope of Work

Since 2008, Mn/DOT has retained ARA to update the APMS for 106 of Minnesota's publicly owned general aviation airports. Mn/DOT identified approximately 1/3 of the airports to be inspected each year and provided the available construction history information and existing MicroPAVER databases for each airport. ARA coordinated the PCI inspections with each airport. After the field work was completed, ARA updated the MicroPAVER database and computer-aided drafting (CAD) map for each airport. MicroPAVER was then used to develop a maintenance work plan based on current distresses. In addition, a 5-year projection identifying work levels of recommended pavement repair needs was prepared at the state level for the various stakeholders to use as a planning tool. Individual reports, such as this one, were prepared for each airport documenting the results of the pavement inspections. A statewide analysis report was prepared based on that inspection year's airports. The airport maps were linked to the MicroPAVER database to allow for geographic information system (GIS) viewing of data. In addition, training was provided on the use of the MicroPAVER software and PCI procedure.



2. Project Approach

2.1 Update Pavement Inventory

The pavement inventory at STC represents the airfield pavements that are intended for aviation-related traffic. The main objective in updating the pavement inventory was to determine the year of the construction (or most recent overlay), the limits of the project, and the surface type for each pavement area based on construction history. When available, Mn/DOT provided this information for the pavement-related projects for areas not already included in previous inspections. ARA then used this information to update the pavement section definitions on the CAD map and MicroPAVER database based on project limits, surface type, layer properties, traffic patterns, and overall condition.

2.1.1 Pavement Network Definition

The construction history information was used to divide the pavement network at STC into management units—branches, sections, and sample units. A branch is a single entity that serves a distinct function. For example, a runway is considered a branch because it serves a single function (allowing aircraft to take off and land). On an airfield, a branch typically represents an entire runway, taxiway, or apron.

Because of the disparity of characteristics that can occur throughout a branch, it is further subdivided into units called sections. A section is a portion of the pavement that has uniform construction history, pavement structure, traffic patterns, and condition throughout its entire length or area. Sections are used as a management unit for the selection of potential maintenance and rehabilitation projects. The guideline used in deciding where section breaks are located is to think of the section as the "repair unit"—a portion of the pavement that will be managed independently and evaluated separately for pavement maintenance and rehabilitation.

Pavement sections are further subdivided into sample units for inspection purposes. The typical sample unit size for asphalt concrete (AC) pavements is 5,000 square feet \pm 2,000 square feet and 20 slabs \pm 8 slabs for portland cement concrete (PCC) pavements. A statistical based sampling rate was used to determine the number of sample units to inspect for each section. The inspected sample units were representative of the overall condition within a section and were used to extrapolate the condition as a whole.

2.1.2 Naming Scheme


For the pavement management system to work efficiently, some unique identifiers were added to the database. The branch names assigned were designed to assist in identification of the pavement area. The first characters are used to identify the pavement use—apron, runway, taxiway, or taxilane (pavement in and around hangar areas). The next character is a number or letter used to further identify the pavement branch (such as RY1331 for Runway 13-31 or CTA1 for Connecting Taxiway A1). The sections for each branch are assigned a number starting with 001, 002, and so on. Table 1 presents the branches defined for STC and their corresponding areas. For those airports with taxiway guidance signs, the branch ID may or may not match up with the signage in the field; however, the branch name will correspond.



Figure 2 presents the network definition for STC and represents the pavements included in the APMS. Some privately built/maintained pavements and "driveways" leading into hangars may not be included here because they are considered outside the scope of work.

Branch Id	Name	Number of Sections	Area (SF)
APA	Apron A	1	150,000
APB	Apron B	2	275,000
CTA1	Connecting Taxiway A1	1	22,000
CTA2	Connecting Taxiway A2	1	26,300
CTA3	Connecting Taxiway A3	1	26,300
СТАЗХ	Connecting Taxiway A3 Extended	2	14,825
CTA4	Connecting Taxiway A4	1	22,000
СТАМ	Connector Taxiway Military Ramp	1	12,150
СТС	Connecting Taxiway C	1	21,750
CTD1	Connecting Taxiway D	3	28,550
CTD2	Connecting Taxiway D2	1	17,400
CTE	Connecting Taxiway E	1	38,400
PPTC	Part Parallel Taxiway C	1	66,700
PPTE	Part Parallel Taxiway E	2	57,580
ΡΤΑ	Parallel Taxiway A	2	470,100
PTD	Parallel Taxiway D	5	158,635
RP1	Run-Up Pad 1	1	22,800
RP2	Run-Up Pad 2	1	23,620
RY1331	Runway 13-31	6	1,098,000
RY523	Runway 5-23	3	241,800
TLA	Taxilane A	1	100,000
		Airport Total	2,893,910

Table 1. Branch definition.





2.2 Pavement Evaluation

The pavement surfaces at STC were visually inspected on May 31, 2018, using the PCI procedure. During a PCI inspection, inspectors walk over the surface of the pavement and identify visible signs of distress within a sample unit. Appendix A presents the scalable map used during the inspection to locate the inspected sample units. Each distress type is identified, then classified as low, medium, or high severity, and recorded on field sheets. In general, the higher the severity, the higher the foreign object damage (FOD) potential. The quantity, or extent, is measured for each distress/severity combination.

After collecting and summarizing the distress type, severity, and quantity for each of the inspected sample units, the distress data were entered into the MicroPAVER database and a PCI was calculated. The PCI procedure uses established deduct curves to determine the number of points to deduct for each distress type/severity combination, depending on the density of the distress. The inspected sample unit PCI's were then averaged to determine an overall PCI for that section.

The PCI value provides a general sense as to the level of rehabilitation that will be needed to repair a given pavement. In general terms, maintenance activities such as crack sealing and patching often provide benefit when the PCI is above 60. However, as the pavement continues to deteriorate, more complex and expensive treatments will be necessary. Pavements with a PCI between 40 and 60 are good candidates for a variety of major repairs ranging from overlays to reconstruction. Once the PCI drops below 40, reconstruction is typically the only viable alternative. Figure 3 presents the PCI inputs, rating scale, and the corresponding general work repair levels.




Figure 3. PCI rating scale and repair levels.



2.2.1 Distress Types

To better understand the cause of pavement deterioration, it is necessary to look at the distress types associated with each PCI. Each distress type has been classified into one of three groups based on cause—load, climate/durability, or other. Load-related distresses such as alligator cracking in asphalt pavements, or corner breaks in PCC pavements, indicate that the structural integrity of the pavement has been compromised. Climate-related distresses indicate that the pavement has aged due to seasonal environmental effects. Distresses that cannot be attributed solely to either load or climate are classified as other. Table 2 presents the asphalt and PCC distress types in the PCI procedure, their classification, and identifies which distresses were observed at STC during the pavement inspection.

Asphalt Distresses	Cause Classification	PCC Distresses	Cause Classification
Alligator cracking	Load	Blowup	Climate
Bleeding	Other	Corner break	Load
Block cracking	Climate	Linear cracking	Load
Corrugation	Other	Durability cracking	Climate
Depression	Other	Joint seal damage	Climate
Jet blast	Other	Small patch	Other
Joint reflection cracking	Climate	Large patch	Other
L&T cracking	Climate	Popouts	Other
Oil spillage	Other	Pumping	Other
Patching	Other	Scaling/crazing	Other
Polished aggregate	Other	Faulting	Other
Raveling	Climate	Shattered slab	Load
Rutting	Load	Shrinkage cracking	Other
Shoving	Other	Joint spalling	Other
Slippage cracking	Other	Corner spalling	Other
Swelling	Other	Alkali Silica Reaction	Climate
Weathering	Climate		

Table 2. PCI distress types.	Table	2.	PCI	distress	types.
------------------------------	-------	----	-----	----------	--------

Indicates distresses found at STC



2.3 PCI Results

The results of the 2018 PCI inspection are presented in figure 4. The overall area-weighted, inspected PCI for STC is 89. When summarizing PCI values, an area-weighted calculation is used instead of a straight mathematical average because the area-weighted calculations eliminate the skewing of the PCI due to the disparity of the section sizes.

Figures 5 and 6 present the overall PCI for STC by area distribution and pavement use, respectively. Table 3 presents the PCI summary for each section at STC, including the drop in PCI per year. Generally, pavement sections will deteriorate between 1 and 3 PCI points per year. Sections deteriorating at higher rates may need maintenance above the normal application rates and should be closely monitored in case major repairs become necessary earlier than expected.

Appendix C contains the detailed inspection report with sample unit data produced from MicroPAVER. Appendix D describes the distress types most commonly identified during the PCI inspections of Minnesota airports.



This page intentionally left blank.



Table 3. PCI section summary table.

	Casting ID	Surface	Section		2015	2018	Drop in	% Dedu	ct due to	2
Branch ID	Section ID	type ¹	area (SF)	LCD ²	PCI	PCI	PCI/Yr ³	Load ⁴	Climate ⁵	Distress types
APA	001	PCC	150,000	2001	100	99	.1	-	-	Joint spalling
APB	001	AC	225,000	1985	59	56	1.3	25	75	Alligator cr, Block cr, L&T cr
APB	002	AC	50,000	1985	47	45	1.7	30	70	Alligator cr, Block cr, L&T cr
CTA1	001	PCC	22,000	2001	96	94	.4	-	34	Joint seal damage, Joint spalling
CTA2	001	PCC	26,300	2001	92	87	.8	-	45	Faulting, Joint seal damage
CTA3	001	PCC	26,300	2001	98	98	.1	-	100	Joint seal damage
CTA3X	001	PCC	10,700	2001	89	89	.7	-	66	Joint seal damage, Shrinkage cr
СТАЗХ	002	AC	4,125	2001	68	61	2.3	21	72	Alligator cr, Depression, L&T cr, Weathering
CTA4	001	PCC	22,000	2001	98	98	.1	-	-	Joint spalling
CTAM	001	AC	12,150	2009	77	75	2.8	-	100	L&T cr, Weathering
CTC	001	PCC	21,750	2001	98	98	.1	-	100	Joint seal damage
CTD1	001	AC	17,100	2013	100	92	1.5	-	100	L&T cr, Weathering
CTD1	002	AAC	7,700	1985	50	48	1.6	20	80	Alligator cr, L&T cr, Raveling, Weathering
CTD1	003	AC	3,750	2001	74	64	2.1	-	100	L&T cr, Raveling, Weathering
CTD2	001	AC	17,400	2013	100	94	1.2	-	100	Weathering
CTE	001	PCC	38,400	2001	95	94	.4	-	77	Corner spalling, Joint seal damage
PPTC	001	PCC	66,700	2001	98	92	.5	-	65	Joint seal damage, Joint spalling
PPTE	001	AC	55,000	1985	59	59	1.2	30	70	Alligator cr, L&T cr
PPTE	002	AAC	2,580	2001	66	66	2.0	-	100	L&T cr, Raveling, Weathering
ΡΤΑ	001	PCC	418,100	2001	98	98	.1	-	51	Corner spalling, Joint seal damage, Joint spalling
PTA	002	PCC	52,000	2017	-	100	-	-	-	-
PTD	001	AC	52,890	1985	46	38	1.9	43	57	Alligator cr, Depression, L&T c, Patching, Weathering
PTD	002	AAC	3,320	2001	74	67	2.0	-	100	L&T cr, Weathering
PTD	003	PCC	53,550	2001	97	96	.2	-	40	Corner spalling, Joint seal damage, Joint spalling



Duou oh ID	Continu ID	Surface	Section	LCD ²	2015	2018	Drop in	% Dedu	ct due to	Distrass types	
Branch ID	Section ID	type ¹	area (SF)	LCD	PCI	PCI	PCI/Yr ³	Load ⁴	Climate ⁵	Distress types	
PTD	004	AC	6,125	2001	74	67	2.0	-	100	L&T cr, Weathering	
PTD	005	AC	42,750	1985	50	48	1.6	24	76	Alligator cr, L&T cr, Patching, Raveling, Weathering	
RP1	001	PCC	22,800	2001	100	98	.1	-	100	Joint seal damage	
RP2	001	PCC	23,620	2001	100	100	-	-	-	-	
RY1331	001	PCC	315,000	2001	95	96 ⁶	.2	-	90	Joint seal damage, Joint spalling, Small patch	
RY1331	002	PCC	420,000	2001	95	95	.3	-	72	Corner spalling, Joint seal damage, Small patch	
RY1331	003	PCC	315,000	2001	95	94	.4	-	70	Corner spalling, Faulting, Joint seal damage, Joint spalling, small patch	
RY1331	004	PCC	22,500	2017	-	100	-	-	-	-	
RY1331	005	PCC	3,000	2017	-	100	-	-	-	-	
RY1331	006	PCC	22,500	2017	-	100	-	-	-	-	
RY523	001	AC	61,250	2013	100	94	1.2	-	100	L&T cr, Weathering	
RY523	003	PCC	74,300	2001	95	95	.3	-	86	Corner spalling, Joint seal damage	
RY523	004	AC	106,250	2013	100	92	1.5	-	100	L&T cr, Weathering	
TLA	001	AAC	100,000	2018	-	100	-	-	-	-	

¹AC = asphalt cement; AAC = asphalt overlaid with asphalt; PCC = portland cement concrete; APC = PCC overlaid with asphalt

²LCD = last construction date (original construction, last overlay, or reconstruction [whichever is most recent])

³Drop in PCI/Yr = (100 - PCI)/age where age = 2018 - LCD

⁴Percent of deduct due to load = Percentage of PCI points subtracted from 100 for load related distresses

⁵Percent of deduct due to climate = Percentage of PCI points subtracted from 100 for climate/durability related distresses ⁶Increase in PCI in section RY1331-001 due to patching that occurred in 2016





Figure 4. 2018 Pavement Condition Index Rating at St. Cloud Regional Airport (STC).





Pavement Condition Index (PCI) Range








Figure 6. Area-weighted PCI by pavement use.



2.4 Projected PCI

After the 2018 distress data was entered into MicroPAVER and the PCI determined, a modeling approach was used to predict future PCI levels based on historical PCI data from Mn/DOT's airports. Pavements were grouped together in performance families based on similar construction, traffic, pavement use, and other factors affecting pavement performance. These performance models predict future PCI, not future distresses.

Figure 7 shows the projected PCI at STC by percent area for the next 5 years assuming no major repairs (overlays, reconstruction, etc.) are performed during that period. It shows how quickly a pavement network can deteriorate when no capital improvements are made.




Figure 7. Projected PCI by percent area.



3. Recommendations

A 5-year maintenance and rehabilitation program was developed for STC based on the 2018 pavement inspections and the anticipated PCI deterioration for this period. The recommendations are divided into two categories—near term maintenance (Local M&R) and major rehabilitation (Major M&R). The near term maintenance is intended to address annual maintenance needs such as crack sealing and localized patching. The major rehabilitations are applied globally and are capable of returning the pavement to a nearly distress free-state. Costs for both categories are based on industry averages and may have to be adjusted to account for local costs.

The last portion of the report covers the FAA Grant Assurance Number 11 and the steps the airport must take to remain in compliance with this program.

3.1 Near Term Maintenance

Near term maintenance is considered activities such as crack sealing, patching, and surface treatments that help to slow down the rate that a pavement is deteriorating. Localized maintenance policies and unit costs were developed with Mn/DOT for both asphalt and PCC surfaces; each policy presents the recommended maintenance treatment for each distress/severity combination and are presented in appendix E.

Table 4 presents the summarized maintenance work quantities and estimated cost to apply this near term maintenance plan at STC. The repair quantities are based on extrapolated distress quantities from the 2018 PCI inspection. National averages of unit costs are used to estimate total costs for each treatment type; adjustments of local unit costs rates may be necessary for each airport to more accurately determine the maintenance budgetary needs.

Work Description	Work Quantity	Work Units	Unit Cost	Work Cost
Crack Sealing - AC	17,959.43	Ft	\$1.26/Ft	\$22,629.11
Joint Seal (Localized)	38,699.33	Ft	\$1.92/Ft	\$74,302.56
Patching - AC Deep	2,260.59	SqFt	\$11.82/SqFt	\$26,720.13
Patching - AC Shallow	1,296.32	SqFt	\$7.95/SqFt	\$10,305.72
Patching - PCC Partial Depth	205.69	SqFt	\$10.68/SqFt	\$2,196.78
Surface Treatment	42,056.49	SqFt	\$0.52/SqFt	\$21,869.24
			Total	\$158,024

Table 4. Summary of maintenance work plan.

Detailed results are reported by section and by treatment type in appendix F. Table F1 summarizes the maintenance that could be done for each pavement section by type of repair, and estimated quantity of repair. Likewise, table F2 summarizes the quantity for each repair type across the entire airport.

When using this plan, it is recommended that the entire section be viewed to determine whether the identified distress types are so advanced in density and severity that maintenance efforts will no longer be cost-effective. Maintenance treatments are most cost-effective when applied to pavements that are generally in good condition. It is also important to understand that the maintenance plan is based on the distress types, severities, and quantities found during the 2018 PCI survey. As field conditions



change, the maintenance plan will become less accurate. Therefore, the maintenance plan will be most useful the sooner it is implemented. Applying maintenance treatments should be an annual event at the airport, and this maintenance plan can serve as a baseline for that work. Guidelines for performing crack sealing and patching techniques are provided in appendix G.

3.2 Major Rehabilitation

In addition to the annual maintenance activities such as crack sealing and patching, some pavements may require more substantial rehabilitation. As a planning aid to the airport, Mn/DOT, and FAA, table 5 provides a summary from MicroPAVER of the predicted 5-year pavement rehabilitation needs at STC. Although the predicted rehabilitation timeline identifies specific sections and the general timing for the repair, more in-depth project-level studies will be needed to determine exactly how to fix each pavement. Routine maintenance should also be programmed annually throughout the airport, but these efforts should be coordinated with the following rehabilitation recommendations.

The pavement sections identified for major rehabilitation in this report are at or are predicted to reach a condition level where either overlays or reconstruction should be considered. Note that this analysis is based on an unconstrained budget, and these recommendations will need to be adjusted to account for economic and operational considerations. Additionally, identifying projects for work does not guarantee that Federal or State funding will be available to complete the work in the year shown. The airport and Mn/DOT should view these recommendations as viable projects when preparing future Capital Improvement Plans (CIP).

Branch ID	Section ID	Year	Predicted PCI Before Rehab	Estimated Cost
APB	002	2019	44	\$330,452
CTD1	002	2019	47	\$48,223
PPTE	001	2019	59	\$244,886
PTD	001	2019	37	\$401,283
PTD	005	2019	47	\$267,732
CTA3X	002	2020	60	\$17,616
CTD1	003	2023	59	\$16,113
			5-year Airport Total	\$1,326,305

Table 5. Recommended 5-year major rehabilitation plan.

3.3 Federal Guidelines

In 1995, Congress mandated that the FAA require, as a condition of grant funding, that airports be prepared to present documentation of a maintenance management program on pavement that has been constructed, reconstructed, or repaired with Federal assistance.

The FAA has defined an acceptable maintenance management program, and this report fulfills many requirements of such a program, including documenting:

- Locations of all runways, taxiways, and aprons.
- Dimensions of the pavement system.
- Types of pavement.



• Year of construction or most recent major rehabilitation.

However, **the airport owner must be an active participant**, specifically by implementing the following actions:

- Annotate pavement areas that have been constructed, reconstructed, or repaired with Federal financial assistance.
- Conduct a "drive-by" inspection at least monthly to detect changes in pavement condition.
- Keep complete records of maintenance activities. Record the date of each "drive-by" inspection and any maintenance performed as a result. Records must be maintained on file for a minimum of 5 years.
- Document detailed inspection information with a history of recorded pavement deterioration by PCI survey (e.g., this report).

An example of a form that can be completed during "drive-by" inspections is provided in appendix G.



This page intentionally left blank.

Appendix A Sample Unit Maps






Figure A.1. Sample unit layout map at St. Cloud Regional Airport (STC).



Denotes additional sample unit surveyed

Figure A.2. Sample unit layout map at St. Cloud Regional Airport (STC).






Figure A.4. Sample unit layout map at St. Cloud Regional Airport (STC).

Appendix B **Pictures**



STC APA 001 (PCI = 99)



STC APB 001 (PCI = 56)



STC APB 001 (PCI = 56)



STC APB 002 (PCI = 45)



STC APB 002 (PCI = 45)



STC CTA1 001 (PCI = 94)



STC CTA3 001 (PCI = 98)



STC CTA3X 001 (PCI = 89)



STC CTA3X 002 (PCI = 61)



STC CTA3X 002 (PCI = 61)



STC CTA4 001 (PCI = 98)



STC CTA4 001 (PCI = 98)



STC CTAM 001 (PCI = 75)



STC CTC 001 (PCI = 98)



STC CTD1 001 (PCI = 92)



STC CTD1 002 (PCI = 48)



STC CTD1 003 (PCI = 64)



STC CTD2 001 (PCI = 94)



STC CTE 001 (PCI = 94)



STC PPTE 001 (PCI = 59)



STC PPTE 001 (PCI = 59)



STC PPTE 002 (PCI = 66)



STC PTA 001 (PCI = 98)



STC PTA 001 (PCI = 98)



STC PTD 001 (PCI = 38)



STC PTD 002 (PCI = 67)



STC PTD 003 (PCI = 96)



STC PTD 004 (PCI = 67)



STC PTD 005 (PCI = 48)





STC RY523 001 (PCI = 94)



STC RY523 003 (PCI = 95)



STC RY523 004 (PCI = 92)



STC RY523 004 (PCI = 92)



STC RY1331 001 (PCI = 96)



STC RY1331 002 (PCI = 95)



STC RY1331 002 (PCI = 95)



STC RY1331 003 (PCI = 94)



STC RY1331 003 (PCI = 94)



STC TLA 001 (PCI = 100)

Appendix C PCI Distress Report

Re-Inspection Report

Generated	_	ng_2018_0	8_28	9/7/	2018												Page 1 of 38
Network:	STC			2111	2010		Nan	ne:	ST.	CLOUD							
Branch:	APA	1]	Name:	APRO	ON A			Use:	APRO	N		Area:		150,000 SqFt	
Section:	001		of	f 1	l	From:	100				To:	305				Last Const.	: 9/30/2001
Surface:	PCC	1	Family:	MN2	2018 PCC		Zon	le: 1	E		Cat	egory:	2			Rank: P	
Area:		150,000	SqFt		Length:		600 H	Ft		Width:		250 F	t				
Slabs:	375		Slab Len	gth:		20 Ft		Slab W	vidth:		20 Ft			Joint Le	ngth:	14,150	Ft
Shoulder:			Street Ty	pe:				Grade	: 0					Lanes:	0		
Section Co	omments	estima	ated LCD														
Last Insp.	Date:	5/31/2018			TotalS	amples:	18			Surveye	ed: 4						
Conditions	s: PC	I: 99															
Inspection	Comme	ents:															
Sample Nu	umber:	101	Тур	e:	R		Area:		2	0.00 Slabs		PCI:	100				
Sample Co	omments	:															
<no distre<="" td=""><td>ess></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></no>	ess>																
Sample Nu	umber:	202	Тур	be:	R		Area:		2	0.00 Slabs		PCI:	96				
Sample Co	omments	:															
74 JOI	INT SPA	LL		Ν	1	1.00	Slabs										
Sample Nu	umber:	205	Тур	be:	R		Area:		2	0.00 Slabs		PCI:	100				
- Sample Co	omments	:															
<no distre<="" td=""><td>ess></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></no>	ess>																
Sample Nu	umber:	303	Тур	be:	R		Area:		2	0.00 Slabs		PCI:	100				
- Sample Co																	

<No Distress>

Network: STC			Name:	ST. CLOUD			
Branch: APB	1	Name: APR	ON B	Use:	APRON	Area: 2	75,000 SqFt
Section: 002	of 2	From:	109		To: 510		Last Const.: 9/30/1985
Surface: AC	Family: MN2	2018 Asphalt Apron	s Zone: E		Category: 2		Rank: S
Area:	50,000 SqFt	Length:	175 Ft	Width:	250 Ft		
Slabs:	Slab Length:	F	t Slab Wie	dth:	Ft	Joint Length:	Ft
Shoulder:	Street Type:		Grade:	0		Lanes: 0	
Section Comments:	2011 slurry seal						
Last Insp. Date: 5/31/	/2018	TotalSamples:	10	Surveyed	1: 3		
Conditions: PCI:	45						
Inspection Comments:							
Sample Number: 209	Туре:	R	Area:	5000.00 SqFt	PCI: 46		
Sample Comments:							
48 L & T CR	Μ	1 301.0	0 Ft				
41 ALLIGATOR C			0 SqFt				
48 L & T CR41 ALLIGATOR CI	R L		0 Ft 0 SqFt				
Sample Number: 310		R 20.0	Area:	3750.00 SqFt	PCI: 38		
Sample Comments:	i,pe.	K	11100.	5750.00 541 (1011 30		
43 BLOCK CR	L	2000.0	0 SqFt				
43 BLOCK CR	M		0 SqFt				
41 ALLIGATOR C			0 SqFt				
41 ALLIGATOR C	R M	1 34.0	0 SqFt				
Sample Number: 409	Туре:	R	Area:	5000.00 SqFt	PCI: 50		
Sample Comments:							
43 BLOCK CR	L	3800.0	0 SqFt				
41 ALLIGATOR CI			0 SqFt				
43 BLOCK CR	Μ		0 SqFt				

Network:	STC			Na	me: ST. CLOUD			
Branch:	APB		Name:	APRON B	Use:	APRON	Area:	275,000 SqFt
Section: 00	1	of 2	2	From: 100		To: 508		Last Const.: 9/30/1985
Surface: A	C Fam	nily: M	IN2018 Asp	halt Aprons Zor	ne: E	Category: 2	2	Rank: S
Area:	225,000 SqF	Ft	Length	900	Ft Width:	250 Ft		
Slabs:	Sla	b Length	:	Ft	Slab Width:	Ft	Joint Len	gth: Ft
Shoulder:	Str	eet Type	:		Grade: 0		Lanes:	0
Section Comr	nents: 2011 sluri	ry seal						
Last Insp. Da	te: 5/31/2018		Total	Samples: 45	Survey	ed: 8		
Conditions:				.				
Inspection Co								
Sample Numl		Туре:	R	Area:	5000.00 SqFt	PCI:	56	
Sample Rum		rype:	К	AICd:	5000.00 SqFt	101;	50	
-								
43 BLOC			L	4300.00 SqFt 40.00 SqFt				
41 ALLIC 43 BLOC	GATOR CR K CR		L M	40.00 SqFt 200.00 SqFt				
Sample Numl		Туре:	R	Area:	5000.00 SqFt	PCI:	67	
Sample Com		• 1			· · · · · · · · · · · · · · · · · · ·			
-			м	226 00 E4				
48 L&T 48 L&T			M L	236.00 Ft 550.00 Ft				
Sample Numl		Туре:	R	Area:	5000.00 SqFt	PCI:	61	
Sample Com		• •						
43 BLOC			L	4400.00 SqFt				
43 BLOC 43 BLOC			L M	4400.00 SqFt 18.00 SqFt				
Sample Numl		Type:	R	Area:	5000.00 SqFt	PCI:	57	
Sample Com		••						
43 BLOC	KCR		М	300.00 SqFt				
43 BLOC 43 BLOC			L	4000.00 SqFt				
41 ALLIC	GATOR CR		L	15.00 SqFt				
Sample Numl	ber: 306	Type:	R	Area:	5000.00 SqFt	PCI:	51	
Sample Com	nents:							
43 BLOC			L	4200.00 SqFt				
	GATOR CR		L	60.00 SqFt				
43 BLOC		<i></i>	M	450.00 SqFt				
Sample Numl		Type:	R	Area:	5000.00 SqFt	PCI:	51	
Sample Com	nents: only 20 s	st of low g	gators noted					
43 BLOC			L	3000.00 SqFt				
41 ALLIC 43 BLOC	GATOR CR K CR		L M	20.00 SqFt 1800.00 SqFt				
Sample Numl		Туре:	R	Area:	5000.00 SqFt	PCI:	62	
Sample Rum		rype.	ĸ	Alta.	5000.00 SqFt	1 (1,	02	
-			-	4000 00 0 =				
43 BLOC 48 L&T			L L	4000.00 SqFt 45.00 Ft				
Sample Numl		Туре:	R	45.00 Pt	5000.00 SqFt	PCI:	41	
Sample Rum		rybe:	ĸ	AICd:	5000.00 SqFt	101;		
-			-	4000 00 0 =				
43 BLOC 48 L&T			L H	4000.00 SqFt 12.00 Ft				
	GATOR CR		н М	70.00 SqFt				
	K CR		М	450.00 SqFt				

Network:	STC			Name:	ST. CL	OUD			
Branch:	CTA1		Name:	CONNECTING T.	AXIWAY A1	Use:	TAXIWAY	Area:	22,000 SqFt
Section:	001	0	f 1 I	From: 100			To: 102		Last Const.: 9/29/2001
Surface:	PCC	Family:	MN2018 PCC	Zone:	Е		Category: 2		Rank: P
Area:		22,000 SqFt	Length:	295 Ft	W	idth:	60 Ft		
Slabs:	68	Slab Len	ngth:	20 Ft Sla	b Width:		15 Ft	Joint Length:	1,710 Ft
Shoulder:		Street T	ype:	Gra	ade: 0			Lanes: 0	
Section Co	omments:								
Last Insp.	Date: 5/3	31/2018	TotalS	amples: 3		Survey	ed: 1		
Condition	s: PCI:	94							
Inspection	o Comments	s:							
Sample Nu	umber: 10	01 Ty	pe: R	Area:	20.00) Slabs	PCI: 94		
Sample Co	omments:								
	INT SPALL		М	1.00 Slabs					
65 JT	SEAL DMO	3	L	20.00 Slabs					

Network:	STC			Name:	ST. CLOU)			
Branch:	CTA2		Name:	Connecting Taxiwa	y A2	Jse: TAX	XIWAY	Area:	26,300 SqFt
Section:	001	0	f 1 I	From: 100]	Fo: 102		Last Const.: 9/30/2001
Surface:	PCC	Family:	MN2018 PCC	Zone:	Е	(Category: 2		Rank: S
Area:		26,300 SqFt	Length:	295 Ft	Widt	:	60 Ft		
Slabs:	77	Slab Ler	ngth:	20 Ft Slab	Width:	15 H	Ft	Joint Length	1,710 Ft
Shoulder:		Street T	ype:	Gra	de: 0			Lanes: 0	
Section Co	omments:								
Last Insp.	Date: 5/3	1/2018	TotalS	amples: 3	Su	rveyed: 1			
Condition	s: PCI:	87							
Inspection	o Comments	:							
Sample Nu	umber: 10	00 Ty	pe: R	Area:	20.00 SI	bs	PCI: 8	37	
Sample Co	omments:								
	SEAL DMC ULTING	ì	M L	20.00 Slabs					

Network:	STC			Nar	ne: ST	. CLOUD			
Branch:	CTA3		Name:	Connecting T	axiway A3	Use:	TAXIWAY	Area:	26,300 SqFt
Section:	001	0	f 1	From: 100			To: 102		Last Const.: 9/30/2001
Surface:	PCC	Family:	MN2018 PCC	Zor	e: E		Category: 2		Rank: P
Area:		26,300 SqFt	Length:	2951	Ft	Width:	60 Ft		
Slabs:	77	Slab Ler	ngth:	20 Ft	Slab Width	:	15 Ft	Joint Length	: 1,710 Ft
Shoulder:		Street T	ype:		Grade:)		Lanes: 0	
Section Co	omments:								
Last Insp.	Date: 5/3	31/2018	TotalS	Samples: 3		Surveye	ed: 1		
Condition	s: PCI:	98							
Inspection	n Comment	s:							
Sample N	umber: 10	01 Ty	pe: R	Area:		20.00 Slabs	PCI: 98		
Sample Co	omments:								
65 JT	SEAL DMO	3	L	20.00 Slabs					

Network	STC :			Na	ime: ST	. CLOUD			
Branch:	CTA3X		Name:	Connecting '	Taxiway A3 ext	tended Use:	TAXIWAY	Area:	14,825 SqFt
Section:	002	0	f 2	From: 105			To: 105		Last Const.: 9/30/2001
Surface:	AC	Family:	MN2018 As Taxiways	phalt Runway- Zo	ne: E		Category: 2		Rank: P
Area:		4,125 SqFt	Lengtl	h: 60	Ft	Width:	60 Ft		
Slabs:		Slab Ler	ngth:	Ft	Slab Width:	:	Ft	Joint Length:	Ft
Shoulder	:	Street T	ype:		Grade: ()		Lanes: 0	
Section (Comments:								
	Date: 5/31		Tota	ISamples: 1		Survey	ed: 1		
Conditio	ns: PCI:	61							
Inspectio	on Comments:								
Sample N	Number: 105	5 Ty]	pe: R	Area:	42	70.00 SqFt	PCI: 61		
Sample (Comments:								
45 D	EPRESSION		L	26.00 SqFt					
48 L	& T CR		М	24.00 Ft					
57 W	EATHERING	ì	L	2900.00 SqFt					
			т	15.00 SqFt					
41 A	LLIGATOR C	R	L	15.00 Sqrt					
	LLIGATOR C & T CR	CR	L L	215.00 Sqrt					

Network:	STC			Name:	ST. CLOUD			
Branch:	CTA3X		Name:	Connecting Taxiw	way A3 extended Use:	TAXIWAY	Area:	14,825 SqFt
Section:	001	to	f 2	From: 103		To: 104		Last Const.: 9/30/2001
Surface:	PCC	Family:	MN2018 PCC	Zone:	Е	Category: 2		Rank: P
Area:		10,700 SqFt	Length:	170 Ft	Width:	60 Ft		
Slabs:	36	Slab Len	gth:	20 Ft Sla	ab Width:	15 Ft	Joint Length:	960 Ft
Shoulder:	:	Street Ty	pe:	Gi	rade: 0		Lanes: 0	
Section Co	omments:							
Last Insp.	. Date: 5/3	1/2018	TotalS	amples: 2	Survey	ed: 1		
Condition								
•	umber: 10		e: R	Area:	20.00 Slabs	PCI: 89		
-	omments:							
65 JT	SEAL DMG	ł	М	20.00 Slabs				
73 SH	IRINKAGE	CR	Ν	5.00 Slabs				

Network:	STC			Name	: ST.	CLOUD			
Branch:	CTA4		Name:	Connecting Tax	iway A4	Use:	TAXIWAY	Area:	22,000 SqFt
Section:	001	0	f 1 F	'rom: 100			To: 102		Last Const.: 9/30/2001
Surface:	PCC	Family:	MN2018 PCC	Zone:	Е		Category: 2		Rank: P
Area:		22,000 SqFt	Length:	295 Ft		Width:	60 Ft		
Slabs:	68	Slab Ler	ngth:	20 Ft	Slab Width:		15 Ft	Joint Length	: 1,710 Ft
Shoulder:	:	Street T	ype:	(Grade: 0			Lanes: 0	
Section C	omments:								
Last Insp.	. Date: 5/3	31/2018	TotalSa	amples: 20		Surveye	ed: 1		
Condition	s: PCI:	98							
Inspection	n Comment	s:							
Sample N	umber: 10	00 Ty	pe: R	Area:	2	0.00 Slabs	PCI: 98		
Sample C	omments:								
74 JO	INT SPALL		L	1.00 Slabs					

Network:	STC			Na	me: ST.	. CLOUD				
Branch:	СТАМ		Name:	CONNECTO MILITARY	OR TAXIWAY RAMP	Use:	TAXIW	AY	Area:	12,150 SqFt
Section:	001	0	f 1	From: TWY			To:	RAMP		Last Const.: 11/1/200
Surface:	AC	Family:	MN2018 Aspl Taxiways	halt Runway- Zo	ne:		Cate	gory:		Rank: P
Area:		12,150 SqFt	Length:	200	Ft	Width:		50 Ft		
Slabs:		Slab Ler	ngth:	Ft	Slab Width:		Ft		Joint Length:	Ft
Shoulder:		Street T	ype:		Grade: 0)			Lanes: 0	
Section Co	omments:									
Last Insp.	Date: 5/3	1/2018	Totals	Samples: 2		Surveye	e d: 1			
Condition	s: PCI:	75								
Inspection	n Comments	:								
Sample N	umber: 10	0 Ty	pe: R	Area:	500	00.00 SqFt		PCI: 75	i	
Sample Co	omments:									
48 L &	& T CR		L	36.00 Ft						
57 WI	EATHERING	3	L	2500.00 SqFt						
57 WI	EATHERING	3	Μ	250.00 SqFt						
48 L &	& T CR		Μ	80.00 Ft						

Network:	STC			Name	e: ST. C	LOUD			
Branch:	CTC		Name:	CONNECTING	G TAXIWAY C	Use:	TAXIWAY	Area:	21,750 SqFt
Section:	001	0	f 1 I	From: 100			To: 102		Last Const.: 9/30/2001
Surface:	PCC	Family:	MN2018 PCC	Zone	: Е		Category: 2		Rank: S
Area:		21,750 SqFt	Length:	310 Ft	,	Width:	60 Ft		
Slabs:	64	Slab Ler	ngth:	20 Ft	Slab Width:		15 Ft	Joint Length	: 1,800 Ft
Shoulder:		Street T	ype:		Grade: 0			Lanes: 0	
Section C	omments:								
Last Insp.	. Date: 5/3	31/2018	TotalS	amples: 4		Surveye	ed: 1		
Condition	s: PCI:	98							
Inspection	n Comment	ts:							
Sample N	umber: 1	00 Ty	pe: R	Area:	20.	00 Slabs	PCI: 98		
Sample C	omments:								
65 JT	SEAL DM	G	L	20.00 Slabs					

Network:	STC				Name:	ST. C	CLOUD				
Branch:	CTD1		Nan	e: CONN	ECTING	TAXIWAY I	Use:	TAXIWAY	Area:	28,550 SqFt	
Section:	001	of	f 3	From:	200			To: 206		Last Const.:	6/23/2013
Surface:	AC	Family:	MN2018 Taxiway	Asphalt Runway s	- Zone:	Е		Category: 2		Rank: S	
Area:		17,100 SqFt	Lei	ngth:	270 Ft		Width:	60 Ft			
Slabs:		Slab Len	gth:	Ft	S	lab Width:		Ft	Joint Length:	F F	t
Shoulder:		Street Ty	ype:		G	Frade: 0			Lanes: 0		
Section Co	omments:										
Last Insp.	Date: 5/3	1/2018	Т	otalSamples:	6		Survey	ed: 2			
Condition	s: PCI:	92									
Inspection	n Comments	:									
Sample N	umber: 20)1 Typ	e: R		rea:	3000	.00 SqFt	PCI: 90			
Sample Co	omments:										
48 L &	& T CR		L	16.00	Ft						
57 WI	EATHERIN	G	L	3000.00	SqFt						
						2000	.00 SqFt	PCI: 95			
	umber: 20)4 Тур	e: R	. 4	rea:	3000	.00 SqFt	ICI. <i>15</i>			
Sample N	umber: 20 omments:	04 Ty p	be: R		Area:	3000	.00 Sqrt	i ei. 93			

Network:	STC					Nam	с.	ST. CLOU	D							
Branch:	CTD1		Nam	e:	CONNE	ECTIN	G TAXIW	AY D	Use:	TAXIWA	ΑY	Area:		28,550 SqF	-t	
Section:	002	o	f 3	Fro	m: 4	00				To:	400			Last Cor	nst.: 9	/30/1985
Surface:	AAC	Family:	MN2018 Taxiway		Runway-	Zone	е: Е			Categ	gory: 2			Rank:	S	
Area:		7,700 SqFt	Ler	gth:		142 Ft	t	Widt	h:		50 Ft					
Slabs:		Slab Len	gth:		Ft		Slab Wid	h:		Ft		Joint L	ength:		Ft	
Shoulder:		Street Ty	ype:				Grade:	0				Lanes:	0			
Section C.	omments:															
Section Co	omments.															
	Date: 5/31	/2018	Т	otalSam	ples: 2			Sı	irveyed	1: 1						
	Date: 5/31	/2018 48	Т	otalSam	ples: 2			Sı	ırveyed	d: 1						
Last Insp. Condition	Date: 5/31	48	Т	otalSam	ples: 2			Sı	irveyed	d: 1						
Last Insp. Condition Inspection	Date: 5/31/	48				rea:		S ı 5335.00 So			PCI: 48					
Last Insp. Condition Inspection Sample Nu	Date: 5/31/ s: PCI: n Comments: umber: 400	48									PCI: 48					
Last Insp. Condition Inspection Sample No Sample Co	Date: 5/31/ s: PCI: n Comments: umber: 400	48				rea:					PCI: 48					
Last Insp. Condition Inspection Sample No Sample Co 48 L &	Date: 5/31/ as: PCI: a Comments: umber: 400 omments:	48 Typ	be: R		AI	rea: Ft					PCI: 48					
Last Insp. Condition Inspection Sample No Sample Co 48 L & 57 WE	Date: 5/31/ as: PCI: a Comments: umber: 400 omments: & T CR	48 • Typ	e: R H		- Ar 7.00	rea: Ft SqFt					PCI: 48					
Last Insp. Condition Inspection Sample No Sample Co 48 L & 57 WE 41 AL	Date: 5/31, is: PCI: in Comments: umber: 400 omments: & T CR EATHERING	48 • Typ	De: R H L		Ar 7.00 1 400.00 \$	rea: Ft SqFt SqFt					PCI: 48					
Last Insp. Condition Inspection Sample No Sample Co 48 L & 57 WF 41 AL 48 L &	Date: 5/31, is: PCI: in Comments: umber: 400 omments: & T CR EATHERING LLIGATOR C	48 • Typ	e: R H L M		7.00 1 400.00 2 15.00 2	r ea: Ft SqFt SqFt Ft					PCI: 48					
Last Insp. Condition Inspection Sample No Sample Co 48 L & 57 WF 41 AL 48 L & 48 L &	Date: 5/31, is: PCI: in Comments: umber: 400 omments: & T CR EATHERING LLIGATOR C & T CR	48 • Typ	De: R H L M M		7.00 1 400.00 2 15.00 2 272.00 1	rea: Ft SqFt SqFt Ft Ft					PCI: 48					

Network:	STC			Name	e: ST. CLOUD			
Branch:	CTD1		Name:	CONNECTING	G TAXIWAY D Use	: TAXIWAY	Area:	28,550 SqFt
Section:	003	0	f 3	From: 401		To: 401		Last Const.: 9/30/2001
Surface:	AC	Family:	MN2018 Asp Taxiways	ohalt Runway- Zone	: Е	Category: 2		Rank: S
Area:		3,750 SqFt	Length	: 75 Ft	Width:	50 Ft		
Slabs:		Slab Ler	igth:	Ft	Slab Width:	Ft	Joint Length:	Ft
Shoulder:	Shoulder: Street Type:			Grade: 0		Lanes: 0		
Section C	omments:							
Last Insp	. Date: 5/31	/2018	Total	Samples: 1	Surve	yed: 1		
Condition	ns: PCI:	64						
Inspection	n Comments:							
Sample N	umber: 401	Тур	e: R	Area:	3750.00 SqFt	PCI: 64		
Sample C	omments:							
57 W	EATHERING		М	800.00 SqFt				
57 W	EATHERING		L	2900.00 SqFt				
				-				
	AVELING		Η	52.00 SqFt				

Network:	STC			Ν	Name:	ST. CLOU	JD			
Branch:	CTD2		Name:	CONNECT	FING TAXIW	AY D2	Use:	TAXIWAY	Area:	17,400 SqFt
Section:	001	0	f 1 I	From: 300				To: 306		Last Const.: 6/23/2013
Surface:	AC	Family:	MN2018 Asph Taxiways	alt Runway- Z	Zone: E			Category: 2		Rank: S
Area:		17,400 SqFt	Length:	27	75 Ft	Wid	th:	60 Ft		
Slabs:		Slab Ler	ngth:	Ft	Slab Wid	lth:		Ft	Joint Length:	Ft
Shoulder:		Street T	ype:		Grade:	0			Lanes: 0	
Section Co	omments:									
Last Insp. Condition	. Date: 5/3 s: PCI:		TotalS	amples: 6		S	urveye	e d: 1		
Inspection	n Comments	s:								
Sample No Sample Co	umber: 30 omments:	02 Ty]	pe: R	Area	:	3000.00 S	qFt	PCI: 94		
57 WI	EATHERIN	G	L	3000.00 SqI	Ft					

Network:	STC			Nam	ne: ST. (CLOUD			
Branch:	CTE		Name:	CONNECTIN	G TAXIWAY	E Use:	TAXIWAY	Area:	38,400 SqFt
Section:	001	o	f 1 F	From: 100			To: 105		Last Const.: 9/30/2001
Surface:	PCC	Family:	MN2018 PCC	Zone	e: E		Category: 2		Rank: P
Area:		38,400 SqFt	Length:	610 F	Ϊt	Width:	60 Ft		
Slabs:	135	Slab Len	gth:	20 Ft	Slab Width:		15 Ft	Joint Length:	3,600 Ft
Shoulder:		Street Ty	ype:		Grade: 0			Lanes: 0	
Section Co	omments:								
Last Insp.	Date: 5/3	1/2018	TotalSa	amples: 7		Surveye	ed: 2		
Condition	s: PCI:	94							
Inspection	Comments	s:							
Sample Nu	umber: 10)1 Typ	e: R	Area:	20	0.00 Slabs	PCI: 93		
Sample Co	omments:								
65 JT	SEAL DMC	Ĵ	М	20.00 Slabs					
Sample Nu	umber: 10	04 Typ	e: R	Area:	20	0.00 Slabs	PCI: 96		
Sample Co	omments:								
75 CO	RNER SPA	LL	L	2.00 Slabs					

Network:	STC			Name:	ST. CLOUD			
Branch:	PPTC		Name:	PART PARALLI C	EL TAXIWAY Use:	TAXIWAY	Area:	66,700 SqFt
Section:	001	of	1 F	rom: 100		To: 110		Last Const.: 9/30/2001
Surface:	PCC	Family: 1	MN2018 PCC	Zone:	Е	Category: 2		Rank: P
Area:		66,700 SqFt	Length:	1,070 Ft	Width:	60 Ft		
Slabs:	216	Slab Lengt	h:	20 Ft Sl	ab Width:	15 Ft	Joint Length:	6,360 Ft
Shoulder:		Street Typ	e:	G	rade: 0		Lanes: 0	
Section Co	omments:							
Sample N	umber: 10		R	Area:	20.00 Slabs	PCI: 93		
-	SEAL DMC	3	М	20.00 Slabs				
Sample N	umber: 10)5 Type :	R	Area:	20.00 Slabs	PCI: 85		
Sample Co	omments:							
65 JT	SEAL DMC	3	L	20.00 Slabs				
74 JO	INT SPALL	,	Н	1.00 Slabs				
Sample No Sample Co	umber: 10 omments:	08 Type:	R	Area:	20.00 Slabs	PCI: 98		
65 JT	SEAL DMC	3	L	20.00 Slabs				

Network:	STC						Nam	ie: S	F. CLC	UD						
Branch:	PPTE			Na	me:	PART P E		LLEL TAXIV		Use:	TAXIW	/AY		Area:	57,580 SqFt	i.
Section:	001		of 2	!	Fr	om: 20	00				To:	210			Last Con	st.: 9/30/1985
Surface:	AC	Family		N20 axiwa		t Runway-	Zon	e: E			Cate	egory:	2		Rank: S	
Area:		55,000 SqFt		L	ength:	1	,100 F	ťt	Wi	dth:		50 Ft				
Slabs:		Slab L	ength	:		Ft		Slab Width	ı:		Ft			Joint Lengt	h:	Ft
Shoulder:		Street	Type:	:				Grade:	0					Lanes:	0	
Section Cor	mments:	2011 slurry s	eal est.													
Last Insp. l	Date: 5/31	/2018			TotalSa	nples: 1	1			Surveye	d: 3					
Conditions	: PCI:	59														
Inspection	Comments:	:														
Sample Nu	mber: 201	1 1	ype:		R	Ar	ea:	50	00.00	SqFt		PCI:	54			
Sample Co																
-	TCR			L		652.00 I	- +									
	LIGATOR C	R		M		15.00										
	TCR			M		218.00										
41 ALL	LIGATOR C	CR		L		35.00	SqFt									
Sample Nu	mber: 204	4 1	ype:		R	Ar	rea:	50	00.00	SqFt		PCI:	62			
Sample Co	mments:															
41 ALI	LIGATOR C	R		L		15.00 \$	SaFt									
48 L &	T CR			М		254.00 1										
48 L &	T CR			L		607.00 I	Ft									
Sample Nu	mber: 207	7 1	ype:		R	Ar	ea:	50	00.00	SqFt		PCI:	60			
Sample Co	mments:															
48 L&	TCR			L		687.00 l	Ft									
48 L &	T CR			М		275.00 I	Ft									
41 ALL	LIGATOR C	מי		L		12.00 \$	- E4									

Network:	STC			Name:	ST. CLOUD			
Branch:	PPTE		Name:	PART PARALLI E	EL TAXIWAY Use:	TAXIWAY	Area:	57,580 SqFt
Section:	002	0	f 2	From: 211		To: 211		Last Const.: 9/30/200
Surface:	AAC	Family:	MN2018 Asp Taxiways	halt Runway- Zone:		Category:		Rank: P
Area:		2,580 SqFt	Length:	47 Ft	Width:	60 Ft		
Slabs:		Slab Ler	ngth:	Ft SI	ab Width:	Ft	Joint Length:	Ft
Shoulder:	:	Street T	ype:	G	rade: 0		Lanes: 0	
Section Co	omments:							
Last Insp.	. Date: 5/31	/2018	Total	Samples: 1	Survey	ed: 1		
Condition	ns: PCI:	66						
Inspectior	n Comments:	crscks have be	en sealed					
Sample N	umber: 211	Ty	pe: R	Area:	2820.00 SqFt	PCI: 6	6	
-	umber: 211	Tyj	pe: R	Area:	2820.00 SqFt	PCI: 6	6	
Sample C		Tyj	pe: R L	Area: 235.00 Ft	2820.00 SqFt	PCI: 6	6	
Sample Co 48 L &	omments:				2820.00 SqFt	PCI: 6	6	
Sample Co 48 L & 57 WI	omments: & T CR		L	235.00 Ft	2820.00 SqFt	PCI: 6	6	

Network	STC				Nar	ne: ST	. CLOUD					
Branch:	PTA			Name:	PARALLEL	TAXIWAY A	Use:	TAXIWAY	A	Area:	470,100 SqFt	
Section:	001		of	2	From: 100			To: 16	9		Last Const.:	9/29/2001
Surface:	PCC		Family: N	MN2018 PC	C Zon	e: E		Category	y: 2		Rank: P	
Area:		418,10	0 SqFt	Lengtl	1: 6,9251	Ft	Width:	60	Ft			
Slabs:	1,385		Slab Lengt		20 Ft	Slab Width:		15 Ft		Joint Lengt	h: 41,490 Ft	
Shoulder	:		Street Type	e:		Grade: 0)			Lanes: ()	
Section (Comments:											
Last Insp	b. Date: 5/	/31/2018		Tota	ISamples: 69		Surveye	e d: 7				
Conditio	ns: PCI:	98										
Inspectio	on Commen	ts:										
Sample N	Number:	105	Type:	R	Area:	2	20.00 Slabs	PC	[: 100			
Sample (Comments:	nd										
<no dist<="" td=""><td>ress></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></no>	ress>											
Sample N	Number:	115	Туре:	R	Area:	2	20.00 Slabs	PC	[: 94			
Sample (Comments:											
75 C	ORNER SP	ALL		L	1.00 Slabs							
74 JC	DINT SPAL	L		М	1.00 Slabs							
-	Number:	125	Type:	R	Area:	2	20.00 Slabs	PC	[: 98			
Sample (Comments:											
74 JC	DINT SPAL	L		L	1.00 Slabs							
Sample N	Number:	135	Type:	R	Area:	2	20.00 Slabs	PC	[: 96			
Sample (Comments:											
	DINT SPAL			L	1.00 Slabs							
	SEAL DM			L	20.00 Slabs							
-	Number:		Туре:	R	Area:	2	20.00 Slabs	PC.	[: 100			
Sample (Comments:	nd										
<no dist<="" td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></no>												
-	Number:	155	Туре:	R	Area:	2	20.00 Slabs	PC	[: 100			
Sample (Comments:											
<no dist<="" td=""><td>ress></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></no>	ress>											
Sample N	Number:	165	Type:	R	Area:	2	20.00 Slabs	PC	[: 98			
Sample (Comments:											
75 C	ORNER SP	ALL		L	1.00 Slabs							

Network:	STC				Nai	ne: ST	Г. CLOUD							
Branch:	PTA			Name:	PARALLEL	TAXIWAY A	Use:	TAXIW	AY	Aı	rea:	4	70,100 SqFt	
Section:	002		of 2	Fr	om: A			To:	В				Last Const.:	1/15/2017
Surface:	PCC	Family:	MN	2018 PCC	Zoi	ne:		Cate	gory:				Rank: P	
Area:		52,000 SqFt		Length:	795	Ft	Width:		60 Ft					
Slabs:	173	Slab L	ength:		20 Ft	Slab Width	:	15 Ft			Joint Le	ngth:	4,710 Ft	
Shoulder:		Street	Туре:			Grade:	0				Lanes:	0		
Section Cor	mments:													
Last Insp. I	Date: 5/3	31/2018		TotalSa	nples: 8		Surveye	ed: 5						
Conditions	: PCI:	100												
Inspection	Comment	s:												
Sample Nu	mber: 1	70 T	ype:	R	Area:		20.00 Slabs		PCI:	100				
Sample Cor	mments:													
<no distres<="" td=""><td>ss></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></no>	ss>													
Sample Nu	mber: 1	71 T	ype:	R	Area:		20.00 Slabs		PCI:	100				
Sample Cor	mments:													
<no distres<="" td=""><td>ss></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></no>	ss>													
Sample Nu	mber: 1	72 T	ype:	R	Area:		20.00 Slabs		PCI:	100				
Sample Cor	mments:													
<no distres<="" td=""><td>ss></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></no>	ss>													
Sample Nu	mber: 1	73 T	ype:	R	Area:		20.00 Slabs		PCI:	100				
Sample Cor	mments:													
<no distres<="" td=""><td>ss></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></no>	ss>													
Sample Nu	mber: 1	76 T	ype:	R	Area:		20.00 Slabs		PCI:	100				
Sample Cor	mments:													

Netw	vork: STC			Na	me: ST.	CLOUD				
Bran	ich: PTD		Name:	PARALLEL	TAXIWAY D	Use:	TAXIWAY	Area:	158,635 SqFt	
Secti	on: 001	of 5		From: 100			To: 111		Last Const.:	9/30/1985
Surfa	ace: AC		l2018 As tiways	sphalt Runway- Zon	ne: E		Category: 2		Rank: S	
Area	: 52,890) SqFt	Lengt	h: 1,200	Ft	Width:	40 Ft			
Slabs	5:	Slab Length:		Ft	Slab Width:		Ft	Joint Length	: F1	t
Shou	lder:	Street Type:			Grade: 0			Lanes: 0		
Secti	on Comments: has of	d ST								
Last	Insp. Date: 5/31/2018		Tota	alSamples: 13		Surveye	d: 3			
Cond	litions: PCI: 38									
Inspe	ection Comments:									
Sam	ple Number: 102	Туре:	R	Area:	400	0.00 SqFt	PCI: 4	2		
Samj	ple Comments:					-				
50	PATCHING]	L	39.00 SqFt						
50	PATCHING		М	41.00 SqFt						
57	WEATHERING]	L	800.00 SqFt						
57	WEATHERING	1	М	2500.00 SqFt						
48	L & T CR]	L	405.00 Ft						
48	L & T CR]	М	175.00 Ft						
41	ALLIGATOR CR]	М	56.00 SqFt						
-	ple Number: 106	Type:	R	Area:	400	00.00 SqFt	PCI: 3	2		
Samj	ple Comments:									
57	WEATHERING]	М	900.00 SqFt						
50	PATCHING]	М	80.00 SqFt						
48	L & T CR]	L	290.00 Ft						
48	L & T CR	1	М	73.00 Ft						
45	DEPRESSION]	Ĺ	2.00 SqFt						
41	ALLIGATOR CR	1	Ĺ	52.00 SqFt						
41	ALLIGATOR CR		М	122.00 SqFt						
57	WEATHERING]	L	600.00 SqFt						
Samj	ple Number: 110	Type:	R	Area:	400	0.00 SqFt	PCI: 4	1		
Samj	ple Comments:									
50	PATCHING]	М	40.00 SqFt						
41	ALLIGATOR CR	1	М	37.00 SqFt						
57	WEATHERING	1	М	1500.00 SqFt						
48	L & T CR	1	М	150.00 Ft						
57	WEATHERING	1	L	800.00 SqFt						
48	L & T CR]	L	281.00 Ft						
41	ALLIGATOR CR]	L	36.00 SqFt						
50	PATCHING]	L	40.00 SqFt						

	ork: S	ГС				INAL	me: ST	. CLOUD						
Bran	ch: P	ГD		Name	e: PAI	RALLEL	TAXIWAY D	Use:	TAXIW	'AY	Area:	1:	58,635 SqFt	
Sectio	on: 004		0	f 5	From:	121			To:	121			Last Con	st.: 9/30/200
Surfa	ace: AC		Family:	MN2018 . Taxiways	Asphalt Runw	vay- Zoi	ne: E		Cate	egory: 2			Rank: S	
Area:	:	6,	125 SqFt	Leng	gth:	110	Ft	Width:		55 Ft				
Slabs	s:		Slab Ler	ngth:	I	Ft	Slab Width:		Ft		Joint Le	ngth:		Ft
Shoul	lder		Street T	uno:			Grade: 0)			Lanes:	0		
Shou	iuci.		Street 1	ype.			Graue.				Lunco.	0		
	on Comme	nts:	Sheet 1	ype.			Graue.				Lunco	Ū		
Sectio	on Comme Insp. Date:	5/31/20	18		otalSamples:	99		Survey	e d: 1					
Section Last 1 Cond	on Comme Insp. Date:	5/31/20 PCI: 67	18		otalSamples:	99			e d: 1					
Sectio Last 1 Cond Inspe	on Commer Insp. Date: litions: I	5/31/20 PCI: 67 ments:	18	Te	otalSamples:	99 Area:				PCI: 67				
Section Last 1 Cond Inspe Samp	on Commer Insp. Date: litions: I ection Com	5/31/20 PCI: 67 ments: :: 121	18	Te	talSamples:			Survey		PCI: 67				
Section Last 1 Cond Inspe Samp Samp	on Commen Insp. Date: litions: I ection Com ple Number	5/31/20 PCI: 67 ments: : 121 nts:	18	Te				Survey		PCI: 67				
Section Last 1 Cond Inspe Samp	on Commer Insp. Date: litions: I ection Com ple Number ple Commer	5/31/20 PCI: 67 ments: : 121 nts: ERING	18	To pe: R	5500.	Area:		Survey		PCI: 67				
Section Last 1 Cond Inspe Samp Samp 57	on Commer Insp. Date: litions: I ection Com ple Number ple Commer WEATH	5/31/20 PCI: 67 ments: :: 121 nts: ERING	18	To pe: R L	5500.	Area: 00 SqFt		Survey		PCI: 67				

Network:	STC			Nar	ne: ST.	CLOUD						
Branch:	PTD		Name:	PARALLEL	FAXIWAY D	Use:	TAXIW	AY	Area:	1	158,635 SqFt	
Section: 0	005	of	5	From: 122			To:	129			Last Const.:	9/30/1985
Surface: A	AC		MN2018 Asj Taxiways	phalt Runway- Zon	e: E		Categ	gory: 2			Rank: S	
Area:	4	2,750 SqFt	Length	: 800 I	⁷ t	Width:		50 Ft				
Slabs:		Slab Leng	th:	Ft	Slab Width:		Ft		Joint L	ength:	Ft	
Shoulder:		Street Typ	be:		Grade: 0				Lanes:	0		
Section Com	ments:	old ST										
Last Insp. D	ate: 5/31/2	2018	Tota	Samples: 9		Surveye	ed: 2					
Conditions:	PCI:	48										
Inspection C	Comments:											
Sample Nun	nher• 122	Туре	: R	Area:	344().00 SqFt		PCI: 52	!			
Sample Con		Type	•		011	100.541.1		101. 02				
57 WEA	THERING		L	600.00 SqFt								
41 ALLI	IGATOR CR	ł	М	5.00 SqFt								
52 RAV	ELING		L	200.00 SqFt								
57 WEA	THERING		Μ	1200.00 SqFt								
48 L&7	ГCR		L	393.00 Ft								
48 L&7	ГCR		М	125.00 Ft								
Sample Nun	aber: 126	Туре	e: R	Area:	4000).00 SqFt		PCI: 44				
Sample Con	nments:											
48 L&T	ГCR		М	140.00 Ft								
57 WEA	THERING		L	2800.00 SqFt								
50 PATC	CHING		L	60.00 SqFt								
50 PATC	CHING		М	60.00 SqFt								
41 ALLI	IGATOR CR	t i i i i i i i i i i i i i i i i i i i	L	6.00 SqFt								
57 WEA	THERING		М	1000.00 SqFt								
48 L&T	ГCR		L	440.00 Ft								
41 ALLI	IGATOR CR	t	М	15.00 SqFt								
	ELING		L	75.00 SqFt								

Network:	STC			Nan	ne: ST.	CLOUD				
Branch:	тD		Name:	PARALLEL	FAXIWAY D	Use:	TAXIWAY	Area:	158,635	SqFt
Section: 003		of	5	From: 100			To: 107		Last	Const.: 9/30/2001
Surface: PCC	2	Family:	MN2018 PC0	C Zon	e: E		Category:	2	Rank	: S
Area:	53,55	0 SqFt	Length	650 F	ł	Width:	60 I	ł		
Slabs: 170		Slab Len	gth:	20 Ft	Slab Width:		15 Ft	Joint	t Length:	3,840 Ft
Shoulder:		Street Ty	pe:		Grade: 0			Lane	es: 0	
Section Comm	ents:									
Last Insp. Date	: 5/31/2018		Total	Samples: 8		Surveye	ed: 2			
Conditions:	PCI: 96									
Inspection Con	iments:									
Sample Numbe	r: 103	Тур	e: R	Area:	2	0.00 Slabs	PCI:	92		
Sample Comm	ents:									
75 CORNE	R SPALL		М	1.00 Slabs						
74 JOINT S	PALL		L	1.00 Slabs						
65 JT SEA	_ DMG		L	20.00 Slabs						
Sample Numbe	r: 107	Тур	e: R	Area:	2	0.00 Slabs	PCI:	100		
Sample Comm	ents: nd									

Network:	STC				Name:	ST. CLOUD			
Branch:	PTD		Name:	PARALL	EL TAXIWAY	D Use:	TAXIWAY	Area:	158,635 SqFt
Section:	002	0	f 5	From: 112	2		To: 112		Last Const.: 9/30/2001
Surface:	AAC	Family:	MN2018 As Taxiways	phalt Runway-	Zone:		Category:		Rank: S
Area:		3,320 SqFt	Length	:	50 Ft	Width:	60 Ft		
Slabs:		Slab Ler	igth:	Ft	Slab Wid	th:	Ft	Joint Leng	t h: Ft
Shoulder:		Street T	ype:		Grade:	0		Lanes:	0
Section Co	omments:								
Last Insp.	Date: 5/31	/2018	Tota	Samples: 1		Surveye	ed: 1		
Condition	s: PCI:	67							
Inspection	n Comments:								
Sample N	umber: 112	2 Typ	e: R	Are	a:	3000.00 SqFt	PCI: 6	57	
Sample Co	omments:	cracks have be	en filled						
48 L&	& T CR		L	298.00 Ft					
48 L &	& T CR		Μ	13.00 Ft					
57 WE	EATHERING	ł	М	3000.00 Se	ıFt				

Network:	STC				Name:	ST.	CLOUD				
Branch:	RP1		Name:	Run-up	Pad 1		Use:	TAXIW	AY	Area:	22,800 SqFt
Section:	001	0	f 1	From:	200			To:	301		Last Const.: 9/30/200
Surface:	PCC	Family:	MN2018 PC	C	Zone:	Е		Cate	gory: 2		Rank: S
Area:		22,800 SqFt	Lengtl	n:	190 Ft		Width:		120 Ft		
Slabs:	76	Slab Ler	ngth:	20 Ft	SI	ab Width:		15 Ft		Joint Length	: 2,350 Ft
Shoulder:		Street T	ype:		G	rade: 0				Lanes: 0	
Section Co	omments:										
Last Insp.	Date: 5/3	31/2018	Tota	ISamples:	1		Surveye	ed: 1			
Condition	s: PCI:	98									
Inspection	n Comment	ts:									
Sample N	umber: 2	00 Ty	pe: R	А	rea:	2	0.00 Slabs		PCI: 98		
Sample Co	omments:										
65 JT	SEAL DM	G	L	20.00	Slabs						

Network:	STC			Nam	e: ST	. CLOUD			
Branch:	RP2		Name:	Run-up Pad 2		Use:	TAXIWAY	Area:	23,620 SqFt
Section:	001	of	1 1	From: 268			To: 369		Last Const.: 9/30/2001
Surface:	PCC	Family:	MN2018 PCC	Zone	: Е		Category: 2		Rank: S
Area:		23,620 SqFt	Length:	190 F	ī.	Width:	120 Ft		
Slabs:	76	Slab Len	gth:	20 Ft	Slab Width:		15 Ft	Joint Length	2,350 Ft
Shoulder:		Street Ty	pe:		Grade: 0)		Lanes: 0	
Section Co	omments:								
Last Insp.	Date: 5/3	31/2018	TotalS	amples: 4		Surveye	ed: 1		
Condition	s: PCI:	100							
Inspection	n Comment	s:							
Sample Nu	umber: 2	69 Тур	e: R	Area:	2	20.00 Slabs	PCI: 10	0	
Sample Co	omments:	nd 4 rs							

Networ	k: STO	; 					Nan	ne:	ST. CLO	υD									
Branch	RY:	1331			Name:	RUNW	'AY 13	-31		Use:	RUNW	ΆY		Area	:	1,0	98,000 Sq	Ft	
Section	: 001		(of 6	F	rom:	100				To:	157					Last Co	onst.:	9/30/2001
Surface	: PCC		Family:	MN	2018 PCC		Zon	e: E			Cat	egory:	2				Rank:	Р	
Area:		315,0	000 SqFt		Length:		7,000 F	łt	Wie	lth:		50 F	ťt						
Slabs:	1,167		Slab Le	ngth:		20 Ft		Slab Wie	dth:		15 Ft				Joint Le	ngth:	33,	783 Ft	
Shoulde	er:		Street T	ype:				Grade:	0						Lanes:	0			
Section	Comment	s:																	
Last In	sp. Date:	5/31/201	8		TotalSa	mples: 5	58		5	Survey	ed: 7								
Conditi	ons: PC	CI: 96																	
Inspect	ion Comm	ents:																	
Sample	Number:	103	Ту	pe:	R	А	rea:		18.00	labs		PCI:	92						
Sample	Comment	s:																	
66	SMALL PA	АТСН]	L	1.00	Slabs												
	IT SEAL D				М	18.00													
Sample	Number:	113	Ту	pe:	R	А	rea:		18.00	labs		PCI:	98						
Sample	Comment	s:																	
65	IT SEAL D	MG]	L	18.00	Slabs												
Sample	Number:	123	Ту	pe:	R	Α	rea:		18.00	labs		PCI:	93						
Sample	Comment	s: co	ould not find	l corne	er spall														
65	IT SEAL D	MG]	М	18.00	Slabs												
Sample	Number:	133	Ту	pe:	R	А	rea:		18.00	labs		PCI:	97						
Sample	Comment	s:																	
65	IT SEAL D	MG		J	L	18.00	Slabs												
66	SMALL PA	ATCH]	L	1.00	Slabs												
Sample	Number:	139	Ту	pe:	R	А	rea:		18.00	labs		PCI:	99						
Sample	Comment	s:																	
66	SMALL PA	ATCH]	Ĺ	1.00	Slabs												
Sample	Number:	143	Ту	pe:	R	А	rea:		18.00	labs		PCI:	97						
Sample	Comment	s:																	
66	SMALL PA	ATCH]	Ĺ	1.00	Slabs												
65	IT SEAL D	MG]	Ĺ	18.00	Slabs												
Sample	Number:	153	Ту	pe:	R	А	rea:		18.00	labs		PCI:	96						
Sample	Comment	s:																	
65	IT SEAL D	MG			L	18.00	Slabs												
74	JOINT SPA	LL]	L	1.00	Slabs												

Network:	STC			Name:	ST. CLOUD			
Branch:	RY133	1	Name:	RUNWAY 13-31	Use:	RUNWAY	Area:	1,098,000 SqFt
Section:	006	0	f 6 F	rom: A		To: B		Last Const.: 1/15/20
Surface:	PCC	Family:	MN2018 PCC	Zone:		Category:		Rank: P
Area:		22,500 SqFt	Length:	500 Ft	Width:	45 Ft		
Slabs:	75	Slab Ler	ngth:	20 Ft Slat	Width:	15 Ft	Joint 1	Length: 2,080 Ft
Shoulder:		Street T	уре:	Gra	de: 0		Lanes	: 0
Section Co	omments:							
Last Insp.	Date: 5/3	1/2018	TotalSa	mples: 4	Surveye	d: 3		
Conditions	s: PCI:	100						
Inspection	Comments	:						
Sample Nu	umber: 49	6 Ty	pe: R	Area:	18.00 Slabs	PCI:	100	
Sample Co	omments:							
<no distre<="" td=""><td>ess></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></no>	ess>							
Sample Nu	umber: 49	98 Ty j	pe: R	Area:	18.00 Slabs	PCI:	100	
Sample Co	omments:							
<no distre<="" td=""><td>ess></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></no>	ess>							
Sample Nu	umber: 49	9 Tyj	pe: R	Area:	18.00 Slabs	PCI:	100	
Sample Co	omments:							

Network:	STC			Name:	ST. CLOUD			
Branch:	RY1331		Name:	RUNWAY 13-31	Use:	RUNWAY	Area:	1,098,000 SqFt
Section:	005	0	f 6 F	rom: A		To: B		Last Const.: 1/15/2017
Surface:	PCC	Family:	MN2018 PCC	Zone:		Category:		Rank: P
Area:		3,000 SqFt	Length:	500 Ft	Width:	60 Ft		
Slabs:	10	Slab Ler	igth:	20 Ft Slal	b Width:	15 Ft	Joint 1	Length: 2,940 Ft
Shoulder:		Street T	ype:	Gra	ide: 0		Lanes	: 0
Section Co	mments:							
Last Insp.	Date: 5/31	1/2018	TotalSa	mples: 4	Surveye	ed: 3		
Conditions	s: PCI:	100						
Inspection	Comments	:						
Sample Nu	mber: 29	6 Ty j	e: R	Area:	24.00 Slabs	PCI:	100	
Sample Co	omments:							
<no distres<="" td=""><td>ss></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></no>	ss>							
Sample Nu	mber: 29	8 Tyj	e: R	Area:	24.00 Slabs	PCI:	100	
Sample Co	omments:							
<no distres<="" td=""><td>ss></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></no>	ss>							
Sample Nu	mber: 29	9 Ty j	e: R	Area:	24.00 Slabs	PCI:	100	
Sample Co								

Network:	STC			Name:	ST. CLOUD			
Branch:	RY133	1	Name:	RUNWAY 13-31	Use:	RUNWAY	Area:	1,098,000 SqFt
Section:	004	0	f 6 F	rom: A		To: B		Last Const.: 1/15/2017
Surface:	PCC	Family:	MN2018 PCC	Zone:		Category:		Rank: P
Area:		22,500 SqFt	Length:	500 Ft	Width:	45 Ft		
Slabs:	75	Slab Ler	ngth:	20 Ft Slab	Width:	15 Ft	Joint 1	Length: 2,080 Ft
Shoulder:		Street T	ype:	Gra	de: 0		Lanes	: 0
Section Co	omments:							
Last Insp.	Date: 5/3	1/2018	TotalSa	mples: 4	Surveye	d: 3		
Conditions	s: PCI:	100						
Inspection	Comments	5:						
Sample Nu	umber: 09	96 Ty j	pe: R	Area:	18.00 Slabs	PCI:	100	
Sample Co	omments:							
<no distre<="" td=""><td>ess></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></no>	ess>							
Sample Nu	umber: 09	98 Tyj	pe: R	Area:	18.00 Slabs	PCI:	100	
Sample Co	omments:							
<no distre<="" td=""><td>ess></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></no>	ess>							
Sample Nu	umber: 09	99 Tyj	pe: R	Area:	18.00 Slabs	PCI:	100	
Sample Co	mments							

Netw	ork: STC			Name:	ST. CLOUD			
Bran	ch: RY1331		Name:	RUNWAY 13-31	Use:	RUNWAY	Area:	1,098,000 SqFt
Secti	on: 002	of 6	1	From: 300		To: 357		Last Const.: 9/30/20
Surf	ace: PCC	Family: Mi	N2018 PCC	Zone:	E	Category: 2		Rank: P
Area	: 420,000	SqFt	Length:	7,000 Ft	Width:	50 Ft		
Slabs	:: 1,167	Slab Length:		20 Ft Sla	b Width:	15 Ft	Joint 1	Length: 33,783 Ft
Shou	lder:	Street Type:		Gra	ade: 0		Lanes	: 0
Secti	on Comments:							
Last	Insp. Date: 5/31/2018		TotalS	amples: 58	Surveye	d: 8		
Cond	litions: PCI: 95							
Insp	ection Comments:							
Sam	ple Number: 304	Type:	R	Area:	24.00 Slabs	PCI: 97		
Sam	ple Comments:							
66	SMALL PATCH		L	5.00 Slabs				
Sam	ple Number: 314	Type:	R	Area:	24.00 Slabs	PCI: 95		
Samj	ple Comments:							
65	JT SEAL DMG		L	24.00 Slabs				
66	SMALL PATCH		L	5.00 Slabs				
Sam	ple Number: 324	Type:	R	Area:	24.00 Slabs	PCI: 93		
Sam	ple Comments:							
75	CORNER SPALL		L	1.00 Slabs				
65 75	JT SEAL DMG CORNER SPALL		L M	24.00 Slabs 1.00 Slabs				
	ole Number: 334	Туре:	R	Area:	24.00 Slabs	PCI: 93		
	ole Comments:	-51						
65	JT SEAL DMG		М	24.00 Slabs				
	ole Number: 340	Туре:	R	Area:	24.00 Slabs	PCI: 95		
-	ple Comments:	-, pe.			2			
			т	24.00 Slabs				
65 75	JT SEAL DMG CORNER SPALL		L M	1.00 Slabs				
Sam	ple Number: 344	Type:	R	Area:	24.00 Slabs	PCI: 98		
Sam	ple Comments:							
65	JT SEAL DMG		L	24.00 Slabs				
	ple Number: 353	Type:	R	Area:	24.00 Slabs	PCI: 94		
Sam	ple Comments: this s	sample was add	ded					
65	JT SEAL DMG		L	24.00 Slabs				
75	CORNER SPALL		Н	1.00 Slabs				
Sam	ple Number: 354	Type:	R	Area:	24.00 Slabs	PCI: 93		
Samj	ple Comments:							
65	JT SEAL DMG		М	24.00 Slabs				

Network: STC		Name:	ST. CLOUD			
Branch: RY1331	Name:	RUNWAY 13-31	Use:	RUNWAY	Area:	1,098,000 SqFt
Section: 003		rom: 500		To: 557		Last Const.: 9/30/2001
Surface: PCC	Family: MN2018 PCC	Zone:	E	Category: 2		Rank: P
	00 SqFt Length:	7,000 Ft	Width:	50 Ft		
Slabs: 1,167	Slab Length:		Width:	15 Ft	Joint Lengt	
Shoulder:	Street Type:	Grad	le: 0		Lanes:	0
Section Comments:						
Last Insp. Date: 5/31/201	8 TotalSa	mples: 58	Surveye	d: 6		
Conditions: PCI: 94						
Inspection Comments:						
Sample Number: 505	Type: R	Area:	18.00 Slabs	PCI: 96		
Sample Comments:						
74 JOINT SPALL	L	1.00 Slabs				
65 JT SEAL DMG	L	18.00 Slabs				
Sample Number: 515	Type: R	Area:	18.00 Slabs	PCI: 98		
Sample Comments:						
66 SMALL PATCH	L	2.00 Slabs				
Sample Number: 525	Type: R	Area:	18.00 Slabs	PCI: 82		
Sample Comments:						
71 FAULTING	L	3.00 Slabs				
65 JT SEAL DMG	М	18.00 Slabs				
Sample Number: 535	Type: R	Area:	18.00 Slabs	PCI: 98		
Sample Comments:						
65 JT SEAL DMG	L	18.00 Slabs				
Sample Number: 545	Type: R	Area:	18.00 Slabs	PCI: 98		
Sample Comments:						
75 CORNER SPALL	L	1.00 Slabs				
Sample Number: 555	Type: R	Area:	18.00 Slabs	PCI: 93		
Sample Comments:						
65 JT SEAL DMG	М	18.00 Slabs				

Network:	STC				Nar	ne: ST.	CLOUD							
Branch:	RY523		I	Name:	RUNWAY 5-	-23	Use:	RUNWA	Y	Ar	rea:	2	41,800 SqFt	
Section:	001	of	3	F	rom: 100			To:	114				Last Const.	6/23/2013
Surface:	AC		MN2 Taxi		lt Runway- Zon	ie: E		Cate	gory: 2				Rank: S	
Area:		61,250 SqFt		Length:	700 H	Ft	Width:		75 Ft					
Slabs:		Slab Leng	gth:		Ft	Slab Width:		Ft			Joint Le	ength:	1	Ft
Shoulder:		Street Typ	pe:			Grade: 0					Lanes:	0		
Section Co	omments:													
Last Insp.	Date: 5/31	/2018		TotalSa	mples: 16		Surveye	ed: 4						
Conditions	s: PCI:	94												
Inspection	Comments:	1												
Sample Nu	imber: 101	l Type	e:	R	Area:	375	0.00 SqFt		PCI: 9	02				
Sample Co	omments:													
57 WE	ATHERING	Ĵ	L		2000.00 SqFt									
48 L &	t T CR		L		7.00 Ft									
Sample Nu	106 imber: 106	б Туре	e:	R	Area:	375	0.00 SqFt		PCI: 9	94				
Sample Co	omments:													
57 WE	ATHERING	Ì	L		3600.00 SqFt									
Sample Nu	imber: 11	і Туре	e:	R	Area:	375	0.00 SqFt		PCI: 9	94				
Sample Co	omments:													
57 WE	EATHERING	}	L	·	3000.00 SqFt									
Sample Nu	imber: 114	4 Туре	:	R	Area:	375	0.00 SqFt		PCI: 9	94				
Sample Co	omments:													
57 WE	EATHERING	ł	L		3600.00 SqFt									

Network:	STC			Nam	e: ST.	CLOUD			
Branch:	RY523		Name:	RUNWAY 5-2	23	Use:	RUNWAY	Area:	241,800 SqFt
Section:	003	0	f 3 1	From: 116			To: 131		Last Const.: 9/30/2001
Surface:	PCC	Family:	MN2018 PCC	Zone	e: E		Category: 2		Rank: S
Area:		74,300 SqFt	Length:	700 F	t	Width:	100 Ft		
Slabs:	140	Slab Ler	igth:	20 Ft	Slab Width:		25 Ft	Joint Lengtl	n: 5,500 Ft
Shoulder:		Street T	ype:		Grade: 0			Lanes: 0)
Section Co	omments:								
Last Insp.	Date: 5/3	1/2018	TotalS	amples: 7		Surveye	ed: 2		
Condition	s: PCI:	95							
Inspection	o Comments	:							
Sample N	umber: 10	0 Ty	pe: R	Area:	2	0.00 Slabs	PCI: 93	3	
Sample Co	omments:								
65 JT	SEAL DMG	ł	М	20.00 Slabs					
Sample N	umber: 10	5 Tyj	pe: R	Area:	2	0.00 Slabs	PCI: 98	3	
Sample Co	omments:								
75 CO	RNER SPA	LL	L	1.00 Slabs					

Network: STC		Name:	ST. CLOUD			
Branch: RY523	Name:	RUNWAY 5-23	Use:	RUNWAY	Area: 2	241,800 SqFt
Section: 004	of 3 I	From: 132		To: 159		Last Const.: 6/23/2013
Surface: AC	Family: MN2018 Asph Taxiways	alt Runway- Zone:	Е	Category: 2		Rank: S
Area: 106,25	0 SqFt Length:	1,400 Ft	Width:	75 Ft		
Slabs:	Slab Length:	Ft S	lab Width:	Ft	Joint Length:	Ft
Shoulder:	Street Type:	G	Grade: 0		Lanes: 0	
Section Comments: main	t since 2009 inspection					
Last Insp. Date: 5/31/2018	TotalS	amples: 29	Surveyee	d: 6		
Conditions: PCI: 92						
Inspection Comments:						
Sample Number: 134	Type: R	Area:	3750.00 SqFt	PCI: 84		
Sample Comments:			_			
48 L & T CR	L	71.00 Ft				
57 WEATHERING	L	3750.00 SqFt				
48 L & T CR	М	4.00 Ft				
Sample Number: 138	Type: R	Area:	3750.00 SqFt	PCI: 94		
Sample Comments:						
57 WEATHERING	L	3600.00 SqFt				
Sample Number: 143	Type: R	Area:	3750.00 SqFt	PCI: 90		
Sample Comments:						
48 L & T CR	L	14.00 Ft				
57 WEATHERING	L	3600.00 SqFt				
Sample Number: 148	Type: R	Area:	3750.00 SqFt	PCI: 94		
Sample Comments:						
57 WEATHERING	L	3600.00 SqFt				
Sample Number: 153	Type: R	Area:	3750.00 SqFt	PCI: 94		
Sample Comments:						
57 WEATHERING	L	3600.00 SqFt				
Sample Number: 158	Type: R	Area:	3750.00 SqFt	PCI: 95		
Sample Comments:			L.			
57 WEATHERING	L	2000.00 SqFt				
	L	2000.00 Bqrt				

Network: STC				Name	e: ST. CLOUD					
Branch: TLA			Name: Tax	xilane A	Use:	TAXILANE	Area:	1	.00,000 SqFt	
Section: 001		of 1	From:	100		To: ??			Last Const.:	1/15/2018
Surface: AAC	F	amily: MN	2018 Asphalt Taxi	lanes Zone	: E	Category:	2		Rank: T	
Area:	100,000	SqFt	Length:	420 Ft	Width:	350 Ft	t			
Slabs:		Slab Length:		Ft a	Slab Width:	Ft	Jo	oint Length:	Ft	
Shoulder:		Street Type:			Grade: 0		L	anes: 0		
Section Comments:	estima	ted LCD								
Last Insp. Date: 5	/31/2018		TotalSamples :	: 103	Surveyed	: 10				
Conditions: PCI										
Inspection Commen	nts:									
Sample Number:	100	Type:	R	Area:	5000.00 SqFt	PCI:	100			
Sample Comments:										
<no distress=""></no>										
Sample Number:	301	Type:	R	Area:	5000.00 SqFt	PCI:	100			
Sample Comments:										
<no distress=""></no>										
Sample Number:	305	Type:	R	Area:	5000.00 SqFt	PCI:	100			
Sample Comments:										
<no distress=""></no>										
Sample Number:	402	Type:	R	Area:	5000.00 SqFt	PCI:	100			
Sample Comments:										
<no distress=""></no>										
Sample Number:	508	Type:	R	Area:	5000.00 SqFt	PCI:	100			
Sample Comments:										
<no distress=""></no>										
Sample Number:	809	Type:	R	Area:	5000.00 SqFt	PCI:	100			
Sample Comments:										
<no distress=""></no>										
Sample Number:	905	Type:	R	Area:	5000.00 SqFt	PCI:	100			
Sample Comments:										
<no distress=""></no>										
Sample Number:		Type:	R	Area:	5000.00 SqFt	PCI:	100			
Sample Comments:										
<no distress=""></no>										
1	973	Type:	R	Area:	5000.00 SqFt	PCI:	100			
Sample Comments:										
<no distress=""></no>										
Sample Number:	990	Type:	R	Area:	5000.00 SqFt	PCI:	100			
Sample Comments:										

Appendix D Distress Identification

This appendix lists and describes distress types most commonly identified during the PCI inspections of Minnesota airports. Note that the pictures provided in this appendix are for illustration purposes and do not necessarily reflect the conditions or pavements at this airport. Descriptions and measurement inspection criteria are provided herein.

Flexible (Asphalt) Pavement Distress



Example of Longitudinal and Transverse Cracking (L&T cracking)

Longitudinal and transverse cracks are caused by pavement aging, by construction, and by subsurface movement. Aging occurs as pavement loses some of its components to the atmosphere and becomes more brittle. Consistent application of pavement sealcoats can help to prevent the occurrence of age related cracks. Cracks will also develop along poorly constructed paving lane joints. Ensuring that joints are made when both sides are still hot, and near the same temperature, is one of the best ways to mitigate this potential problem. Seasonal movement caused by changes in moisture content or temperature differences can also cause pavement cracks. Asphalt pavement placed over a PCC pavement or cement stabilized base course may evidence reflective cracking from the underlying material. Longitudinal and transverse cracks are not caused by wheel loads, although traffic may worsen their condition.

Low severity longitudinal and transverse cracks are less than ¼ inch wide, or if sealed with suitable filler material in satisfactory condition can be any width, less than 3 inches, if they are not spalled. Maintenance usually is not indicated for low-severity cracking. Moderately spalled cracks and cracks wider than ¼ inch which are not satisfactorily sealed are at medium severity. Medium-severity cracks should be sealed with a high-quality crack filling material. Severely spalled cracks and cracks wider than 3 inches are at high severity. High-severity L&T cracks normally require patching.

Example of Block Cracking



Block cracking is longitudinal and transverse cracking that has established a pattern of blocks ranging in size from 1ft x 1ft to 10ft x 10ft. This distress typically happens in older asphalt pavements and is an indication that the bituminous binder has lost most of its flexibility. The severity determination is basically determined by the crack width criteria defined for longitudinal and transverse cracking. Crack sealing typically is used to repair block cracking; however, the amount of required sealant can be extensive due to the high density of cracks.

Example of Alligator Cracking



Alligator (or fatigue) cracks are a series of interconnected load-related cracks caused by fatigue of the asphalt surface. Alligator cracking is a significant structural distress and develops only in places subject to traffic loads. These cracks typically initiate at the bottom of the asphalt layer (where tensile strains

are highest) and propagate upward - so once a fatigue crack is visible, significant damage has already occurred.

At low severity, alligator cracks are evidenced by a series of parallel hairline cracks (usually in a wheel path). Further traffic and deterioration leads to the interconnection of these cracks. Medium severity alligator cracking is a well-defined pattern of interconnected cracks, some spalling may be present. High severity alligator cracks have lost aggregate interlock between adjacent pieces, the cracks may be severely spalled with FOD potential, and most likely the pieces will move freely under traffic. Alligator cracking is a structural failure and cannot be repaired with sealant, the proper repair is full-depth patching.

Example of Raveling/Weathering




Raveling and weathering are the wearing away of the pavement surface. Raveling is the condition where the mid- to large size aggregates are becoming dislodged; weathering is when the fine aggregate wears away exposing the edges of the larger aggregate. These distresses are usually evident over large areas and may occur together (pictured above) or separately. Raveling and weathering may indicate that the asphalt binder has hardened significantly.

<u>Raveling</u> – At low severity, the number of missing coarse aggregates (> 3/8 inch) is between 5-20 missing/yd², medium severity (pictured below where the missing coarse aggregates have been dotted with yellow paint) is 21-40 missing/yd², and high severity is > 40 missing/yd².



MN APMS - ARA

<u>Weathering</u> – At low severity, the coarse aggregate is slightly exposed due to the wearing away of the fine aggregate. At medium severity, the coarse aggregate is exposed up to ½ the width of the longest side. At high severity, the coarse is exposed greater than ¼ the width of the longest side.



Example of Patching



Patched areas are defined when a portion of the original pavement is replaced with a material intended as a semi-permanent repair. A patch is documented as a defect because it is considered a break in the integrity of the pavement structure. Patches are constructed for a variety of reasons including utility repairs, correcting grade issues, and addressing a defect in the original pavement. The severity level of patches is determined by the amount of distress (i.e. cracking, depression, weathering/raveling, etc.) occurring within the limits of the patched area.

Example of Rutting



Ruts are localized, load related, areas of pavement having elevations lower than the surrounding sections. Rutting is due to base and subgrade consolidation, caused by excessive wheel loads or poor compaction. Ruts indicate structural failure, and can cause hydroplaning. At low severity, ruts have an

average depth of ¼ to ½ inches. At medium severity, ruts have an average depth of ½ to 1 inch. High severity, ruts have an average depth greater than 1 inch. Full-depth patching is the appropriate repair for ruts.

Rigid (Concrete) Pavement Distress

Example of Longitudinal, Transverse, and Diagonal Cracking



LTD cracking is most often a result of externally applied loads and/or constrained temperature deformations. External loads cause LTD cracking through flexure. Temperature changes on restrained slabs will result in stresses due to friction or curling. When any of these stresses exceed the strength of the slab, cracking will occur. LTD cracking is recorded at low, medium, or high severity, depending on the width of crack opening and degree of deterioration. At low severity, the crack is less than 1/8th inch wide with little spalling and no corrective action is indicated. At medium severity, LTD cracks can be up to 1 inch wide with moderate spalling, and should be repaired and sealed using procedures similar to joint sealing. At high severity, cracks exceed 1 inch in width and may be severely spalled. High-severity LTD cracking is evidence of serious load failure of the slab, and correction may require patching or slab replacement. If the distress occurs in several adjacent slabs at medium or high severity, major rehabilitation of that pavement area is indicated.

When a slab is divided by LTD cracks into four or more pieces, the slab is said to be "divided" or "shattered." Shattered slab is a separate distress category and is indicative of significant structural failure as the slab loses its ability to distribute loads to subgrade and further slab deterioration can be expected. Shattered slabs are rated in three severities, with slab replacement recommended for medium and high severities.

Example of Shrinkage Cracking



Shrinkage cracks are small, nonworking (no spalling along edge) cracks that are visible at the surface but do not penetrate through the full depth of concrete. Shrinkage cracks most commonly occur shortly after construction due to concrete shrinkage during the curing process. Shrinkage cracks are usually so small that they are not visible until staining or material loss at crack edges begins to take place. Shrinkage cracks do not represent a structural weakness, and no corrective action is prescribed.



Example of Joint and Corner Spalling

Spalls at slab joints and corners are caused by excessive internal stress in the pavement. Spalls occur when these stresses exceed the shear strength of the concrete. Spalling usually results from thermal expansion during warm or hot weather. As slabs expand, they push against one another at joints. If the joints are filled with incompressibles, such as sand, or if adjacent slabs offset slightly, stresses can become severe, causing spalls. Spalling can be reduced significantly by conscientious maintenance of joint sealant.

Spall repair requires patching. The extent and severity of spalling on a pavement surface suggests appropriate action. For example, at low severity, spalled concrete remains securely in place in the slab. A low-severity spall should be monitored closely for further deterioration and should be patched when

spalled particles become loose in place, or at the next scheduled patching activity in the section. Medium- and high-severity spalls should be repaired immediately to prevent the incidence of FOD. If the pavement can be restored to serviceable condition, spalls should be carefully patched for long-term service. If the pavement is beyond repair, temporary patching should be considered to control FOD.

Example of Durability Cracking



Durability cracking (D-cracking) is caused by environmental factors, the most common of which is freezing/thawing. It usually appears as a pattern of hairline cracks running parallel to a joint or crack, or in a corner, where water tends to collect. This type of cracking eventually leads to disintegration of the pavement, creating FOD potential. At low severity, D-cracking is evident, but no disintegration has occurred. As the distress advances to medium severity, the distress pattern is evident over a significant area of the slab, and some disintegration and FOD potential exists. High severity durability cracking is evidenced by extensive cracking with loose and missing pieces and significant FOD potential.

Example of Joint Seal Damage



Joint seal damage is recorded at three severities: low, medium, and high. When joint sealant is in perfect condition (no damage), it is not a distress. At low severity, at least 10 percent of the sealant is debonded but still in contact with the joint edges (i.e., joint sealant is in serviceable condition but should

be monitored for evidence of more serious failure). Medium-severity joint seal damage is recorded when at least 10 percent of the sealant has visible gaps smaller than 1/8th inch and is an indicator that replacement should be programmed as soon as is practicable. In the meantime, aggressive inspection and sustaining maintenance is recommended to minimize subsurface damage from moisture penetration. At high severity, visible gaps exceed 1/8th inch and the amount and degree of joint seal damage is such that repair is no longer feasible. The only appropriate corrective action is sealant replacement.

On serviceable pavement, deteriorated joint sealant should be repaired or replaced to preserve pavement and subgrade integrity and prolong service life. The issue is not so clear-cut with unserviceable pavement. Pavement that can be restored to serviceable condition by maintenance activities such as patching and joint seal repair, or by slab replacement, should be so maintained as long as the process is cost-effective. However, when age and condition preclude economical return to serviceable condition by such means, joint seal repair would no longer be cost-effective and should be suspended except for an interim maintenance program to control FOD potential.

Joint sealant can stop the evidence of pumping (water forced to surface through joints and cracks) but will not correct the cause (voids under pavement).

This page intentionally left blank.

Appendix E Maintenance and Major Rehabilitation Policies

Distress type	Distress severity	Maintenance treatment
	Low	Crack Sealing - AC
Alligator cracking	Medium	Patching - AC Deep
	High	Patching - AC Deep
Bleeding	N/A	Monitor
	Low	Monitor
Block cracking	Medium	Crack Sealing - AC
	High	Crack Sealing - AC
	Low	Monitor
Corrugation	Medium	Patching - AC Deep
	High	Patching - AC Deep
	Low	Monitor
Depression	Medium	Patching - AC Shallow
	High	Patching - AC Deep
Jet blast	N/A	Patching - AC Shallow
	Low	Monitor
Joint reflection cracking	Medium	Crack Sealing - AC
	High	Crack Sealing - AC
	Low	Monitor
Longitudinal & transverse cracking	Medium	Crack Sealing - AC
(L&T cracking)	High	Crack Sealing - AC
Oil spillage	N/A	Patching - AC Shallow
	Low	Monitor
Patching	Medium	Patching - AC Shallow
	High	Patching - AC Deep
Polished aggregate	N/A	Monitor
	Low	Monitor
Raveling	Medium	Surface Treatment
	High	Patching - AC Shallow
	Low	Monitor
Rutting	Medium	Patching - AC Deep
	High	Patching - AC Deep
	Low	Monitor
Shoving	Medium	Patching - AC Shallow
	High	Patching - AC Deep
Slippage cracking	N/A	Patching - AC Shallow
	Low	Monitor
Swelling	Medium	Patching - AC Deep
	High	Patching - AC Deep
	Low	Monitor
Weathering	Medium	Surface Treatment
	High	Patching - AC Shallow

Table E1. Localized maintenance policy for asphalt surfaces.

Distress type	Distress severity	Maintenance treatment
	Low	Patching - PCC Partial Depth
Blow up	Medium	Slab Replacement - PCC
	High	Slab Replacement - PCC
	Low	Monitor
Corner break	Medium	Patching - PCC Full Depth
	High	Patching - PCC Full Depth
	Low	Monitor
Linear cracking	Medium	Crack Sealing - PCC
	High	Patching - PCC Full Depth
	Low	Monitor
Durability cracking	Medium	Patching - PCC Full Depth
	High	Slab Replacement - PCC
	Low	Monitor
Joint seal damage	Medium	Joint Seal (Localized)
_	High	Joint Seal (Localized)
	Low	Monitor
Small patch	Medium	Patching - PCC Partial Depth
	High	Patching - PCC Partial Depth
	Low	Monitor
Large patch	Medium	Patching - PCC Full Depth
	High	Patching - PCC Full Depth
Popouts	N/A	Monitor
Pumping	N/A	Monitor
	Low	Monitor
Scaling	Medium	Patching - PCC Partial Depth
	High	Slab Replacement - PCC
	Low	Monitor
Faulting	Medium	Grinding (Localized)
	High	Grinding (Localized)
	Low	Monitor
Shattered slab	Medium	Crack Sealing - PCC
	High	Slab Replacement - PCC
Shrinkage cracking	N/A	Monitor
	Low	Monitor
Joint spall	Medium	Patching - PCC Partial Depth
	High	Patching - PCC Partial Depth
	Low	Monitor
Corner spall	Medium	Patching - PCC Partial Depth
	High	Patching - PCC Partial Depth
	Low	Monitor
ASR	Medium	Patching - PCC Full Depth
	High	Slab Replacement - PCC

Treatment name	Unit cost
Crack Sealing - AC	\$1.26 ft
Crack Sealing - PCC	\$1.92 ft
Grinding (Localized)	\$4.98 ft
Joint Seal (Localized)	\$1.92 ft
Patching - AC Deep	\$11.82 sf
Patching - AC Leveling	\$4.14 sf
Patching - AC Shallow	\$7.95 sf
Patching - PCC Full Depth	\$74.32 sf
Patching - PCC Partial Depth	\$10.68 sf
Slab Replacement - PCC	\$40.00 sf
Surface Treatment	\$0.52 sf
Undersealing - PCC	\$3.17 ft

Table E3. Unit costs for localized maintenance treatments.

Table E4. Major rehabilitation unit costs based on PCI ranges.

PCI range	Cost
0-30	\$8.59 sf
30-40	\$8.59-\$7.13 sf
40-50	\$7.13-\$5.94 sf
50-60	\$5.94-\$4.19 sf
60-70	\$4.19-\$2.66 sf
70-80	\$2.66-\$1.30 sf
> 80	\$1.30 sf

This page intentionally left blank.

Appendix F Localized Maintenance Recommendations

Branch	Section	Treatment	Quantity	Unit	Cost
ΑΡΑ	001	Patching - PCC Partial Depth	30	SqFt	\$323
Preventive		PCI Before: 99 After: 100	-	Total	\$323
АРВ	001	Crack Sealing - AC	7,179	Ft	\$9 <i>,</i> 045
APB	001	Patching - AC Deep	478	SqFt	\$5,645
Prev	ventive	PCI Before: 56 After: 62	-	Total	\$14,691
APB	002	Crack Sealing - AC	3,593	Ft	\$4,528
APB	002	Patching - AC Deep	412	SqFt	\$4,872
Rest	orative	PCI Before: 45 After: 60	-	Total	\$9 <mark>,3</mark> 99
CTA1	001	Patching - PCC Partial Depth	22	SqFt	\$235
Prev	ventive	PCI Before: 94 After: 95	-	Total	\$235
CTA2	001	Joint Seal (Localized)	1,710	Ft	\$3,283
Prev	ventive	PCI Before: 87 After: 92	-	Total	\$3,283
СТАЗХ	001	Joint Seal (Localized)	960	Ft	\$1,843
Prev	ventive	PCI Before: 89 After: 96	-	Total	\$1,843
СТАЗХ	002	Crack Sealing - AC	33	Ft	\$42
СТАЗХ	002	Surface Treatment	1,256	SqFt	\$653
Prev	ventive	PCI Before: 61 After: 70	-	Total	\$695
СТАМ	001	Crack Sealing - AC	195	Ft	\$245
СТАМ	001	Surface Treatment	607	SqFt	\$316
Prev	ventive	PCI Before: 75 After: 87	-	Total	\$561
CTD1	002	Crack Sealing - AC	403	Ft	\$507
CTD1	002	Patching - AC Deep	44	SqFt	\$525
CTD1	002	Surface Treatment	1,588	SqFt	\$826
Ste	opgap	PCI Before: 48 After: 59	-	Total	\$1,857
CTD1	003	Patching - AC Shallow	52	SqFt	\$413
CTD1	003	Surface Treatment	800	SqFt	\$416
Prev	ventive	PCI Before: 64 After: 85	-	Total	\$829
СТЕ	001	Joint Seal (Localized)	1,800	Ft	\$3 <i>,</i> 456
Prev	ventive	PCI Before: 94 After: 98	-	Total	\$3,456
PPTC	001	Joint Seal (Localized)	2,120	Ft	\$4,070
РРТС	001	Patching - PCC Partial Depth	29	SqFt	\$310
Prev	ventive	PCI Before: 92 After: 98	-	Total	\$4,381
PPTE	001	Crack Sealing - AC	2,828	Ft	\$3,563
PPTE	001	Patching - AC Deep	89	SqFt	\$1,050
Rest	orative	PCI Before: 59 After: 63	-	Total	\$4,614
PPTE	002	Surface Treatment	146	SqFt	\$76
Prev	ventive	PCI Before: 66 After: 71	-	Total	\$76
ΡΤΑ	001	Patching - PCC Partial Depth	64	SqFt	\$682
Prev	entive	PCI Before: 98 After: 100	-	Total	\$682
PTD	001	Crack Sealing - AC	1,898	Ft	\$2,391

Table F.1. Recommended maintenance by section report (STC)

PTD	001	Patching - AC Deep	1,075	SqFt	\$12,713
PTD	001	Patching - AC Shallow	821	SqFt	\$6,526
PTD	001	Surface Treatment	21,597	SqFt	\$11,230
Rest	orative	PCI Before: 38 After: 62	-	Total	\$ <mark>32,</mark> 860
PTD	002	Crack Sealing - AC	14	Ft	\$18
PTD	002	Surface Treatment	3,320	SqFt	\$1,726
Prev	ventive	PCI Before: 67 After: 71	-	Total	\$1,745
PTD	003	Patching - PCC Partial Depth	12	SqFt	\$122
Prev	ventive	PCI Before: 96 After: 98	-	Total	\$122
PTD	004	Crack Sealing - AC	256	Ft	\$323
PTD	004	Surface Treatment	101	SqFt	\$53
Prev	ventive	PCI Before: 67 After: 80	-	Total	\$375
PTD	005	Crack Sealing - AC	1,542	Ft	\$1,942
PTD	005	Patching - AC Deep	163	SqFt	\$1,916
PTD	005	Patching - AC Shallow	423	SqFt	\$3,367
PTD	005	Surface Treatment	12,641	SqFt	\$6,573
Sto	opgap	PCI Before: 48 After: 56	-	Total	\$13,798
RY1331	001	Joint Seal (Localized)	9,652	Ft	\$18,533
Prev	ventive	PCI Before: 96 After: 98	-	Total	\$18,533
RY1331	002	Joint Seal (Localized)	8,446	Ft	\$16,216
RY1331	002	Patching - PCC Partial Depth	48	SqFt	\$524
Prev	ventive	PCI Before: 95 After: 97	-	Total	\$16,740
RY1331	003	Joint Seal (Localized)	11,261	Ft	\$21,621
Prev	ventive	PCI Before: 94 After: 96	-	Total	\$21,621
RY523	003	Joint Seal (Localized)	2,750	Ft	\$5,280
Prev	ventive	PCI Before: 95 After: 99	-	Total	\$5,280
RY523	004	Crack Sealing - AC	19	Ft	\$24
Preventive		PCI Before: 92 After: 93	-	Total	\$24

Branch	Section	Distress Type	Severity	Treatment	Estimated Quantity	Unit	Cost
APB	001	L & T CR	Н	Crack Sealing - AC	68	Ft	\$85
APB	001	ALLIGATOR CR	L	Crack Sealing - AC	266	Ft	\$336
APB	001	L & T CR	М	Crack Sealing - AC	1,327	Ft	\$1,673
APB	001	BLOCK CR	М	Crack Sealing - AC	5,517	Ft	\$6,952
APB	002	ALLIGATOR CR	L	Crack Sealing - AC	60	Ft	\$76
APB	002	L & T CR	М	Crack Sealing - AC	1,094	Ft	\$1,379
APB	002	BLOCK CR	М	Crack Sealing - AC	2,438	Ft	\$3,072
CTA3X	002	ALLIGATOR CR	L	Crack Sealing - AC	10	Ft	\$13
CTA3X	002	L & T CR	М	Crack Sealing - AC	23	Ft	\$29
CTAM	001	L & T CR	М	Crack Sealing - AC	195	Ft	\$245
CTD1	002	L & T CR	Н	Crack Sealing - AC	10	Ft	\$13
CTD1	002	L & T CR	М	Crack Sealing - AC	393	Ft	\$495
PPTE	001	ALLIGATOR CR	L	Crack Sealing - AC	89	Ft	\$112
PPTE	001	L & T CR	М	Crack Sealing - AC	2,739	Ft	\$3,451
PTD	001	ALLIGATOR CR	L	Crack Sealing - AC	144	Ft	\$181
PTD	001	L & T CR	М	Crack Sealing - AC	1,754	Ft	\$2,210
PTD	002	L & T CR	М	Crack Sealing - AC	14	Ft	\$18
PTD	004	L & T CR	М	Crack Sealing - AC	256	Ft	\$323
PTD	005	ALLIGATOR CR	L	Crack Sealing - AC	19	Ft	\$24
PTD	005	L & T CR	М	Crack Sealing - AC	1,523	Ft	\$1,919
RY523	004	L & T CR	М	Crack Sealing - AC	19	Ft	\$24
				Total:	17,960	Ft	\$22,629
CTA2	001	JT SEAL DMG	М	Joint Seal (Localized)	1,710	Ft	\$3,283
СТАЗХ	001	JT SEAL DMG	М	Joint Seal (Localized)	960	Ft	\$1,843
CTE	001	JT SEAL DMG	М	Joint Seal (Localized)	1,800	Ft	\$3,456
PPTC	001	JT SEAL DMG	М	Joint Seal (Localized)	2,120	Ft	\$4,070
RY1331	001	JT SEAL DMG	М	Joint Seal (Localized)	9,652	Ft	\$18,533
RY1331	002	JT SEAL DMG	М	Joint Seal (Localized)	8,446	Ft	\$16,216
RY1331	003	JT SEAL DMG	М	Joint Seal (Localized)	11,261	Ft	\$21,621
RY523	003	JT SEAL DMG	М	Joint Seal (Localized)	2,750	Ft	\$5,280
				Total:	38,699	Ft	\$74,303
APB	001	ALLIGATOR CR	М	Patching - AC Deep	478	SqFt	\$5,645
APB	002	ALLIGATOR CR	М	Patching - AC Deep	412	SqFt	\$4,872
CTD1	002	ALLIGATOR CR	М	Patching - AC Deep	44	SqFt	\$525
PPTE	001	ALLIGATOR CR	М	Patching - AC Deep	89	SqFt	\$1,050
PTD	001	ALLIGATOR CR	М	Patching - AC Deep	1,075	SqFt	\$12,713
PTD	005	ALLIGATOR CR	М	Patching - AC Deep	163	SqFt	\$1,916
				Total:	2,262	Ft	\$26,720
CTD1	003	RAVELING	Н	Patching - AC Shallow	52	SqFt	\$413
PTD	001	PATCHING	М	Patching - AC Shallow	821	SqFt	\$6,526

Table F.2. Recommended maintenance by treatment (STC)

PTD	005	PATCHING	М	Patching - AC Shallow	423	SqFt	\$3,367
Total:				1,296	Ft	\$10,306	
APA	001	JOINT SPALL	М	Patching - PCC Partial Depth	30	SqFt	\$323
CTA1	001	JOINT SPALL	М	Patching - PCC Partial Depth	22	SqFt	\$235
PPTC	001	JOINT SPALL	Н	Patching - PCC Partial Depth	29	SqFt	\$310
ΡΤΑ	001	JOINT SPALL	М	Patching - PCC Partial Depth	64	SqFt	\$682
PTD	003	CORNER SPALL	М	Patching - PCC Partial Depth	12	SqFt	\$122
RY1331	002	CORNER SPALL	Н	Patching - PCC Partial Depth	16	SqFt	\$175
RY1331	002	CORNER SPALL	М	Patching - PCC Partial Depth	32	SqFt	\$349
Total:				205	Ft	\$2,197	
CTA3X	002	WEATHERING	М	Surface Treatment	1,256	SqFt	\$653
CTAM	001	WEATHERING	М	Surface Treatment	607	SqFt	\$316
CTD1	002	WEATHERING	М	Surface Treatment	1,588	SqFt	\$826
CTD1	003	WEATHERING	М	Surface Treatment	800	SqFt	\$416
PPTE	002	RAVELING	М	Surface Treatment	37	SqFt	\$19
PPTE	002	WEATHERING	М	Surface Treatment	110	SqFt	\$57
PTD	001	WEATHERING	М	Surface Treatment	21,597	SqFt	\$11,230
PTD	002	WEATHERING	М	Surface Treatment	3,320	SqFt	\$1,726
PTD	004	WEATHERING	М	Surface Treatment	101	SqFt	\$53
PTD	005	WEATHERING	М	Surface Treatment	12,641	SqFt	\$6,573
	Total: 42,056 Ft \$21,869						

Appendix G Maintenance Repair Guidelines

General Comments

Ongoing inspections are the cornerstone of a maintenance management program. Crack sealing prevents surface water from entering the pavement structure and helps prevent the introduction of incompressible material into the paving joints and cracks, reducing the chances for spalls and further pavement deterioration.

Preservation of a pavement system will require a combination of preventive, sustaining, and restorative maintenance repairs. Preventive maintenance is primarily an inspection program, sustaining maintenance is an ongoing maintenance function, whose purpose is to seal newly formed cracks in areas where the sealant is in otherwise satisfactory condition. Restorative repairs are major work items, often performed under contract that typically involves complete removal and replacement of existing sealant.

Maintenance Activities

Flexible (Asphalt) Pavement

Longitudinal and transverse (L&T) cracks at medium severity (>¼" wide) should be filled with a good quality crack filler material. High-severity cracks must normally be patched. Cracks rated at low severity may be narrow-unsealed cracks or sealed cracks up to 3 inches wide. The PCI procedure does not distinguish between narrow unfilled cracks and wider filled cracks. When 25 percent or more of total crack quantity is at medium or high severity, a restorative program becomes cost-effective. When medium- or high-severity cracking constitutes less than 25 percent of the total, sustaining maintenance is usually more cost-effective.

Medium- and high-severity existing patches should be replaced with new patches. Small areas (usually less than 100 square feet per patch) of alligator cracking and rutting at medium and high severity may also be repaired by patching. Larger patches should be considered if equipment can be made available to accomplish the work. Patching to repair up to 10 percent of the surface of a pavement section that is otherwise serviceable can result in significant cost savings as compared to rehabilitation of the entire section.

PCC (Concrete) Pavement

Joint seal damage at medium and high severity should be repaired. If medium- and high-severity damage is limited to less than about 25 percent of total joint length, sustaining maintenance is recommended. If medium and high-severity damage exceeds about 25 percent of the total joint length, joint sealant should be removed and replaced under a restorative repair project.

Longitudinal/transverse/diagonal (LTD) cracks at low and medium severity should be considered for sealing as part of the joint sealing project. High-severity LTD cracks require sealing, patching, or slab replacement, depending on the extent of deterioration.

Small patches are most often placed to repair medium- and high-severity spalls or to replace deteriorated older patches. Restorative small patches are typically partial depth repairs, usually to load transfer steel. Large patches and corner breaks at medium and high severity should be repaired by full-depth large patches.

High-severity LTD cracks and shattered slabs are candidates for patching and slab replacement. Low-severity shattered slabs can be left in place pending further deterioration.

Pavement Failure

Before maintenance and repairs are attempted, it helps to have an understanding of the way pavement performs and deteriorates.

Environmental/Age-Related Deterioration

Seasonal temperature changes cause expansion and contraction of the pavement materials, causing the pavement to move up to 1 foot per 1,000 feet. Much of this movement can be witnessed as the opening and closing of existing transverse cracks.

The pavement thickness and type of subgrade plays a large role in the formation and spacing interval of transverse cracks. If the subgrade material is smooth or rounded, the pavement surface will move relatively freely, the transverse cracks will usually be spaced far apart (>60 feet). If the subgrade material is rough or angular the pavement surface will not move freely and transverse cracks will be spaced more closely (<40 feet). The distance between transverse cracks will also depend on the pavement thickness, as a thicker pavement can resist cracking for longer lengths, but around 50 feet is typical for general aviation airport pavements.

Age related distress deals with the pavement oxidation or loss of volatile components to the atmosphere. An oxidized pavement becomes more brittle with time. Surface treatments and seal coats are designed, in part, to provide a protective barrier and prevent this type of oxidation.

Materials Related Deterioration

Subsurface water can have the greatest impact on pavement deterioration. A wet subgrade greatly reduces the ability of a pavement to support wheel loads, and the results often show up as rutting and cracking. The fine materials in a wet base can be pumped up through the cracks and eventually result in a loss of subgrade support. This loss of support can be evidenced as corner breaks and faulting. Moisture inside a pavement system expands when it freezes; creating stresses that push and tear at the pavement. The following thaw cycles will leave voids in the pavement structure that enable further rutting and breaking. Repeated freeze/thaw cycles will eventually cause pavement to disintegrate. One of the best ways to assure pavement longevity is to provide drainage and keep the subgrade dry.

Aggregate is the biggest component of any pavement structure, and it is the contact between the aggregate particles that actually transfers the load and provides the strength. Aggregate durability and shape are major factors affecting pavement performance. Durability is the ability of the aggregate to perform satisfactorily over time and resist the detrimental effect of nature. Sharp, well-angled aggregate that interlock, compact densely, and resists movement are the most desirable.

Air Voids

Well-distributed interconnected air voids allow escape paths for freezing water and generally reduce susceptibility to freeze/thaw damage. In PCC pavements, closely spaced interconnected air voids provide the greatest degree of protection.

Asphalt pavements, on the other hand, only tolerate air voids as necessary. Air voids allow for expansion of the asphalt binder, but also allow water penetration into the pavement. Interconnected air voids are undesirable here because the voids allow air to penetrate the asphalt layers and oxidize the binder. As air voids increase, durability and flexibility decrease, but stability and skid resistance increase. Asphalt pavements should be designed and compacted so that air voids are not interconnected. The air voids should allow only for the expansion of the asphalt and aggregate without, bleeding, and air voids should be kept low enough to prevent water and air from penetrating the asphalt layers.

Binders

Regardless of whether the pavement is asphalt or concrete, the binder material is mixed with the aggregate to coat all particles with a thin film. An asphalt coating allows the pavement to be flexible and still resist large movements. Durability of the asphalt pavement is increased by a thicker film because it is more resistant to age hardening; however, too thick of a film and the asphalt acts like a lubricant, promoting ruts, shoving, and bleeding. Specifications control aggregate and binder mix quantities, but each mix should be customized for materials available locally.

With a concrete pavement, the aggregate supports the load, but the cement binder interlocks with the aggregate to inhibit all movement. Hydration is the term for the chemical reaction of portland cement with water, and in the hydration process, dry cement particles react with water, to form gels, and then crystals, that grow and bond with the aggregate to form a rigid interlocking structure. Hydration can continue for years, but much of the ultimate strength will be reached within 28 days. Hydration is a sensitive chemical process, and typically, any admixtures used to accelerate the hydration process will reduce durability, and their use should be considered carefully or avoided.

Stress Distribution/Load Related Deterioration

PCC (rigid) and asphalt (flexible) pavements differ in the way loads are distributed. A concrete slab resists bending and transfers loads evenly, an asphalt pavement is designed to bend, and gradually spreads loads over wider areas. Rutting is a subgrade failure caused by a compressive yielding of the subgrade.

Load-related cracks can start at the top or bottom of a pavement section. In asphalt sections, loadrelated (fatigue) cracks start at the bottom. If a load-related crack reaches the surface, it usually indicates significant structural deficiency. In PCC pavement, corner breaks are caused by top tension, and the crack propagates downward. Mid-slab LTD cracks are examples of bottom tension.

Spalls can be caused by either wheel loads or environmental factors, anytime there is movement between adjacent slabs. If a small rock is allowed into a joint, a differential movement between adjacent slabs can cause a spall. Spalling can be minimized by keeping joint and crack sealant intact.




Figure 1. Pavement failure.

Points to Remember

Pavement wears out.

The longer a pavement remains in service, the greater the effort needed to keep it in service. A good maintenance and repair program will increase service life significantly, but cannot be expected to extend service life indefinitely.

Pavement moves.

Pavement moves in response to temperature changes. Transverse cracks can vary from nearly closed in the summer to open an inch or more in winter. This movement cannot be prevented. It must be understood and provided for during design and construction. The changing crack widths will dictate the reservoir size required for sealant. Measure cracks at their widest and narrowest states, then prepare adequate ($\frac{1}{2}$ - 1 $\frac{1}{2}$ inch) sealant reservoirs for crack sealing projects.

Longitudinal joints and cracks are important.

The most important reason for sealing cracks is to deny surface water access to the pavement and subgrade. Most water drains from centerline to shoulders. Longitudinal cracks, which run parallel to the centerline provide the greatest potential to divert water into the pavement structure, and must be sealed.

Sealing is not always the best answer.

The FAA maximum allowable open trench width on aircraft movement areas is three-inches; therefore, any crack wider than three-inches should be patched. A severe spall or a crack that has settled below the pavement elevation indicates a failure. If the pavement has disintegrated to the point that aggregate interlock is lost, sealant alone will not be sufficient, and patching should be considered.

Maintenance and repairs must be done correctly.

To achieve optimum results from repairs, proper preparation, use of quality materials, and proper application are essential. Any shortcuts will reduce the quality and effectiveness of the repairs. A rule of thumb is that proper maintenance will last twice as long as an unprepared area. Good maintenance takes time and deserves high-quality materials.

Schedule maintenance and repair activities carefully.

Any pavement defect can be corrected. Concentrate on repairs that are cost-effective, operationally important, and that extend service life. Some surface blemishes can be ignored safely, and many structural problems are beyond economical correction. When future rehabilitation is imminent, maintenance activities should be limited to only those that ensure continued safety and minimize foreign object damage (FOD) potential.

Equipment

Many excellent pavement repair and sealing products are available. Specialized tools and equipment help ensure quality repairs. This section reviews equipment compatible with airport needs.

Air Compressor

Used to remove sand and debris from prepared cracks and joints, the compressor should have a sustained capacity of 120 cubic feet per minute with a nozzle velocity of 100 psi. Trailer-mounted compressors typically have capacities in this range.

Concrete Saw

A saw capable of making a minimum 3-inch deep cut is required. The saw should be capable of making cuts in asphalt or concrete. Gasoline-powered 5-25 hp wheel mounted saws typically are preferred for this type of work, but electric and pneumatic tools are also available.

Heating Kettle

Applying sealant is the most time-consuming operation, and a sealing machine with heating and pressure application capabilities is a critical item in a sealing program. The capacity of the sealing equipment dictates the rate at which a crew progresses. For large sealing projects, a minimum 100 gallons/per hour sustained capacity is recommended. The unit should be a double boiler type, with mechanical agitators or continuous recirculation.

Router

A concrete saw can be used to prepare joints, but for random cracking, a mechanical router with a vertical impact mechanism is preferred. When cracks are being routed, this activity will dictate speed of the crew. Crack routers in the 25hp range are commonly used and are available from a variety of manufacturers.

Sand Cleaner

A sand blaster helps to clean loose particles and dust from prepared cracks. The unit must have sufficient force to expose fresh, vital pavement to bond with sealant and patching materials.

Vibratory Roller or Plate Compactor

Required to properly compact plant mixed and packaged patching materials. Small rollers are best for pothole type applications, plate compactors are best for large areas.

Other Equipment

Other general use equipment that can be helpful in a maintenance program includes bucket loaders, dump trucks, water tanks, and a power sweeper unit.

Materials

Pavement repair materials are constantly being introduced and improved. This section provides information on products compatible with airport needs.

Joint and Crack Sealer

Hot poured, pressure injected, polymeric rubberized asphalt sealant meeting ASTM D3405 specifications is suitable for most joint and crack sealing requirements. This product is relatively inexpensive, durable, and suitable for both PCC and asphalt pavements. Other, more expensive, hot applied sealants that promise longer life are being developed for specialty applications, and twin component cold applied sealants, similar to URASEAL 200, have also been used with success. Contact your local distributor.

Flexible Pavement Patch

Long-term patches should be made with a high-quality plant mixed hot asphalt having a ¾-inch maximum aggregate size and meeting FAA P401, or highest quality highway specifications. High-performance plant mixed cold patching products that can be stockpiled on-site have been developed. Low-quality packaged materials available from local hardware type stores should be avoided and only be used for temporary patches that maintain safety and service.

PCC Pavement Patch

Permanent patches in PCC pavement should be made with a minimum 6-bag mix of hi-early airentrained cement with 1-inch maximum size aggregate. Concrete should have zero slump and a coarse texture. As with asphalt patches, low-quality packaged materials should only be used as temporary patches to maintain safety and service until a more permanent repair can be made.

Techniques

Crack Sealing

- Cracks over ¼ inches wide should be sealed. Cracks wider than 3 inches should be patched.
- Sealant depth above the backer rope should be equal to the width of the reservoir, or as recommended by the manufacturer.
- Routed cracks should be sand blasted, to prepare the vertical edges for bonding with the sealant. Clean cracks with compressed air prior to sealing.
- Backing material should always be placed into the cracks. Commercial products are available, and several sizes of rope should always be available to accommodate various crack sizes.
- Apply sealant after placing the backer rope. Follow the manufacturer's instructions. Sealant should be applied to within ¼ inch of the pavement surface.
- The final activity is to clean the surrounding pavement areas. A vacuum sweeper works well for this. Allow the sealant time to set, before using a broom.




Figure 2. Crack sealing.

Note:

This crack sealing technique is meticulous in its design and procedure. It has a proven record of performance. Using backer rope forces the sealant into a predictable shape—narrow in the center and wide on the sides. This sealant profile allows the sealant to firmly bond with the vertical edges, yet stretch easily with pavement movement. In an effort to minimize labor requirements and reduce crack-sealing costs, an alternative procedure, the overband technique, is presented on the following page. This procedure can produce good results for up to 5 years.

Always remember that, within reasonable limits, thinner sealant material will stretch more easily with the pavement movement, and stay bonded longer.

Overband Technique


A latex modified, fiber reinforced, asphalt cement sealant using the techniques outlined below.

Material

- Blend grade 20 or equivalent asphalt cement with latex rubber at 5 percent by weight of asphalt.
- Again, at 5 percent by weight of asphalt, add polyester fibers into agitator tank.
- Maintain blended asphalt temperature at least 20 degrees below flash point.
- Continuously recycle hot blended asphalt through pumps and hoses when heating kettle is in standby mode.

Application

- Sealant should be applied to dry pavement, with ambient temperatures above 40 degrees.
- Cracks should be sand cleaned and blown free of debris immediately before sealing.
- Application of sealant immediately follows cleaning of the crack.
- Sealant should be pressure applied from a wand-type applicator with a special "overband" nozzle.
- Seat the sealant with a steel-wheeled roller immediately after placement.
- In wider cracks, a backer rope is recommended to limit material quantities required.







Patching (Asphalt Pavement)

Cracks wider than 3 inches should be patched. Cracks with secondary cracking and vertical movement should also be patched. Failed existing patches should be replaced. Patching can also repair small areas of alligator cracking and rutting. A patch differs from sealant in that it restores load-bearing capacity. Therefore, it must be constructed carefully to distribute stresses evenly and perform as an integral piece of the surrounding pavement. The patch must be wide enough to ensure that it bonds to fresh, vital pavement on all sides, and deep enough to reach fresh underlying layers, but never less than 3 inches.

- Examine the distressed area and mark the patch outline. This examination may require a pick or chisel to test the pavement integrity in and around the distressed area.
- The patch area should be cut out with a vertical saw cut not less than 3 inches deep.
- The enclosed pavement should then be removed, leaving the vertical sawed edges undamaged and providing a relatively even, flat floor at the appropriate depth.
- The sides and bottom should be sand cleaned and blown out with compressed air

- The sides and bottom should then be painted with a rapid curing asphalt tack coat. The tack coat may be sprayed on or applied with a brush or rag. Care should be taken to achieve complete coverage without allowing excess material to "pool" on the bottom.
- Allow tack coat to cure (about 2 to 4 hours) until it reaches a gummy consistency, which readily retains the impression of a fingerprint.
- Place hot mixed asphalt concrete evenly and mound slightly above surrounding pavement. Allow approximately ¼ inch of compaction for each inch of patch depth.
- Compact in place with vibratory roller or plate compactor. Asphalt concrete should not be compacted in layers greater than 6 inches. If patch depth is greater than 6 inches, asphalt concrete should be placed and compacted in successive layers.
- In deep, narrow patches such as at joint reflective cracks, a sand asphalt mix may be required in lower layers to allow movement and prevent bridging the adjacent slabs.
- Considerable judgment is required in placing the asphalt concrete to achieve a fully compacted patch without creating a bump or depression. The ¼ inch per inch factor is a rule of thumb. Actual compression will vary with the mix. Experimentation and experience are required to achieve optimum results.





Patching (PCC)

The technique outlined here simulates a thin bonded PCC overlay. This procedure has been proven in service throughout the country.

- Examine the distressed area and mark the patch outline. This examination may require a pick or chisel to test pavement integrity in and around the distressed area.
- Saw cut the area to a depth of 2 inches. The enclosed area is then chipped or jack hammered to solid pavement, but not less than a 2-inch nominal depth.
- The sides and bottom are sand cleaned and air-blasted to expose vital, clean concrete.
- A 25 percent solution of muriatic acid is applied to all exposed surfaces within the patch.
- The muriatic acid solution is thoroughly flushed from the patch area with water.
- Compressed air is used to remove excess water from the area, but exposed concrete must be maintained in a moist condition.
- The sides and bottom of the area are then coated with approximately a 1/16-inch layer of cement grout applied at the consistency of paste. The grout acts as an adhesive to bond the fresh concrete to existing concrete.
- If the patch is adjacent to joints, the continuity of the joint must be maintained by placing inserts approximately the shape of the desired joint against the wall of the patch.
- Before concrete grout begins to dry, concrete is placed in the patch area and is compacted into position with hand tampers or a vibrating plate tamper.
- When the patch has been struck to the proper slope and elevation, a surface texture is applied to approximate the texture of adjacent pavement.
- Joint edges may be edged slightly to remove sharp edges. The patch should be covered with polyethylene or sprayed with a curing compound.
- Clean the surrounding pavement before concrete spillover has a chance to set up.
- The patch may be open to traffic in 72 hours.






Figure 5. PCC patch.

Joint Repair (PCC)

Seal joints in PCC pavement when existing sealant has deteriorated to a degree that allows water and incompressibles to enter the joint. Hairline cracks are not yet candidates for sealing.

- Rout a reservoir for the sealant. Sealant reservoir should be ½ inch wide and 1 inch deep.
- For cracks wider than ½ inch, the reservoir should be ¼ inch wider than the crack. Depth should be such that sealant above the backer rope is at most equal to reservoir width, or as recommended by manufacturer.
- Routed cracks should be sand cleaned, using fine sand at reduced pressure. Proper cleaning will expose fresh, vital pavement on the vertical crack edge.
- Immediately prior to sealing, cracks should be cleaned with compressed air. Ensure that all sand, debris, and incompressibles are removed from the crack. A small hand-held hook or plowing tool may be needed to dislodge some particles. Water cleaning is not recommended, simply because the drying time delays the sealing operation.
- After cleaning with compressed air, a backing material should be placed into the crack. The backer rope may be any compressible substance compatible with bituminous sealant material that will wedge into cracks at a designated depth and support the sealant. Several sizes should be immediately available in the field to accommodate various crack sizes.
- Sealant should be pressure applied with a wand type applicator to within ¼ inch of the pavement surface. Follow the equipment manufacturer's instructions.
- The final activity is to clean the surrounding pavement area. A vacuum sweeper works well. Brooms should not be used until the sealant has taken an initial set.





Typical joint with deficient sealant and a collection of debris & incompressibles.

Rout out old sealant, debris and incompressibles. Clean joint sides to expose fresh, clean concrete and stone. Retain existing reservoir shape.




Figure 6. PCC joint/crack repair.

Inspection Date	Inspector	Pavement location (branch/section)	Change in condition (new distress type, increased quantity or severity)	Maintenance performed since last inspection

Table 1. Maintenance and "drive by" inspection log.