



# OMRR Updates for Construction Inspectors Concrete Office

Maria Masten, Matt Herbst, Brad Swenson, Rob Golish  
and Gordy Bruhn

February 17 and 23, 2021

# Agenda

- Introductions
- General Concrete Updates (~ 15 minutes)
- Concrete Pavement Rehabilitation (CPR) Updates (~10 minutes)
- Concrete Paving Updates (~15 minutes)
- Certified Ready-Mix Plant and Mix Design Updates (~ 35 minutes)

# Concrete Office Personnel

## **Maria Masten – Concrete Engineer**

**651-366-5572**

- Specifications and Special Provisions
- Materials Failure Recommendations
- Structural Concrete
- High Performance and Mass Concrete
- Specialty Concrete, Self Consolidating Concrete

## **Rob Golish – Assistant Concrete Engineer**

**651-366-5576**

- Concrete Paving and Joint Layout Reviews
- Materials Design Recommendations
- Standard Plans and Plates
- Approved/Qualified Products

# Concrete Office Personnel

## **Matt Herbst – Ready-Mix Engineering Specialist**

**651-366-5423**

- General Concrete Mix Designs
- High Performance, Mass and Specialty Mix Designs
- Concrete Aggregates
- Certified Ready-Mix Program – Metro District
- Clarified Water

## **Gordy Bruhn – Concrete Field Engineering Specialist**

**651-366-5523**

- General Concrete and Structural Concrete Field Issues
- Concrete Pavement Rehabilitation (CPR)
- CPR and Paving Plan Review

## **Brad Swenson – Greater MN Plant Coordinator**

**218-232-1012**

- Certified Ready-Mix and Bituminous Plants Support – Outstate
- Concrete Plant Tech Certification
- Materials Certification

# Concrete Engineering Unit

- 2301 – Concrete Pavement
- 2302 – Concrete Pavement Rehab (CPR)
- 2406 – Bridge Approach Panels
- 2461 – Structural Concrete
- 2519 – Cellular Concrete (CLSM)
- 2520 – Lean Mix Backfill
- 2521 – Concrete Walks
- 2531 – Concrete Curbing
- 2533 – Concrete Median Barrier



# MnDOT Concrete Engineering Website

[Materials Home](#) [Concrete Home](#) [Contacts](#)

## What we do

The Concrete Unit provides leadership and assistance to agencies, contractors, and consultants on specifying, constructing and maintaining long lasting concrete structures and pavements.

## Mix Designs

- [Mix design submittals](#)
- [Approved Contractor mix designs by plant](#)

## Approved and Certified Materials and Sources

- [Approved/qualified products](#)
- [Certified concrete ready-mix plants](#)
- [Clarified Water Qualification Procedure](#)
- [Pre-qualified colored concrete Contractor/Installer list](#)

## Concrete Areas of Interest

- [Ready-mix](#)
- [Concrete pavement rehabilitation \(CPR\)](#)
- [Bridge and low slump concrete overlays](#)
- [Pavement](#)
- [Pavement design](#)
- [Precast concrete](#)
- [Road research](#)

## Guidance Documents

- [Cold Weather Concrete Placement](#)
- [Concrete Cylinders - Handling and Curing](#)
- [Gradation Testing and Acceptance](#)
- [Strength Testing and Acceptance](#)

## Aggregates

- [Concrete aggregate properties](#)
- [New source testing](#)
- [Alkali Silica Reactivity \(ASR\) - Fine aggregate](#)
- [Alkali Silica Reactivity \(ASR\) - Coarse aggregate](#)

## Resources

- [Concrete manual](#)
- [Concrete maturity](#)
- [Schedule of materials control](#)
- [Standard plans](#)
- [Standard plates](#)
- [Standard specifications for construction](#)
- [Special provisions](#)
- [Videos](#)

Always use the most current forms

<http://www.dot.state.mn.us/materials/concrete.html>



# Concrete Office Field Updates

**Gordon “Gordy” Bruhn | Sr. Engineering Specialist**

**Concrete Engineering Unit**

**Winter 2021**


# Vibration

- Protect newly placed concrete from damage by adjacent vibratory or backfilling operations for a minimum of 24 hours.
- Wait at least 72 hours after placing the concrete or after the concrete reaches a compressive strength of at least 3,000 psi
- **(Changed to 2000psi by special provision in April 2020)**  
(2000 psi for Concrete Paving)
- Hand operated concrete consolidation equipment and walk behind vibratory plate compactors are allowed 24 hours after placing the concrete, and other equipment as approved by the Engineer, in conjunction with the Concrete Engineer





# Driveway and Sidewalk Details Standard Plan Sheet 5-297.254



# Preformed Joint Filler (Type F Separation Material) (Approved Products List)

## 1. PRODUCT NAME

- PROFLEX<sup>®</sup> Vinyl Expansion Joint

## 2. PRODUCT DESCRIPTION

PROFLEX Vinyl Expansion Joints are manufactured from 100% recycled vinyl.

Thickness	1/4", 1/2"
Width	3", 3 1/2", 4", 6", 8"
Length	5', 10'

- Special order sizes require a two pallet minimum purchase.

## 3. ADVANTAGES

PROFLEX is easy to handle, extremely durable and flexible. PROFLEX does not use adhesive binders in the manufacturing process, and can be stored outside.



# Structural Concrete Specification 2461

## Water Adjustments

- For **all** grades of concrete, no water additions 1 hour after batching,
- For grades of concrete **NOT used for Slip-Forming**, do not make water adjustments after discharging approximately 1 cubic yard.
- **2461.3.G.7.a “Concrete Placed by the Slip-Form Method”**, The Engineer will allow water adjustments as necessary to facilitate slip-form placement.

**(Again, NO water additions 1 hour after batch time!)**

# 2401.3.G.2.A.9.d On-site Field Adjustments for Bridge Slab Concrete

In addition to 2461.3G.4, Field Adjustments, if any adjustments are necessary on site:

- Except for Viscosity Modifying Admixtures (VMAs), onsite additions of admixtures are limited to admixtures stated on Certificate of Compliance (aka batch ticket)
- On site water additions is limited to maximum 1 gal per cubic yard of batched concrete.

***Test the concrete when an adjustment(s) is made in the field***

# Strength Material Exceptions Table 2461-6

Table 2461-6 Concrete Mix Design Requirements (Not applicable to Mass Concrete)									
Concrete Grade	OLD Mix Number	NEW Mix Number	Intended Use *	Maximum w/c ratio 	Maximum Cementitious Content (lbs/yd <sup>3</sup> )	Maximum %SCM (Fly Ash/ Slag/Ternary)	Slump Range	Minimum 28-day Compressive Strength, f'c	3137 Spec.
<b>B</b> Bridge Substructure	3Y43	3B52	Abutment, stems, wingwalls, paving brackets, pier columns and caps, pier struts	0.45	750	30/35/40	2 - 5"	4000 psi	2.D.1
<b>F</b> Flatwork	3A22 3Y22	3F32	Curb and gutter	0.42	750	30/35/0	½ - 3" #	4500 psi	2.D.1
	3A32 3Y32 3A34	3F52 3F57EX † 3F52CO ‡	Sidewalk, curb and gutter, slope paving, median sidewalk, driveway entrances, ADA pedestrian sidewalk	0.45	750	25/30/0	2 - 5"	4500 psi	2.D.1
	1A43	1G52	Footings and pilecap	0.55	750	30/35/40	2 - 5"	4500 psi	2.D.1
<b>G</b> General Concrete	3A43 3B42 3Y43	3G52	Footings, pilecap, walls, cast-in-place manholes and catch basins, fence posts, signal bases, light pole foundations, erosion control structures, cast-in-place box culverts, culvert headwalls, open flumes, cast-in-place wall stems	0.45	750	30/35/40	2 - 5"	4500 psi	2.D.1
	3Y12	3M12	Slipform barrier, Median barrier, non-bridge	0.42	750	30/35/40	½ - 1" #	4500 psi	2.D.1
<b>M</b> Median Barrier	3Y32	3M52	Barrier, Median barrier, non-bridge	0.45	750	30/35/40	2 - 5"	4500 psi	2.D.1
<b>P</b> Piling	1A43	1P42	MSE and gravity wall leveling pad	0.63	750	30/35/40	2 - 4"	3000 psi	2.D.1
	1C62	1P62	Piling, spread footing leveling pad	0.63	750	30/35/40	3 - 6"	3000 psi	2.D.1
<b>R</b> Pavement Rehabilitation	3A32 3B42	3R52	CPR - Full depth concrete repairs, concrete base	0.45	750	30/35/40	2 - 5"	4000 psi	2.D.3
<b>S</b> Bridge Superstructure	3Y16	3S12	Slipform bridge barrier, parapets, end post	0.42	750	30/35/40	½ - 1" #	4000 psi	2.D.2
	3A32 3A42 3Y43 3Y46 3Y46A	3S52	Median barrier, raised median, pilaster, curb, sidewalk, approach panel, formed bridge barrier, parapet, end post, collar	0.45	750	30/35/40	2 - 5"	4000 psi	2.D.2
	1X62 1X46	1X62	Cofferdam seals, rock sockets, drilled shafts	0.45	750	30/35/40	3 - 6"	5000 psi	2.D.1
<b>X</b> Miscellaneous Bridge	3X46	3X62	Drilled shafts above frost line	0.45	750	30/35/40	3 - 6"	5000 psi	2.D.1
	3Y33 3Y33A 3Y36 3Y36A	3Y42-M § 3Y42-S §	Bridge decks, integral abutment diaphragms, pier continuity diaphragms, expansion joint replacement mix	0.45	750	30/35/40	2 - 4"	4000 psi	2.D.2
<b>Y</b> Bridge Deck	3A37 3Y37	3Y47 **	Deck patching mix	0.45	750	30/35/40	2 - 4"	4000 psi	2.D.2

\* If the intended use is not included elsewhere in the Specification or Special Provisions, use mix 3G52, unless otherwise directed by the Engineer.  
 || The minimum water/cement (w/c) ratio is 0.30.  
 † Mix 3F57EX requires the use of Coarse Aggregate Designation "7", "2" or "3" for the 4<sup>th</sup> digit in accordance with Table 2461-3.  
 ‡ Identify specific color used on the certificate of compliance. Colored concrete is only allowed when specified in the plans or the Contract.  
 # Adjust slump in accordance with 2461.3.G.7.a for slipform concrete placement.  
 § The "-S" indicates a bridge deck with a structural slab and "-M" indicates a monolithic bridge deck.  
 \*\* Mix 3Y47 requires the use of Coarse Aggregate Designation "7" or "3" for the 4<sup>th</sup> digit in accordance with Table 2461-3.

# Documenting Material Exceptions

## Materials Certification Exception Summary (MCES)

### Document All:

- **Failing Tests (All strength Tests > 500psi deficient)**
- **Erroneous Test Results,**
  1. **Cylinders remained in the field greater than 7 days**
  2. **Improper Curing (Temps greater than 80°F)**
- **Monetary Adjustments on Strength Test Moving Average... Table 2461-19**
- **Missing Tests**
- **\*Test Tolerance Between Lab/field or Between QC/QA**
- **Non-Certified Testers**

# Moving Average Monetary Adjustment for Compressive Strength Tests

<b>Table 2461-19 All Concrete Grades</b>	
<b>Moving average of 3 consecutive strength tests</b>	<b>Monetary Reduction for Moving Average Failure *</b>
> 98.0% of f'c	No deductions for the materials placed as approved by the Engineer.
93.0% to 98.0% of f'c	\$20.00 per cubic yard or 10% of the Contractor-provided invoice for quantity represented by test that brought moving average into non-conformance
87.5% to < 93.0% of f'c	\$50.00 per cubic yard or 25% of the Contractor-provided invoice for quantity represented by test that brought moving average into non-conformance
< 87.5% of f'c	<p>Remove and replace concrete in accordance with 1503, "Conformity with Contract Documents," and 1512, "Unacceptable and Unauthorized Work," as directed by the Engineer.</p> <p>If the Engineer, in conjunction with the Concrete Engineer, determines the concrete can remain in place, the Engineer will adjust the concrete at a reduction of \$100.00 per cubic yard or 50% of the Contractor-provided invoice for quantity represented by test that brought moving average into non-conformance.</p>

# Strength Test Material Exceptions

## Failing Concrete Strength Test

1. A strength test is considered a **failing** , when the test strength test results shows **greater** than 500psi deficiency in strength,
  2. The specification does not contain a monetary adjustment for a single failing strength test (Table 2461-19 is for Moving Average monetary adjustments)
  3. A determination must be made as to whether the compressive strength achieved is adequate to perform as intended, (Yes or No)
- **Failing strength tests are required to be documented as **Material Exception**.**



# Moving Average of 3 Strength Test Results



Minnesota Department of Transportation  
Cylinder Strength Moving Average

Last revised (1/8/2019)

Project #:	SP 8825-88	Mix Design:	3G52
Engineer:	Mrs. Engineer	Minimum 28-day Compressive Strength, f'c (psi):	4500
RM Plant:	Mr. Plant	Total Cubic Yards being Adjusted:	125
Contractor:	The Concrete Guys	Total Monetary Adjustment:	\$2,500.00

\* See MnDOT Specification 2461.3.G.5.f(1)  
\*\* See MnDOT Specification 2461.3.G.5.f(2)

Field ID:	Date Made	Cubic Yards Placed	Strength Test (psi)	Strength Test Deficiency ≤ 500 psi below f'c	Strength Test Deficiency > 500 psi below f'c	Moving Average (psi)	Moving Average % of Req'd	Adjusted Contract Unit Price per Cubic Yard	Cubic Yards being Adjusted	Monetary Adjustment	Action Required for Moving Average Failure per MnDOT Specification 2461.G.5.f(4)
Day-1	1/1/21	100	5340								
Day-2	1/2/21	200	4360	*							
Day -3	1/3/21	62	4250	*		4650	103.33				
Day-4	1/4/21	80	4690			4433	98.52				
Day-5	1/5/21	60	4860			4600	102.22				
Day -6	1/7/21	250	4862			4804	106.76				
Day-6	1/7/21	86	5080			4934	109.64				
Day-7	1/8/21	20	4480	*		4807	106.83				
Day -8	1/9/21	60	4400	*		4653	103.41				
Day-9	1/10/21	5	4450	*		4443	98.74				
Day-10	1/11/21	200	4400	*		4417	98.15				
Day -10	1/11/21	125	3900		**	4250	94.44	\$20.00	125.0	\$2,500.00	\$20/yd3 or 10% of the yd3 invoice price




**ONLY MOVING AVERAGE FAILURES HAVE MONETARY DEDUCTIONS**

# Materials Certification Exception Summary

## (Form TP-02171-04)

MATERIALS CERTIFICATION EXCEPTIONS SUMMARY				
S.P. No.	Contract No.	Project Description	Const. Year	
T.H.	District	Contractor	Project Location	
Project Engineer/Supervisor			Federal No.	Page of
<b>Materials and products used on project:</b> (check all boxes that apply)				
<input type="checkbox"/> Grading and Base <input type="checkbox"/> Bituminous <input checked="" type="checkbox"/> <b>Concrete</b> <input type="checkbox"/> Aggregate <input type="checkbox"/> Materials/Chemicals				
Specialty	Exception Description	Resolution	Document Reference	Name/Initials
2461	3G52 Cylinder Strength Moving Average Failure	As per Spec 2461 Applied Standard Monetary Adjustment	Change Order 22	GB
2461	3G52 Cylinder Strength Test Greater than 500 PSI deficient (3900 PSI of 4500 PSI Required)	Structures Engineer Determined 3900 PSI is an Adequate Strength to Perform as Intended. Accepted as "Substantial Compliance"	Project File  OR  See attached Structures Engineers Recommendation	GB

# Initial Cure Temps 60° to 80° F



# 28-Day Cylinders

- **Initial Curing in the Field in Cold/Hot Weather**
  - If field office is nearby, transport sampled concrete to temperature controlled (60° to 80° F) field office and cast cylinders.
  - Begin casting within 15 minutes of obtaining concrete sample.
  - Place caps on molds after final finishing
  - Use insulated coolers with heated water
  - Use insulated coolers with water and/or ice.

# Concrete Sampling ASTM C172

- Changing Concrete Manual to ASTM C172 Sampling Requirements,
- Minimum Sample Size for Strength Testing is 1 Cubic Foot. Which is Around 145 Pounds of Concrete,
- Concrete Field Testers Need Wheelbarrows,
- Mix sample in wheelbarrow prior to performing tests.



# 28-Day Standard Strength Cylinders

- **Initial curing (Final finish up to 48 hours)**
  - An increase in compressive strength failures historically parallels increases in ambient and concrete temperature
  - The Contractor is required to supply whatever it takes to maintain the temperature between 60°F and 80°F.
  - Inspectors please ask for Initial cure environment(s) that will maintain the cylinders between 60°F & 80°F
  - Document requests for initial curing supplies


## Low 28-Day Strength Cylinders

- **Initial curing in the field (continued)**
  - **When outside ambient temps are between 60°F and 80°F, store cylinders in shaded area with mold covers affixed**



# Structural Concrete (2461) (2017) Special Provision & 2018 Spec Book

- The Contractor will,
  - For each separate (initial & Intermediate) curing environment, provide a calibrated waterproof digital temperature recording device that records the daily maximum and minimum ambient temperatures for the previous 7 days.
- The Engineer will,
  - Monitor the daily temperatures of the curing environments. Agency monitoring does not relieve the Contractor of the responsibility to maintain the water temperature as specified herein.





# Low 28-Day Strength Cylinders

- **Initial curing in the field (continued)**

- Options for cooling the cylinders include:
  - Have the Contractor supply insulated cooler(s),
  - Add chilled water, and
  - Add ice if needed during hot weather



# Transporting from Initial Curing Site

- For all grades of concrete Cure minimum 16 hours after casting
- Mass Concrete, cure minimum of 24 hours after casting.
- High Early Concrete, cure minimum of 12 hours after casting.



**Field Office Curing**

# Strength Test Results



## Concrete Cylinders Strength Test Report (ASTM C39)

Office of Materials and Road Research  
1400 Corvallis Avenue  
Maplewood, MN, 55109

CO-CY18-3189

Print Date: 1/8/2019

Project Number: [REDACTED]  
Billing Agency: [REDACTED]  
Project Eng.: [REDACTED]  
Inspector: [REDACTED]  
Bridge No.: [REDACTED]  
Part of Structure: Ret. wall  
Date Received: 12/12/18  
Source: [REDACTED]  
Mix Number: 3G52CF

**Cylinder Information**  
Field ID: 1006  
Date Made: 12/11/2018  
Days Cured in Field: 1  
Ticket Number: 4570156  
Air Content: 6.9 % (5.0% to 8.5% Req'd)  
Slump: 4 in. (2 to 5 in. Req'd)  
Air Temperature: 27 Degrees  
Concrete Temperature: 71 Degrees (50 to 90 Degrees Req'd)

Cylinder ID: 1006.1  
Date Tested: 1/8/2019  
Age: 28  
Fracture Type: Short Shear  
Comment:  
Avg. Dia. (in.): 4.00  
Area (sq. in.): 12.6  
Load (lbs): 39138  
Actual Strength (PSI): 3110  
Defects:

Cylinder ID: 1006.2  
Date Tested: 1/8/2019  
Age: 28  
Fracture Type: Long Shear  
Comment:  
Avg. Dia. (in.): 4.00  
Area (sq. in.): 12.6  
Load (lbs): 74649  
Actual Strength (PSI): 5940  
Defects:

Cylinder ID: 1006.3  
Date Tested: 1/8/2019  
Age: 28  
Fracture Type: Short Shear  
Comment:  
Avg. Dia. (in.): 4.00  
Area (sq. in.): 12.6  
Load (lbs): 51475  
Actual Strength (PSI): 4100  
Defects:

<b>Cylinder Strength Summary</b>	Req'd Strength Specification (psi):	4500
	28 day Strength Test (psi):	5940 See Note

Note: Adjusted Strength. All individual cylinder strengths that are more than 350 psi below the highest individual cylinder strength were removed from the average.

Comments:

Charge: 3 - 1072

Copies To

Curtis Kallio  
engineering@cemstone.com

Report Reviewed By:

*Pamela L. Ogden*  
Pamela L. Ogden

# Mn/DOT Concrete Cylinder Strength Test Report

## Wide Range Between Individual Cylinder Results



### Concrete Cylinders Strength Test Report (ASTM C39)

Office of Materials and Road Research  
1400 Gervais Avenue  
Maplewood, MN, 55109

CO-CY18-3189

Print Date: 1/8/2019

Project Number:	[REDACTED]	<b>Cylinder Information</b>
Billing Agency:	[REDACTED]	Field ID: 1006
Project Eng.:	[REDACTED]	Date Made: 12/11/2018
Inspector:	[REDACTED]	Days Cured in Field: 1
Bridge No.:	[REDACTED]	Ticket Number: 4570156
Part of Structure: Ret. wall		Air Content: 6.9 % (5.0% to 8.5% Req'd)
Date Received: 12/12/18		Slump: 4 in. (2 to 5 in. Req'd)
Source:	[REDACTED]	Air Temperature: 27 Degrees
Mix Number: 3G52CF		Concrete Temperature: 71 Degrees (50 to 90 Degrees Req'd)

Cylinder ID: 1006.1	Avg. Dia. (in.)	4.00	Load (lbs)	39138	<del>3110</del>
Date Tested: 1/8/2019	Area (sq. in.)	12.6	Actual Strength (PSI)	3110	
Age: 28	Defects:				
Fracture Type: Short Shear					
Comment:					

Cylinder ID: 1006.2	Avg. Dia. (in.)	4.00	Load (lbs)	74649	5940
Date Tested: 1/8/2019	Area (sq. in.)	12.6	Actual Strength (PSI)	5940	
Age: 28	Defects:				
Fracture Type: Long Shear					
Comment:					

Cylinder ID: 1006.3	Avg. Dia. (in.)	4.00	Load (lbs)	51475	<del>4100</del>
Date Tested: 1/8/2019	Area (sq. in.)	12.6	Actual Strength (PSI)	4100	
Age: 28	Defects:				
Fracture Type: Short Shear					
Comment:					

<b>Cylinder Strength Summary</b>	Req'd Strength Specification (psi):	4500
	28 day Strength Test (psi):	5940 See Note
		<b>5940</b>

Note: Adjusted Strength. All individual cylinder strengths that are more than 350 psi below the highest individual cylinder strength were removed from the average.

5940 - 350 = 5590 Plus

Average ~~4383~~

**Test Report will Remove Individual Results Greater than 350 PSI from the Highest Result of 5940 PSI**

Charge: 3 - 1072

Copies To

Curtis Kallio  
engineering@cemstone.com

Report Reviewed By:

*Pamela L. Ogden*  
Pamela L. Ogden

# Test Pours

- Self Consolidating Concrete / Self Compacting Concrete (SCC)
- Bridge Decks with High Performance Concrete (HPC)
- Colored Concrete

If the Concrete is going to be pumped to place the concrete into the newly constructed structures, pump the concrete on the test pour...

# When a SCC Test Pour goes Wrong



# Wall Infills using SCC




# Concrete Pavement Rehabilitation Guide

Concrete Repair - All Sections  
Created By Peter Johnson · Current Version

REVIEW FEEDBACK ... Sign In

Concrete Pavement Rehab test



**Concrete Pavement Rehabilitation Guide**

MnDOT Concrete Engineering Unit  
Gordy Bruhn and Maria Masten

**mi** DEPARTMENT OF TRANSPORTATION

021521

Completed by  
end of February  
2021



# Types of Pavement Repairs

Concrete Repair - All Sections  
Created By Peter Johnson · Current Version

REVIEW FEEDBACK Sign In


Concrete Pavement Rehab test

Read the Disclaimer Table of Contents

- 1** Repairs
- 2** Identifying Pavement Defects for Repair
- 3** Opening to Construction Equipment and Traffic
- 4** Repair Evaluation Period
- 5** Common Situations and Recommendations
- 6** Reference Documents (opens a new browser page)

Return to Title Page

PREV





[Read the Disclaimer](#)

## Repairs Menu


**1** Type A Repairs

**2** Type B Repairs

**3** Type C Repairs

**4** Dowel Bar Retrofit

**5** Concrete Grinding



[Return to Table of Contents](#)

# Saw & Seal (Type A1)

## Type A1 Repairs

## How to Perform Joint Repair Type A1

Click on a button to view that step

Type A1 repairs are incidental or paid by linear foot.

**Type A1 repairs are used in two different ways:**

1. Sawing and sealing new and re-established joints in Type B and Type C repairs.
2. When the agency wants freshly sawn joint faces prior to resealing the joints. This type of repair results in increasing the existing joint width.

1. Repair Details

5. Install a Backer Rod

2. Sawing

6. Fill with a Hot Pour Sealer

3. Joint Measurements

7. Measurement for Payment

4. Sandblast and Final Cleaning



### Concrete Unit Recommendation:

The purpose of sealing joints is to protect the repairs from water and to prevent the accumulation of incompressible debris such as sand and dirt.

Seal all concrete pavement repairs in accordance with the Saw and Seal Joint Repair (Type A1).

- Roadways  $\leq$  45mph, seal/reseal transverse and longitudinal joints in accordance with Saw and Seal Joint Repair (Type A1) repair detail, or the Clean and Seal Joint Repair (Type A2) repair detail.
- Roadways  $>$  45 mph, saw and sealing or clean and sealing joints outside of the full or partial depth repairs is not recommended.

However, it is recommended that the performance of the in-place joints be evaluated on a case by case basis. Contact the Concrete Engineering Unit to discuss further.

# Saw & Seal (Type A1) and Clean & Seal (Type A2)

Concrete Repair - All Sections  
Created By Peter Johnson · Current Version


REVIEW FEEDBACK Sign In

Concrete Pavement Rehab test


## Type A1 Repairs

### Sawing


Click on an image for a larger view.



Produce 2 freshly sawn faces no greater than 1/8" wider than the existing joint.



The Contractor needs to stack the blades to determine the correct width for the saw cut.



**Concrete Unit Recommendations**  
MnDOT discourages sawing and sealing random cracks due to the difficulty of widening as shown in the photo.

Return to A1 Sequence Slide 3 of 13

PREV NEXT



Concrete Repair - All Sections  
Created By Peter Johnson · Current Version

REVIEW FEEDBACK

Concrete Pavement Rehab test

## Type A2 Repairs

### Removing the In-Place Joint Sealant



Using a ripper tooth to remove in-place joint sealant on longitudinal joint

**Concrete Unit Recommendation**  
Contractor may use a ripper tooth or saws to remove the in-place joint sealant.


Return to A2 Sequence Slide 4 of 14



[Read the Disclaimer](#)

## Repairs Menu

- 1 Type A Repairs
- 2 Type B Repairs**
- 3 Type C Repairs
- 4 Dowel Bar Retrofit
- 5 Concrete Grinding



[Return to Table of Contents](#)



## Type B Repairs


## Boiler Plate

[Click to return to recommendations](#)



### Partial Depth Repair Type BA

- Spot repair of localized spalling
- Repair delaminated areas above reinforcing steel and dowel bars
- Measured by area



Type BA Repair

### Joint and Crack Repair Type B3

- Repair of joint spalling and transverse contraction joint tunneling
- Measured linearly



Type B3 Repair

### Partial Depth Repair Special Type BE

- Repair of localized bottom-up deteriorations
- Primarily found at intersecting longitudinal and transverse contraction joints and below longitudinal joints
- Always paid for in conjunction with a Type BA or B3 repair
- Measured by area



Type BE Repair

[Return to Repairs Menu](#)

# Spot Surface Repair (Type BA)

Concrete Repair - All Sections  
Created By Peter Johnson · Current Version

REVIEW FEEDBACK ... Sign In


Concrete Pavement Rehab test

## Type BA Repairs

### How to Perform Partial Depth Type BA Repairs

Click on a button to view that step

- Spot repair of localized spalling
- Repair delaminated areas above reinforcing steel and dowel bars
- Measured by area



1. Repair Details
2. Removals
3. Repair Preparation
4. Concrete Placement
5. Saw and Seal
6. Measurement for Payment

Return to Type B Repair Boilerplate Slide 1 of 26

< PREV NEXT >

# Joint Repair (Type B3)

Concrete Repair - All Sections  
Created By Peter Johnson · Current Version


REVIEW FEEDBACK Sign In

Concrete Pavement Rehab test

## Type B3 Repairs

### How to Perform Partial Depth Type B3 Repairs

- Repair of joint spalling and transverse contraction joint tunneling
- Measured linearly



Click on a button to view that step

1. Repair Details
2. Removals
3. Repair Preparation
4. Concrete Placement
5. Saw and Seal
6. Measurement for Payment

Return to Type B Bollerplates Slide 1 of 26

PREV NEXT



# Use Type BE Repair when a PDR Goes Full Depth

Concrete Repair - All Sections  
Created By Peter Johnson · Current Version


REVIEW FEEDBACK Sign In

Concrete Pavement Rehab test

## Type BE Repairs

### How to Perform Partial Depth Type BE Repairs

- Repair of localized bottom-up deteriorations
- Primarily found at intersecting longitudinal and transverse contraction joints and below longitudinal Joints
- Measured by area
- Always paid for in conjunction with a Type BA or B3 repair



Click on a button to view that step

1. Repair Details
2. Removal
3. Repair Preparation
4. Concrete Placement
5. Saw and Seal
6. Measurement for Payment

Return to Type B Repair Boilerplates Slide 1 of 29



[Read the Disclaimer](#)

## Repairs Menu


**1** Type A Repairs

**2** Type B Repairs

**3** Type C Repairs

**4** Dowel Bar Retrofit

**5** Concrete Grinding



[Return to Table of Contents](#)



## Type C Repairs

### Boiler Plate

Click to see the steps for each type repair.



#### Full Depth Repair Type CD-HV

- Provide load transfer to random transverse cracks
- Repair deteriorated transverse contraction and longitudinal joints (bottom-up deterioration.)
- Repair concrete pavement blowups
- Dowel bar diameter, 1.25 inch
- Measured linearly

#### Full Depth Repair Type CD-LV

- For low volume roadways ( $\leq 300$  trucks per day)
- Repair deteriorated contraction Joints (bottom-up deterioration)
- Repair concrete pavement blowups
- Dowels in wheel paths only
- Dowel bar diameter, 1 inch
- Measured linearly

#### Full Depth Repair Type C1-LV

- For low volume roadways ( $\leq 300$  trucks per day)
- Repair concrete drainage and utility structure castings
- Pavement removals for ADA improvements
- Repair deteriorated contraction Joints (bottom-up deterioration.)
- Repair concrete pavement blowups
- For load transfer use No. 8 epoxy coated reinforcement bars or 1-inch diameter dowel bars
- Measured by area (Square Foot)

#### Pavement Replacement Type CX

- Repair of crushed panels
- Repair of concrete pavement blowups which exceed 4 feet
- Remove and replace large sections of roadway that are in disrepair
- Must be used in conjunction with either Type CD-HV or Type CD-LV full depth repair
- May need to include other pay items associated with the Type CX Repair
  - Dowel Bars (each)
  - Drill & Grout Epoxy Coated Reinforcement Bars (each)
  - Epoxy Coated Supplemental Reinforcement Bars (pound)
- Measured by area (square yard)

Return to Repairs Menu



# Full Depth Joint Replacement Type CD-HV & Type CD-LV

Concrete Repair - All Sections  
Created By Peter Johnson · Current Version

REVIEW FEEDBACK Sign In

Concrete Pavement Rehab test

### Type CD-HV Repairs

### Repair Preparation

### Transverse Type CD Repair Bar Installation Locations

Click on an image for a larger view.

**Type CD-HV and Type CD-LV**  
Length of No. 4 Reinforcing Bar:  
 $X - 2$  ft  
Where X = repair width in feet

**Transverse Type CD-HV Repairs**  
Number of 18" x 1.25" dowel bars required:  $2 * (X - 1)$   
Where X = repair width in feet

Add an additional dowel bar per side for each 1 foot increase in lane width/ pay quantity

**Transverse Type CD-LV Repairs**  
Number of 18" x 1" dowel bars required: 3 dowel bars per wheel path

Return to Type CD-HV Sequence Slide 20 of 40

< PREV NEXT >

# Pavement Replacement Type CX Repair

Concrete Pavement Rehab test

## Type CX Repairs

- Repair of crushed panels
- Repair of concrete pavement blowups which exceed 4 feet
- Remove and replace large sections of roadway that are in disrepair
- Must be used in conjunction with either the FDR (Type CD-HV) or (Type CD-LV)
- May need to include other pay items associated with the Type CX Repair
  - Dowel Bars (each)
  - Drill & Grout Epoxy Coated Reinforcement Bars (each)
  - Epoxy Coated Supplemental Reinforcement Bars (pound)
- Measured by area (square yard)

## How to Perform Full Depth Type CX Repairs

Click on a button to view that step

1. Repair Details

2. Removals

3. Repair Preparation

4. Concrete Placement

5. Saw and Seal

6. Measurement for Payment



Return to Type C Repair Boilerplates Slide 1 of 44

### Concrete Unit Recommendations

All CPR projects should include either a Full Depth Repair Type CD-HV or Type CD-LV and Pavement Replacement Type CX.



# Type CX Repair



Concrete Repair - All Sections

Created By Peter Johnson · Current Version ▾

REVIEW

FEEDBACK

Sign In

Concrete Pavement Rehab test



## Type CX Repairs

## Repair Preparation – Install Dowel Bar Baskets – Square Joints



Click on an image for a larger view.

### Concrete Unit Recommendation

If lane removals are not equal, place dowel bar basket as shown.

Type CD-HV +Type CX Repair Installation of Dowel Bar Baskets

Install dowel bars adjacent to existing transverse contraction joints and parallel to the roadway centerline.



Type CD-HV +Type CX Repair Installation of Dowel Bar Baskets

# Thank you!

**Gordon “Gordy” Bruhn**

*[gordon.bruhn@state.mn.us](mailto:gordon.bruhn@state.mn.us)*

651-366-5523



## Concrete Paving and Maturity - Rob Golish



# 2020 Paving Projects

- Fly ash shortage
- Few projects that were driven on early
- Rain damaged concrete
- Everything considering, paving went well in 2020

# New Standard Plans

- 5-297.221 Construction Joints
  - Now includes – Construction and Terminal Headers
  - Joint depth for all concrete –  $T/3$
  - Basket 12” from centerline

# Dowel Bar Bond Breaker Material

- Require dowel bars and dowel baskets to be dipped in a waxy bond breaker material.



# Thickness Verification by Scanning (MIT-SCAN T2)

- ✓ **New Special Provision** used when constructing:
  - ✓ A concrete overlay of existing asphalt (Whitetopping)
  - ✓ Concrete placed directly on grade and the total cubic yard quantity for the project is >3,500 cubic yards
- ✓ **Not to be use on unbonded overlays**
  - ✓ Existing reinforcement and dowel baskets below the UBOL influenced the results



# Benefits of Using Maturity

- Reduce field control cylinders/beams
- Real-time and Continuous
- Effectiveness of Cold Weather Protection Plan
- Monitoring Temperature of Concrete
- Form Removal
- Sawing
- Opening to Traffic

# 2020 Maturity Projects

## Paving

- MnDOT's I-90 near Blue Earth (Croell)
- MnDOT's I-90 near Austin (Croell)
- Fillmore County's CSAH 1 (Croell)
- Goodhue County's CSAH 21 (Croell)
- MnDOT's I-35W MnPASS (Pci Roads)
- MnDOT's I-94 Albertville (Pci Roads)
- MnDOT's I-35W/Lake Street (Shafer Contracting)
- Rice County's CSAH 46 (Doyle Conner and Rochester Ready-Mix)
- Hennepin County's Minneapolis Reconstruction (Ti-Zack & Cemstone)
- City of Detroit Lake's South Washington (Strata Corporation)

## Bridges

- MnDOT's Jordan bridge deck (Cemstone)
- MnDOT's 3<sup>rd</sup> Avenue bridge deck (Cemstone)

# Maturity Method

Developing the maturity-strength relationship requires three steps:

## **Step 1 - Develop the maturity-strength curve**

Step 2 - Estimating the in-place strength

Step 3 - Validating the strength-maturity relationship

*Contractor/Producer responsible for  
all steps Maturity Process*

# Development of Maturity Curve Cast Strength Specimens



Maturity Curve can be built in Field or Lab



Embed the sensors in the center of the 2 additional beams or cylinders specimens




Cure specimens in a moist condition at a temp of range  $60^{\circ} - 80^{\circ} \text{ F}$





# Maturity Equipment Provided by Contractor/Producer



Maturity Readers




Data Loggers





# Development of Maturity Curve

- Strength test specimens at time specified in 2461



# Development of Maturity Curve

- Strength test specimens at time specified in 2461



# Maturity Method

Developing the maturity-strength relationship requires three steps:

**Step 1 - Develop the maturity-strength curve**

**Step 2 - Estimating the in-place strength**

Step 3 - Validating the strength-maturity relationship

*Contractor/Producer reads data and provides  
Engineer with data to determine if pavement can  
be opened/forms can be removed*

# Maturity Method

Developing the maturity-strength relationship requires three steps:

Step 1 - Develop the maturity-strength curve

Step 2 - Estimating the in-place strength

**Step 3 - Validate the maturity-curve**

*Contractor/Producer casts beams/cylinders to validate maturity cure*

# More info on Maturity Method

## Concrete Maturity

[Materials Home](#)

[Concrete Home](#)

[Contacts](#)

### Maturity

#### Introduction

- The maturity method is a non-destructive procedure used to estimate the strength of in-place concrete based on temperature history of the concrete.

#### Uses

- Predicting opening times to traffic, stripping forms, terminating cold weather protection are several uses for the maturity method.

#### Specification

- [Specification 2461.3.G.6, "Development of Maturity-Strength Relationship"](#)
- The updated special provisions will be posted in the near future

#### Procedures

- [Maturity method procedures](#)

#### Forms

[Concrete maturity workbook - beams \(revised 7/22/2019\)](#)

[Concrete maturity workbook - cylinders \(revised 9/2018\)](#)

#### Did you know

Maturity is an allowable method to determine development of concrete strength. See [Standard Specifications for Construction 2018](#), Specification 2461.3.G.6, "Estimating Concrete Strength by the Maturity Method."

Contact the Concrete Engineering Unit if a Contractor wants to use maturity on your project.

# Thank you!

**Rob Golish**

*Robert.golish@state.mn.us*

651-366-5576

# Concrete Ready-Mix – Brad Swenson and Matt Herbst




## *Brad Swenson*

Greater Minnesota Plant Coordinator  
Minnesota Department of Transportation  
Materials and Road Research  
1400 Gervais Avenue  
Maplewood, MN 55109  
218-232-1012 (cell)  
[bradley.s.swenson@state.mn.us](mailto:bradley.s.swenson@state.mn.us)



# 2020 Ready-Mix Plant Visits



# Positives of 2020

- Brad and Matt are continuing to build positive relationships with Industry and Agency
- Learning from errors (limited times the same mistake made twice by same person)
- Improvements (not 100%)
  - Submitting QC/QA workbooks on time
  - Filling out diary in QC workbook
  - Producers are complying with minimum testing requirements

**Lots of room for improvement yet!**

# Concrete Plant Refresher for Producers

- No Concrete plant monitor training this year.
- The aim of the training is to convey correct information and updates directly to people working at the concrete plants.
- Training currently proposed for spring of 2021
  - Options as an industry or by company (companies)
  - Virtual or in-person TBD


- JMF mix design for 3YHPC, Mass Concrete, SCC are project and plant specific
- This is not a new spec but one that has been missed many times
- Not approved for all projects after it is initially approved
  - Special Provisions could be different
- Passing gradation required before start of production for bridge decks

# Certificate of Compliance Issues

- OD weights do not match weights on the mix design
- Not having approved mix designs
- Incorrect absorptions
- Over on water content
- Using materials not on approved project specific mix design
- Moistures on Certificate of Compliance not matching the moisture test results
- Tolerances on aggregates/cement/admixtures (Target vs Actual)
- Missing S.P. or Bridge numbers

***“These issues were seen on signed certificates of compliance”***

# Certificate of Compliance Check

<b>Concrete Plant:</b>		ACME CONCRETE			 <p style="text-align: center; font-weight: bold; font-size: 1.2em;">Only enter data into shaded cells!</p>							
<b>S.P.:</b>		5555-1212										
<b>Date:</b>		7/11/2021										
<b>Time:</b>		6:30 AM										
<b>Ticket #:</b>		619619										
<b>Mix Type:</b>		3F52										
<b>Load Size:</b>		10.00		OD (lbs/CY) From Mix Design!					PER YD <sup>3</sup>			BATCH (lbs)
<b>Ingredient</b>	<b>Pit #</b>	<b>MCFac</b>	<b>Abs Fac</b>		<b>Abs</b>	<b>SSD</b>	<b>Free Moist</b>	<b>Target (CY)</b>	<b>Target Load</b>	<b>Actual</b>		
Sand	69004	0.046	0.011	1205	13.3	1218.3	42.2	1260.4	12604.3	12490	-0.91%	+/- 2%
CA 1	69004	0.038	0.012	1810	21.7	1831.7	47.1	1878.8	18787.8	18880	0.49%	+/- 2%
CA 2												+/- 2%
Cement				510					5100.0	5120	0.39%	+/- 1%
Fly Ash				90					900.0	910	1.11%	+/- 3%
Other CM												+/- 3%
Water				270.0						1645.0		+/- 1%
FM/YD <sup>3</sup> (Total of all Aggregate Free Moistures)					89.2				<b>Batched Cement</b>		5120	
FM Batch (Total FM/YD <sup>3</sup> X Load Size)					892.4				<b>Batched Fly Ash</b>		910	
Batch Water in lbs					1645.0				<b>Other Batched CM</b>		0	
<b>Total Water (Free + Batch)</b>					<b>2537.4</b>				<b>Total Cementitious</b>		<b>6030</b>	
Design Water Batch					2700.0				<b>Common Water Conversions</b>			
Total Water					2537.4				<b>GAL</b>	<b>32.4</b>	<b>LBS</b>	<b>270</b>
Water Available in lbs					162.7				<b>LBS</b>	<b>270</b>	<b>GAL</b>	<b>32.4</b>
<b>*Computed Water Available (GAL)</b>					<b>19.5</b>				<b>*Note:</b> Water Available is computed as taught in the MnDOT Concrete Plant Technical Certification course. Actual Batching systems may compute available water slightly different but should never compute more available water than what is shown on this worksheet.			
<b>Water Available on Cert of Compliance (GAL)</b>					<b>20</b>							
<b>Water added at Plant (GAL)</b>					<b>0</b>							
<b>Water added on Jobsite (GAL)</b>					<b>0</b>							
<b>Adjusted Water Available (GAL)</b>					<b>19.5</b>							
<b>Final W/C Ratio</b>					<b>0.421</b>							

- $\geq 20$  yards daily
- Every 4 hours
- Night before if no rain - starts at time of production even if it is private work
- Sample size weights should be more random





Minnesota Department of Transportation

TP 2152 (4/21/2020)

## Concrete Batching Report

Batch Plant: [REDACTED]

		Fine	Fine	Coarse	Coarse	Coarse	Coarse	Fine	Fine	Coarse	Coarse	Coarse	Coarse	Fine	Fine	Coarse	Coarse	Coarse	Coarse
Aggregate Size		sand		#67				sand		#67									
Pit #		■		■				■		■									
Date																			
Tester																			
A. Wt. Sample + Pan	Wet	591.6		2192				591		2192.3									
B. Wt. Sample + Pan	Dry	574.2		2155				573.8		2154.8									
C. Moisture Loss	A-B	17		37				17		38									
D. Tare Wt. Pan	-	0		0				0		0									
E. Dry Wt. Sample	B-D	574		2155				574		2155									
F. Total Moisture Factor	C/E	0.030		0.017				0.030		0.017									
G. Absorb. Factor	-	0.007		0.012				0.007		0.012									
H. Free Moisture Factor	F-G	0.023		0.005				0.023		0.005									
I. Time Scales Set		10:00						13:00											
<p>Highlighted results on Line F "Total Moisture Factor" must match MCFac column on the Certificate of Compliance unless a moisture probe has been approved on the contact report by the Concrete Engineer.</p>																			

# Minimum Sample Sizes

- Insufficient Sample Sizes
- MnDOT Schedule of Materials Control
  - Random sample sizes (grab a sample – approximate size not always the same exact the number)

<b>Minimum Sample Sizes:</b>	
<b>Gradation:</b>	<b>Moisture:</b>
3/4" Plus, #4: 30 lb.	Fine Aggregate: 500 g
3/4" Minus, #67: 10 lb.	Intermediate Aggregate: 500 g
#7, CA-70: 6 lb.	Coarse Aggregate: 2000 g
CIA, FIA: 1000 g	
CS, FS: 500 g	
#89, CA-80: 500 g	
Fine Aggregate: 500 g	
<b>Companion Required, Double Sample Sizes</b>	

# Minimum Sample Sizes



Minnesota Department of Transportation

TP 2152 (5/20/2020)

## Concrete Batching Report

Batch Plant: [REDACTED]

		Fine	Fine	Coarse	Coarse	Coarse	Coarse	Fine	Fine	Coarse	Coarse	Coarse	Coarse	Fine	Fine	Coarse	Coarse	Coarse	Coarse		
Aggregate Size			FA	#67				FA		#67											
Pit #			[REDACTED]	[REDACTED]				[REDACTED]		[REDACTED]											
Date		9/29/20							[REDACTED]												
Tester		[REDACTED]							[REDACTED]												
A. Wt. Sample + Pan	Wet	547.2		581.5				560.2		561.2											
B. Wt. Sample + Pan	Dry	522.6		574.2				541.1		556.1											
C. Moisture Loss	A-B	25		7				19		5											
D. Tare Wt. Pan	-	0		0				0		0											
E. Dry Wt. Sample	B-D	523		574				541		556											
F. Total Moisture Factor	C/E	0.047		0.013				0.035		0.009											
G. Absorb. Factor	-	0.003		0.005				0.003		0.005											
H. Free Moisture Factor	F-G	0.044		0.008				0.032		0.004											
I. Time Scales Set		7:00							12:00												
<p>Highlighted results on Line F "Total Moisture Factor" must match MCFac column on the Certificate of Compliance unless a moisture probe has been approved on the contact report by the Concrete Engineer.</p>																					

# Minimum Sample Sizes

Composite Gradation for: **#67**

Agg. Fractions	3/4-	5/8-		Composite	
Proportions	50 %	50 %	%	100%	Grad. Req.
1 1/4"	50	50		100	100
1"	50	50		100	100
3/4"	45	50		95	90-100
3/8"	23	17		40	20-55
#4	7	2		9	0-10

Washing Data for Sieve Analysis of Fine Aggregate

(A) Dry Sample and Record Weight	489.7
(B) Wash and Dry Sample, Record Weight	486.6
(C) Loss by Washing (A - B)	3.1

\* #6 and #200 not included in Fineness Modulus

\*\* Recommended filler sieve

Comments:	
-----------	--

Sieve Analysis of Fine Aggregate

Sieve Sizes	Test No.: QCF2		Sample Wt. (g): 489.7	
	Weights (g)		% Pass	Req.
Pass - Ret.	Ind.	Cum.		
3/8" - #4		488.9	100	100
#4 - #6		488.9	100	95 - 100
*#6 - #8	30.4	488.9	-	**
#8 - #16	144.8	458.5	94	80 - 100
#16 - #30	83.2	313.7	64	55 - 85
#30 - #50	147.4	230.5	47	30 - 60
#50 - #100	74.1	83.1	17	5 - 30
#100 - #200	5.8	9.0	2	0 - 10
*#200 - Btm	0.1	3.2	0.7	0 - 2.5
Loss by Washing	3.1			
Check Total	488.9	± 0.3 % of Sample Wt		488.2 - 491.2
Fineness Modulus	Within + 0.20		2.76	2.68

# Overloaded Sieves



Minnesota Department of Transportation

## Concrete Aggregate Worksheet

S.P.:	Plant:
Engineer:	Tester:

Agg. Fractions	CA: #67	Mix Prop.: 100	%
Sieve Sizes	Test No.:	Sample Wt. (lb):	40.4
Pass - Ret.	Ind.	Cum.	% Pass
1 1/4" - 1"		40.2	100
1" - 3/4"	2.5	40.2	100
3/4" - 5/8"	6.0	37.8	94
5/8" - 1/2"	8.6	31.8	-
1/2" - 3/8"	9.4	23.3	58
3/8" - 1/4"	10.1	13.9	34
1/4" - #4	2.4	3.8	-
#4 - Btm	1.4	1.4	3
Check Total	40.2	± 0.2 lb of Sample Wt	40.2 - 40.6

MAXIMUM ALLOWABLE QUANTITY OF MATERIAL RETAINED ON A SIEVE  
References from ASSHTO T 27 - 97<sup>1</sup> and/or Mn/DOT Standards  
{+ #4 Sieve Quantities interpolated by this formula = [(2.5) x (Sieve opening, mm) x (Sieving Area, M2)] }

Nominal Dimensions of Sieve	203mm	8"	305mm	12"	305mm x 305mm	12"x12"	360mm x 360mm	14"x14"	400mm x 400mm	16"x16"	368mm x 572mm	14.5 x 22.5
Sieving Area m <sup>2</sup>	.02850		.06701		.09290		.12645		.16516		.21048	
	kg	lbs	kg	lbs	kg	lbs	kg	lbs	kg	lbs	kg	lbs
In. Mm												
4 100	-	-	-	-	23.23	-	-	-	-	-	-	-
3 1/2 88	-	-	15.08	33.2	20.90	-	-	-	-	-	-	-
3 75	-	-	12.56	27.7	17.42	-	-	-	-	-	39.47	87.0
2 1/2 63	-	-	10.55	23.3	14.63	-	-	-	-	-	31.15	69.4
2 50	1.56	7.8	8.38	18.5	11.61	25.5	15.79	34.8	20.59	45.4	26.31	58.0
1 1/2 37.5	2.67	5.9	6.28	13.8	8.71	19.2	11.84	26.1	15.47	34.1	19.73	43.5
1 1/4 31.5	2.24	5.6	5.28	12.6	7.32	16.1	9.96	21.9	13.01	28.6	16.58	36.5
1 25	1.78	3.9	4.19	9.2	5.81	12.8	7.89	17.4	10.30	22.7	13.15	29.0
3/4 19	1.35	3.0	3.18	7.0	4.41	9.7	5.99	13.2	7.85	17.3	10.00	22.0
5/8 16	1.14	2.5	2.68	5.9	3.72	8.2	5.06	11.2	6.61	14.6	8.42	18.6
1/2 12.5	0.89	2.0	2.09	4.6	2.90	6.4	3.95	8.7	5.17	11.4	6.57	14.5
3/8 9.5	0.67	1.5	1.59	3.5	2.21	4.9	2.99	6.6	3.90	8.6	5.00	11.0
1/4 6.35	0.45	1.0	1.06	2.3	1.47	3.3	2.01	4.4	2.6	5.8	3.34	7.4
4 4.75	0.33	0.7	0.80	1.8	1.10	2.4	1.50	3.3	1.95	4.3	2.50	5.5

# Screen Sizes



14" X 14"




14.5" X 22.5"

# Overloaded Sieves

Composite	Grad. Req.	Sieve Analysis of Fine Aggregate				
100%		Test No.:	4F		Sample Wt. (g):	812.4
		Sieve Sizes	Weights (g)		% Pass	Req.
		Pass - Ret.	Ind.	Cum.		
		3/8" - #4	22.1	812.5	100	100
		#4 - #6	0.0	790.4	97	95 - 100
		*#6 - #8	88.8	790.4	-	**
		#8 - #16	153.3	701.6	86	80 - 100
		#16 - #30	220.9	548.3	67	55 - 85
		#30 - #50	202.0	327.4	40	30 - 60
		#50 - #100	110.8	125.4	15	5 - 30
		#100 - #200	13.1	14.6	2	0 - 10
		*#200 - Btm	1.5	1.5	0.2	0 - 2.5
		Loss by Washing	0.0			
		Check Total	812.5	± 0.3% of Sample Wt		810.0 - 814.9
		Fineness Modulus	Within ± 0.20		2.93	2.85
of Fine Aggregate		812.4				
		812.4				
		0.0				
		** Recommended filler sieve				

# Stockpile Issues





# Contact Report

TP-2163 (revised 12/11/20)

**m DOT Minnesota Department of Transportation**

## Contact Report - Ready Mix 2021

Plant Name:  M #:   
Address:  Date:   
 Phone:   
Batch Person:  Plant Email:   
Test results Email:  Has the Test Results email address changed?

Prior to the production of Department concrete **each construction season**, a Department Representative shall perform a thorough on-site inspection of the concrete plant with a MnDOT Certified Plant Technician, Quality Control Supervisor or Quality Control Manager representing the Producer. Display the Contact Report and site map in plain site at all times.

MnDOT Certified Plant Technician:  Cert#:  Phone#:   
MnDOT Certified Plant Technician:  Cert#:  Phone#:   
MnDOT Certified Plant Technician:  Cert#:  Phone#:   
MnDOT Certified Plant Technician:  Cert#:  Phone#:   
MnDOT Certified Plant Quality Control Supervisor:  Cert#:  Phone#:   
MnDOT Certified Plant Quality Control Manager:  Cert#:  Phone#:

Agency verifies the cementitious and admixture samples are documented in the current year electronic Sample Log.

Agency Representative:  Agency:   
 Cell #:   
 Approved Date:  Cert #:   
 Not approved for the following reason(s): 

Final Certification of the plant will be posted on the Concrete Unit website.

**Agency Inspection**

Re-inspected and approved on  by

A MnDOT Certified Plant Technician, Quality Control Supervisor or Quality Control Manager, representing the Producer, signs the report certifying compliance with the Certified Ready Mix requirements and continual maintenance of the plant to assure that the plant can

**Page 1**

Contact Report - Ready Mix Addendum Ready-Mix Paving

- Updated the Water Section to include Clarified Water
- Listed filler sieves to prevent overloading
- Added the Paving Addendum

# MnDOT Audit Investigations

- Biggest concern identified by Audit is lack of communication from Plant Monitors
  - Not relaying non-compliance issues to the Engineer
- Inexperience (both Agency and Consultants)
- Increasing compliance but room for improvement

# MnDOT Audit Investigations

- Focused on ready-mix plant operations and QC personnel along with Agency Plant Monitoring
  - Falsification of Test Results – repeated starting weights
  - Knowingly using non-compliant material
  - Unqualified Personnel (does not mean non-certified)
  - Repeated Incomplete Documentation
  - Moistures in QC workbook not matching Certificate of Compliance.

## 2461.3.F.5 Agency Quality Assurance (QA)

- (10) *If any equipment malfunctions, testing procedures or test results are questionable, or unusual activity is occurring during the plant visit perform the following:*
- (a) Continue monitoring at the plant and document observations in the diary.*
  - (b) Investigate to determine the origin of the concern and document the resolution.*
  - (c) Contact Independent Assurance Inspector, Project Engineer or Concrete Engineering Unit when necessary.*

# Non-compliance with Certified Ready-Mix Plant Program

If the Engineer observes the Producer not complying with the requirements of the Certified Ready-Mix Plant Program, the Engineer will perform the following:

- (1) Verbally notify and promptly email the Producer and the Concrete Engineer the list of observed deficiencies and provide a deadline to correct the non-compliance.

# Non-compliance with Certified Ready-Mix Plant Program (cont.)

(2) If non-compliance is not corrected by the deadline, notify the Contractor and Producer that concrete production is unauthorized in accordance with 1512, “Unacceptable and Unauthorized Work.”

The Concrete Engineer will determine if the severity of the non-compliance results in decertification of the plant in accordance with 2461.3.F.1.c, “Certified Ready-Mix Plant Decertification.”

# Non-compliance with Certified Ready-Mix Plant Program

- MnDOT Concrete Unit is requesting Producer to explain in writing why it happened and what action will be taken to prevent reoccurrence
- Ask IA for assistance if procedural issue
- Call Matt or Brad at the Concrete Office if issues persist

# Consequences of Non-Compliance

- Additional MnDOT Audit
- Removal of Federal Funds from a Project
- Decertification of Ready-Mix Plant
- Suspension or Revocation of Tech Certification
- Prosecution for fraud



# Certified Ready-Mix Decertification

The Concrete Engineer, with coordination from the Engineer, may decertify the plant and halt production of concrete under any of the following conditions:

- 1) Unauthorized procedural, material, or equipment changes made after the completion of the Concrete Plant Contact Report,
- 2) Failure to meet the required testing rates,
- 3) Failure to complete required documents,

# Certified Ready-Mix Decertification (cont.)

The Concrete Engineer, with coordination from the Engineer, may decertify the plant and halt production of concrete under any of the following conditions:

- 4) Failure to provide competent MnDOT Certified Plant Technicians,
- 5) Disregard of any of the requirements of 2461.3.F, Certified Ready-Mix Concrete, or
- 6) Falsification of test records or certificates of compliance.

# 2020 Special Provision Changes to 2018 Schedule of Materials Control

Incorporated Into 2019 & 2020 & 2021 Projects

# Schedule of Materials Control Changes

- Revised Plant Testing Rates
  - Effective in Contracts let March 22, 2019 and later
  - Gradation rates based on daily CY for JMF & Bridge
  - Gradation rates based on weekly CY for all other concrete
  - Eliminated 1 per 2 days, 2 per 3 or more days
  - Typically QA will test 1 QA (QC Split) and 1 Agency Verification each week

# 3131 - Intermediate Aggregate Requirements

- Quality

- Provide CIA in accordance with 3137.
- Provide FIA, CS and FS in accordance with 3126.

- Gradation

- Intermediate aggregates do not have individual sieve gradation requirements, they will be combined with another aggregate.

- Intermediate Aggregate Test Methods

- When proportioning CIA with a coarse aggregate to meet the specified limits of ASTM #67 gradation, sample and test CIA in accordance with Table 3137-6 using a minimum sample size equivalent to CA-70 per the Schedule of Materials Control. Sample and test all other CIA intermediate aggregates in accordance with Table 3126-5.
- Sample and test FIA, CS and FS in accordance with Table 3126-5.

# Quality Control Personnel

The Producer will provide the following personnel:

- QC Plant Technician(s) to perform all testing and quality control requirements of 2461.

**Plant Certified**

- Quality Control Supervisor responsible for oversight of all QC testing and is required to remain on-site during concrete production or have cellular phone availability.

**Plant Certified**

- Quality Control Manager responsible for oversight of the Quality Control Supervisor and the certified ready-mix plant program.

<http://www.dot.state.mn.us/const/tcp/>

# Provisional Testers Using QC Workbook

- MnDOT will allow provisional testers to work in the Concrete Ready-Mix Plant QC Workbook
  - Provisional Testers can't sign Certificate of Compliance
- New 2461.3.F.4.e Language:
  - *The Producer's designated QC Supervisor will review and submit to the Engineer and the Concrete Engineering Unit by the Tuesday immediately following the previous week's production.*

# Agency Aggregate Gradation Results

- Spec 2461.3.F.4.d Aggregate Gradation Control Charts and Sample Log
  - Removed requirement for Producer to record any Agency gradation results (Verification or QA Gradation) in QC Workbook or Chart



# Concrete Ready-Mix Plant QA Workbook

*The Engineer will complete the Concrete Ready-Mix Plant QA Workbook in real time which includes all of the following documents:*

- (1) Diary*
- (2) Weekly Certified Ready-Mix Plant Report*
- (3) Concrete Aggregate Worksheet if gradation testing performed in the field*
- (4) JMF Concrete Aggregate Worksheet if gradation testing performed in the field*

*Submit to the Engineer and the Concrete Engineering Unit by the Thursday immediately following the previous week's production.*

# Thank you!

**Matt Herbst**

*matthew.herbst@state.mn.us*

651-366-5423

Thanks!

Questions?

